

TECHNICAL MEMORANDUM DEWATERING/BARRIER WALL ALIGNMENT INVESTIGATION REPORT

AMERICAN CHEMICAL SERVICE, INC. NPL SITE GRIFFITH, INDIANA

PREPARED FOR:
ACS RD/RA EXECUTIVE COMMITTEE

PREPARED BY:
MONTGOMERY WATSON
ADDISON, ILLINOIS

MARCH 1996



TECHNICAL MEMORANDUM DEWATERING/BARRIER WALL ALIGNMENT INVESTIGATION REPORT

AMERICAN CHEMICAL SERVICE, INC. NPL SITE GRIFFITH, INDIANA

PREPARED FOR: ACS RD/RA EXECUTIVE COMMITTEE

PREPARED BY:
MONTGOMERY WATSON
ADDISON, ILLINOIS

MARCH 1996

CRA

CONESTOGA-ROVERS & ASSOCIATES

1801 Old Highway 8, Suite 114 St. Paul, Minnesota 55112

(812) 639-0913

Fax:(612) 839-0923

March 29, 1996

Reference No. 3481

Ms. Sheri Bianchin
UNITED STATES ENVIRONMENTAL
PROTECTION AGENCY (USEPA)
Region V (HSRL-6J)
77 West Jackson Boulevard
Chicago, Illinois 60604-3590

Dear Ms. Bianchin:

Re: Technical Memorandum - Dewatering/
Barrier Wall Alignment Investigation Report - ACS

Please find enclosed a copy of the Technical Memorandum for the Dewatering/Barrier Wall Alignment Investigation. Please note the schedule in Table 4 which shows that we hope to complete the construction of the barrier wall this year. In order to meet this schedule, we will need comments on this document, as well as the 50% and 100% Design submittals.

We look forward to discussing the results of this investigation with you. Please feel free to contact us with any questions you may have.

Sincerely,

CONESTOGA-ROVERS & ASSOCIATES

Ronald Frehner

RF/br Enc.

c.c. Holly Grejda; IDEM

Steve Mrkvicka/Rob Lantz; Black & Veatch

Steve Magnion; USEPA ACS Technical Committee

TABLE OF CONTENTS

1

*	
INTRODUCTION	
2	
PROCEDURES	
2.1 Drilling	
SAMPLE ANALYSIS	5
3.3 Analytical Laboratory Analysis	6
3.4 Geotechnical Laboratory Analysis4	6
	_
BARRIER WALL	
4.1 Proposed Final Alignment	
4.2.1 North Alignment	
4.2.2 West Alignment	
4.2.3 Rail Spur Area	
4.2.4 Additional Borings - Proposed Final Alignment	
4.3 Off-Site Containment Area	10

CROSS SECTIONS OF PROPOSED FINAL ALIGNMENT	11
6	
ANALYTICAL RESULTS ALONG PROPOSED FINAL ALIGNMENT	12
7	
GEOTECHNICAL RESULTS8	14
PILOT TEST CELL BORINGS	15
9	
SCHEDULE FOR BARRIER WALL CONSTRUCTION	16

LIST OF TABLES

Table 1	Soil Boring Location and Elevation Information
Table 2	Summary of Soil Borings and Sample Analysis Conducted Along the Final Barrier Wall Alignment
Table 3	Geotechnical Laboratory Results Summary
Table 4	Schedule for Barrier Wall Construction

LIST OF FIGURES

Figure 1	Soil Boring Location Map
Figure 2	Barrier Wall Alignment Location Map
Figure 3	Cross Section Location Map
Figure 4	Cross Section A-A' and B-B'
Figure 5	Cross Section C-C'
Figure 6	Pilot Test Cells Soil Boring Location Map
Figure 7	Barrier Wall Alignment and Utility Location Map

LIST OF APPENDICES

Appendix A	Area Survey Report
Appendix B1 Appendix B2 Appendix B3	Soil Boring Logs – Proposed Final Alignment Pilot Test Cell Soil Boring Logs Remaining Soil Boring Logs
Appendix C	Field PCB Results (Ohmicron Environmental Diagnostics Rapid Assay Soil Test)
Appendix D	Field GC Results - VOCs
Appendix E	IEA Analytical Laboratory Results
Appendix F	Geotechnical Laboratory Results

J:\4077\0075\TOC_APP.DOC

INTRODUCTION

1.1 OBJECTIVES

This Technical Memorandum summarizes the results of investigation activities conducted to delineate the alignment and support the design of the dewatering/barrier wall at the ACS NPL site in Griffith, Indiana. The purpose of the dewatering/barrier wall is to prevent migration of contaminants from the Still Bottoms/Treatment Lagoon and Off-Site Containment Area (OSCA) to the site boundary. The dewatering/barrier wall investigation was performed in accordance with the January 12, 1996 Dewatering/Barrier Wall Alignment Pre-Design Work Plan approved by U.S. EPA and IDEM. It was originally proposed to install two separate barrier walls, one for the Still Bottoms/Treatment Lagoon Area, the other for the Off-Site Containment Area. Data were collected and evaluated for the investigation to accomplish the following objectives:

- Determine the lateral extent of waste materials at the locations where the barrier wall alignment is proposed. (According to the ROD, wastes are classified as soils with total VOC concentrations of 10,000 ppm (1 percent) or greater, and/or PCB concentrations of 10 ppm or greater.)
- Collect field and laboratory geotechnical information to support the design and construction of the barrier wall.
- Define the elevation of the top of the clay confining layer along the barrier wall alignment.
- Collect soil samples for potential mix design testing of a soil-bentonite barrier wall.
- Collect groundwater samples for potential compatibility testing of the proposed barrier wall.
- Provide sufficient information regarding site conditions to barrier wall subcontractors intending to propose and bid on barrier wall technology and design.

Samples of soil and groundwater were collected for soil-bentonite wall mix and compatibility testing. The soil-bentonite design and compatibility testing will be performed by the barrier wall subcontractor during barrier wall final design if a soil-bentonite mix design as needed to complete the technology selection process.

1.2 SCOPE OF WORK

Field investigations for the barrier wall alignment generally consisted of drilling soil borings extending to the underlying clay confining layer along the proposed alignment of the barrier walls, and assessing the presence of waste materials through visual inspections and field and laboratory analyses of selected soil samples. If material was found that met or exceeded the criteria for "waste", additional borings were conducted outward from the waste area to determine the extent of waste materials.

Field analysis of soil samples consisted of using field test kits for analysis of PCBs, a field gas chromatograph (GC) for analysis of total VOCs (defined as the sum total of the concentrations of detected target VOCs), and hydrophobic dye to test for the presence of free-phase materials. Duplicate soil samples were submitted to the laboratory for analysis when field analysis indicated VOC concentrations greater than 8,000 ppm or PCB concentrations approaching or exceeding 10 ppm.

Representative soil samples for geotechnical analyses were collected from borings located along the barrier wall final alignment and submitted to the laboratory for grain size analysis and hydraulic conductivity/permeability testing.

Soil borings were drilled during the barrier wall investigation to gather geotechnical information to design Pilot Test Cells in the Still Bottoms/Treatment Lagoon Area and the Off-Site Containment Area. Information gathered during the test cell soil borings included standard penetration testing, field soil classification and the depth to the clay confining layer. Field and laboratory analyses were not performed on soil samples collected from these areas.

PROCEDURES

2.1 DRILLING

A total of 23 soil borings were advanced in the Off-Site Containment Area (SB201 through SB223) and 48 soil borings were drilled in Still Bottoms/Treatment Lagoon Area (SB101 through SB144 and SB149 through SB152). The locations of the soil borings are shown in Figure 1. Soil boring location coordinates, ground surface elevations, and depth to the clay confining layer are presented in Table 1. Work was conducted following the SOW and SOPs approved by the U.S. EPA on January 12, 1996.

The intervals between soil boring locations ranged from 25 feet in the area south of the fire pond area to approximately 200 feet along the eastern perimeter (Figure 1). In general, locations were more closely spaced in areas where detailed information was required regarding the extent of waste materials. Ground surface elevations, and northing and easting coordinates were surveyed to the nearest 0.1 foot for each boring by Area Survey of Orland Park, Illinois. The survey report for the barrier wall investigation is presented in Appendix A.

Soil borings were advanced approximately two feet into the top of the clay confining layer and logged by a geologist at both areas of the site. The depth to clay and elevation of the top of clay for all soil boring locations are also included in Table 1. The elevation of the top of the clay confining layer ranged from approximately 617 feet to 622 mean sea level (msl) feet throughout the site area. Soil boring logs for borings located along the proposed final alignment are presented in Appendix B1. Pilot test cell soil borings are presented in Appendix B2. Remaining soil boring logs (borings not along the final alignment) are presented in Appendix B3.

Two drilling rigs were utilized concurrently to advance soil borings in the Still Bottoms/Treatment Lagoon Area and Off-Site Containment Area during the field investigation. An all-terrain vehicle (ATV) mounted drill rig was used to access the soil borings in the Off-Site Containment Area, whereas a truck-mounted rig was used in the Still Bottoms/Treatment Lagoon Area. All borings were drilled with 3.25-inch inside diameter (I.D.) hollow stem augers. Following completion of the borings, the boreholes were backfilled to the ground surface using a bentonite-cement grout. Soil boring locations were subsequently surveyed by Area Survey (Appendix A).

Soil boring and sample collection were conducted in accordance with the U.S. EPA and IDEM approved, January 12, 1996 Dewatering/Barrier Wall Alignment Pre-Design Work Plan and the Specific Operating Procedure (SOP) for drilling and soil sampling, with the following exceptions:

- Soil borings SB109 through SB113, SB134 through SB136, and SB150 through SB152 in the Still Bottoms/Treatment Lagoon Area and borings SB206, SB212, SB215, SB217, and SB221 in the Off-Site Containment Area were continuously sampled (i.e., 1 to 3 ft, 3 to 5 ft, etc.) to the bottom of each boring in order to collect additional soil volume for geotechnical laboratory analyses.
- Pilot test cell borings SB145 through SB148 in the Still Bottoms/Treatment Lagoon Area, and borings SB224 through SB227 in the Off-Site Containment Area, were allowed to cave-in naturally for borehole backfill as opposed to the bentonite cement grout used for the remainder of the barrier wall alignment borings. This was conducted with concurrence from the EPA field representative. The cave-in technique was used due to the large void spaces present within the formation which made grouting with bentonite impractical.

2.2 SAMPLE COLLECTION

Soil samples were collected from borings for field and laboratory analyses. Samples were collected in the field according to the following strategy outlined in the Dewatering/Barrier Wall Alignment Pre-Design Work Plan:

- One to two soil samples per boring were collected based on visual observations, (i.e., black or brown staining, presence of free phase material) for PCB field screening using an Ohmicron Environmental Diagnostics Rapid Assay Soil Test.
- One to two soil samples per boring were selected based on visual observations and PID readings for VOC analyses with the field GC.
- One soil sample per boring, located at the interface of the sand and clay confining layer, was collected and analyzed for the presence of free phase material utilizing the hydrophobic dye testing technique.
- Four 30-inch long, 3-inch diameter Shelby tube samples were collected from the areas (two from the Off-Site Containment Area and two from the Still Bottoms/Treatment Lagoon Area). The Shelby tube samples were collected from borings located along the proposed final alignment and one sample from each Shelby tube was analyzed for permeability using the falling head method.
- Twenty-two soil samples (from 11 borings) were collected along the proposed final alignment and analyzed for grain size distribution (ASTM D422).

SAMPLE ANALYSIS

3.1 PCB ANALYSIS

Soil samples were analyzed for PCB field screening using the Ohmicron Environmental Diagnostics Rapid Assay Soil Test according to the User's Guide presented in the approved Dewatering/Barrier Wall Alignment Pre-Design Work Plan. Montgomery Watson field personnel were trained in the use and application of the method by an Ohmicron representative prior to starting the sampling analysis. The following exceptions occurred to the Work Plan:

- A dilution of five was used in Step 46 of the flow diagram (provided in the Barrier Wall Investigation Work Plan) rather than a dilution of twenty. The one to five dilution was used to achieve the 10 ppm cutoff (waste criteria) for PCBs in soil.
- No soil samples were selected for field PCB analysis from soil boring SB201 due to auger refusal at a depth of 8 ft (See boring log for SB201 in Appendix B1). Soil boring SB210 was used as a replacement for SB201.

Field screening results from the soil samples and proficiency samples analyzed are presented in Appendix C.

3.2 FIELD GC ANALYSIS

Soil samples were analyzed for target VOCs using the field GC in accordance with the approved SOP with the following exceptions:

- Due to the high concentration of target VOCs in the soils, samples were run at a
 five-to-one dilution. Detection limits are subsequently five-times higher than the
 proposed limits.
- No soil samples were analyzed for VOCs from soil boring SB201 due to auger refusal at a depth of 8 ft (See boring log for SB201 in Appendix B2).). Soil boring SB210 was used as a replacement for SB201.

Tabulated field GC screening results from each sample analyzed are presented in Appendix D.

3.3 LABORATORY ANALYSIS

Soil samples which indicated VOC concentration greater than 8,000 ppm from the field GC analytical results, or PCB concentrations close to 10 ppm from the Ohmicron Rapid Assay Soil Field Test kit were sent to IEA Analytical Laboratories in Cary, North Carolina for confirmatory analyses in accordance with the Contract Laboratory Program (CLP) Statement of Work.

A summary of the analytical laboratory results and comparison to the field GC and PCB test kits are presented in Table 2. The complete IEA Laboratory report is presented in Appendix E.

3.4 GEOTECHNICAL LABORATORY ANALYSIS

Geotechnical laboratory analysis performed at CGC, Inc. of Madison, Wisconsin included grain size distribution (ASTM D422) for granular, Atterberg limits (liquid limit and plasticity index) (ASTM D4318), grain size distribution (ASTM D422), and falling head permeabilities using the U.S. Army Corps of Engineers Method EM 1110-2-1906 (VII) for samples from the clay confining layer.

Geotechnical laboratory testing for the soil-bentonite mix design and compatibility testing was not performed at this time. As previously stated, these tests will be performed by our construction subcontractor, as necessary, to select a soil-bentonite mix for sections of the barrier wall to be constructed as a bentonite slurry wall.

Geotechnical analyses of selected soil samples were conducted in accordance with the Dewatering/Barrier Wall Alignment Pre-Design Work Plan, with the following exceptions:

- Soil samples collected for grain size analysis along the proposed final alignment were analyzed at intervals greater than 200 feet. Because the original 200-foot spacing of soil samples for grain size analysis was based on a shorter length of alignment, increasing the proposed alignment length served to extend the distance between samples. Due to the consistent geology over the entire site, little variation in grain size was noted between borings located more than 200 feet apart (see Section 7). Soil samples were collected from all borings conducted during the investigation and are currently being stored. These soil samples will be available for additional grain size analyses in the future, if necessary.
- Due to the low conductivity of the clay, the results of the flexible-wall hydraulic conductivity/permeability tests (ASTM D5084) are not available at this time. The results will be submitted to the U.S. EPA under separate cover on April 19, 1996.
- In addition to the flexible-wall hydraulic conductivity/permeability testing, rigid-wall falling head permeability testing (U.S. Army Corps of Engineers Method EM

1110-2-1906 (VII)) was performed on the four Shelby tube samples. The U.S. Army Cops rigid wall falling head permeability test method was performed in order to model the worse case existing soil conditions of the clay confining layer at ACS.

BARRIER WALL ALIGNMENT

4.1 PROPOSED FINAL ALIGNMENT

The proposed final alignment of the Dewatering/Barrier Wall is presented in Figure 2. The objective of the field investigation was to evaluate the suitability of the proposed barrier wall alignments. The approved Work Plan included a method to move the barrier wall alignment outward at locations where waste conditions were identified in the subsurface. Therefore, the final wall alignment was based on the preliminary estimate of location, modified by the field and laboratory analysis of soil samples for VOCs and PCBs.

4.2 STILL BOTTOMS/TREATMENT LAGOON

4.2.1 North Alignment

PCBs were detected greater than 10 ppm in soil borings SB112 and SB125 by field screening tests (Appendix C). This required the proposed alignment to be moved outward, further to the north. Soil borings SB127 and SB142 were advanced to the north of SB112 and SB125, respectively. No exceedences of waste criteria for PCBs (10 ppm) or total VOCs (10,000 ppm) were observed in soil samples analyzed in the field from soil boring SB142.

Field screening for PCBs in a soil sample collected from SB127 at a depth of 6 to 8 ft did not indicate an exceedence of the waste criteria (8.5 ppm). However, a duplicate sample sent to IEA for confirmatory analyses indicated a total PCB concentration of 44 ppm. The next deeper zone, from the 8 to 10 foot depth was also field-tested for PCBs but none were detected. On the basis of all the sampling results along the north alignment, the PCB exceedance at SB127 is considered a localized condition. Furthermore, there is an above ground liquid nitrogen storage tank and several other tanks located just to the north of the SB127 so it is not feasible to move the alignment north around a localized area. The soil cuttings generated during any excavation for barrier wall construction in the vicinity of SB127 will be managed stored on site for future remediation.

4.2.2 West Alignment

Exceedences of PCBs (>10 ppm) were found in soil samples collected from soil borings SB122 and SB137, requiring the west portion of the alignment to be moved further to the west. PCBs were not detected greater than the waste criteria in soil samples collected from soil boring SB141, located approximately 26 ft west of soil boring SB137 (Figure 1).

Therefore, the final alignment was oriented through this boring location. Additional soil samples collected along the revised alignment soil borings (SB140, SB136, SB139 and SB131) did not indicate PCB concentrations greater than 10 ppm.

4.2.3 Railroad Spur Area

Soil borings advanced at 25-foot intervals along the railroad spur indicated potential exceedences of PCBs with field screening (>10ppm) in soil samples collected from soil borings SB101, SB103, SB105, SB107, and SB108. These potential exceedences required that the southern section of the proposed barrier wall be moved further south. Soil boring SB120 was advanced approximately 100 feet south of soil boring SB105, near a building located immediately south of the railroad spur (Figure 1). Because PCBs were detected in SB120 greater than 50 ppm with field screening, the final alignment was moved further south.

A new potential alignment, 50 feet farther to the south from SB120, was selected for sampling and proposed to U.S. EPA. U.S. EPA approved the revised location, and a series of borings (SB129 through SB135) were made along the fence line marking the south boundary of the ACS facility (Figures 1 and 2). Field screening results suggested PCBs were present in soil borings SB129, SB134 and SB135 greater than 10 ppm, and positive results from the hydrophobic dye test were noted in soil samples collected at the sand/clay confining layer interface in soil boring SB134 (19 to 21 ft). The positive dye test results indicated the presence of free phase material at these locations.

Soil boring SB138 was advanced south of soil boring SB134, near the fence boundary of the ACS facility. PCBs were detected with field screening at 26.8 ppm in the 18.5 to 20.5 ft sample interval, indicating an exceedance of the "waste" criteria. The hydrophobic dye test from the same interval also indicated the presence of free phase material in this sample.

4.2.4 Additional Soil Borings - Proposed Final Alignment

The results of borings SB129 through SB135, and SB138 suggested that oil and PCB containing soil extended at least to the south ACS property line. Therefore, Montgomery Watson proposed to the U.S. EPA that borings be conducted for the consideration of connecting the two barrier walls into a single wall encompassing both the Still Bottoms/Treatment Lagoon Area and the Off-Site Containment Areas. U.S. EPA approved the proposal, and new borings were made farther to the east along Colfax.

Soil boring SB149 was advanced approximately 125 feet east of soil boring SB142, along the north side of the proposed final alignment. Soil borings SB150, SB151, and SB152 were advanced at 200 feet (approximate) intervals along the east alignment within the ACS facility boundaries

4.3 OFF-SITE CONTAINMENT AREA

The proposed barrier wall alignment in the Off-Site Containment Area is relatively unchanged from the alignment presented in the Dewatering/Barrier Wall Alignment Pre-Design Work Plan. Some minor alignment modifications were made based on the soil boring program and results of field and laboratory samples. Because the refuse and void spaces would limit construction of a barrier wall in this area, additional construction activities may be necessary prior to implementation. Twenty-three boring locations were originally planned and staked around the Still Bottom Pond in the Off-Site Area. The borings were spaced 50 feet apart along the southwestern side, adjacent to the Griffith Landfill, and 200 feet apart around the rest of the area. The closer spacing was planned because previous investigations indicated the probable presence of landfill waste along the southwest side of the Off-Site Area.

Refuse and fill material was encountered in soil borings SB201 through SB210, from near the ground surface, to depths of approximately 17 feet below ground surface. This was consistent with information from previous investigations which indicated that refuse has been buried over much of the southern part of the Off-Site Area.

The PCB waste criterion was not exceeded at any of the boring locations. The waste criterion was exceeded at one sample location, SB205, located along the southwest border of the Off-Site Area. The field GC indicated a concentration of 111,639 ppm total VOCs in the 3.5 to 5.5 foot sample interval. In accordance with the approved Scope of Work, a second boring, SB205A, was made outward, approximately 40 feet west of SB205.

The SB205 location was outside the Off-Site Area fence, in the center of the Griffith Landfill perimeter road. The sampling results did not indicate any exceedences of the waste criteria, however, the boring indicated that virtually the entire soil profile consists of buried municipal landfill refuse. Buried refuse was encountered from a depth of approximately 2 feet, to a depth of 17 feet, just three feet above the confining clay layer. Clearly, moving the barrier wall alignment outward into the Griffith Town Landfill is not a viable solution. Nor would moving the alignment to the east, further into the Off-Site Containment Area be viable, since previous investigations indicate buried waste there too.

The most viable location for the final barrier wall alignment will be through the locations of SB201 to SB210. The boring logs show that there are variable thicknesses of refuse along this alignment. But the waste is generally found above the static water table. Refuse and the associated void spaces would limit the constructability of a barrier wall in this area. A possible solution will be to excavate a trench to the base of the refuse along this portion of the alignment. After removal of the refuse, soils would be brought in to backfill the trench. The proposed final barrier wall would then be constructed through the imported soil. There may be other solutions to the refuse issue, the actual method will be determined in the 100% design.

CROSS SECTIONS OF PROPOSED FINAL ALIGNMENT

A location map of cross sections through the proposed final alignment is presented in Figure 3. Figure 4 shows the cross sections through the north alignment (soil borings SB115 through SB151), and the east alignment (soil borings SB151 through SB213). Figure 5 represents the cross section of the west alignment (soil borings SB115 to SB208). Soil boring logs used for cross sections along the proposed final alignment are presented in Appendix B1. (All other boring logs for the barrier wall alignment investigation are presented in Appendix B3.)

As shown by the cross sections, the geology of the alignment is generally uniform, consisting of fine to coarse sand with some silt and clay overlying a clay confining layer. Soil borings SB151 and SB152, located along Colfax Avenue, contained more sand and gravel than typically observed throughout the site. The depth to clay varied primarily on the basis of ground surface elevation. The clay surface was typically observed to be at an elevation of 617 feet to 622 feet msl. The elevation of the top of clay is consistent with the findings of the Remedial Investigation (RI). The average groundwater elevation of 635 feet above msl along the north (A-A') and east (B-B') cross-section lines, and 634 feet above msl on the west (C-C') cross-section line, is based on groundwater elevation data compiled during the RI from August 17, 1989 to September 13, 1990. The RI data were used to estimate an average water level occurring over a period of time in the late summer and early fall at the site.

ANALYTICAL RESULTS ALONG THE PROPOSED FINAL ALIGNMENT

6.1 PCBs

Field and laboratory PCB results for soil samples collected from borings located along the final alignment are summarized on Table 2. Field screening results and proficiency samples are included in Appendix C. Laboratory analytical reports are presented in Appendix E.

Along the proposed barrier wall final alignment in the Still Bottoms/Treatment Lagoon Area (i.e., 100-series borings), 33 soil samples were collected and analyzed for PCBs using the Ohmicron field test kit. PCBs were detected greater than 10 ppm in 10 of the soil samples analyzed with the test kits collected from the following soil borings: SB113, SB143, SB149, SB150, SB151 and SB152. All of the soil samples which exceeded the 10 ppm waste criteria, as well as two samples near the 10 ppm cutoff level (SB124, 8.5 to 10.5 feet, and SB127, 6 to 8 feet) were submitted to IEA Laboratory for confirmatory PCB analysis.

Of the twelve confirmatory soil samples submitted to the laboratory for PCB analysis, only one soil sample exhibited PCB concentrations greater than 10 ppm (Table 2). PCBs were detected in the 6 to 8 foot soil sample collected from soil boring SB127 at 44 ppm, whereas field results for the same sample indicated PCB concentrations at 8.5 ppm.

A total of 34 soil samples from the Off-Site Containment Area portion of the proposed final alignment (200-series borings) were analyzed with the field test kit. Only one sample, SB214 at 13.5 to 15.5 feet, indicated PCBs above the waste criteria (10.6 ppm). This sample was subsequently sent to IEA for confirmatory analysis. The results indicated the presence of PCBs at a concentration of 2.7 ppm, below waste criteria (Table 2).

6.2 VOCs

Field and laboratory VOC results for soil samples collected from borings located along the final alignment are summarized on Table 2. Field GC results are included in Appendix D. Laboratory analytical reports from IEA are presented in Appendix E.

A total of 23 soil samples from Still Bottoms/Treatment Lagoon Area portion of the proposed final alignment were analyzed with the field GC (Table 2). The field results

indicated only one soil sample, SB143 6 to 8 feet, had a total VOC concentrations (11,583 ppm) greater than 10,000 ppm waste criteria. A sample from the same split spoon was subsequently submitted to IEA for confirmatory analysis. Results from the lab analysis indicated a total VOC concentration of 0.76 ppm. One other sample from soil boring SB142 (6 to 8 feet) was also submitted for laboratory analysis, although the field-determined VOC concentration was less than criteria set forth in the Dewatering/Barrier Wall Alignment Pre-Design Work Plan (5,168 ppm). Results from this sample indicated a total VOC concentration of 335 ppm.

A total of 35 soil samples from Off-Site Containment Area portion of the proposed final alignment were analyzed with the field GC (Table 2). A soil sample from soil boring SB205 exceeded the 10,000 ppm waste criteria for total VOCs. Confirmation samples were not submitted immediately from this soil boring because of anticipation of moving the barrier wall alignment toward a second boring drilled approximately 40 feet west from this location at SB205A. Upon discovery of landfill refuse at SB205A, the alignment of the barrier wall shifted back to SB205 and the holding time for VOC analysis had elapsed. As discussed in Section 4.3, the area around SB205 will be addressed in the 100% design.

Field GC analyses did not show VOCs greater than 8,000 ppm in any other soil samples from the Off-Site Containment Area; therefore, no soil samples were submitted to the laboratory for confirmation analysis.

GEOTECHNICAL RESULTS

The geotechnical laboratory results performed on selected soil samples are summarized on Table 3. The laboratory reports are presented in Appendix F.

The granular soils above the clay confining layer are generally classified as a fine to coarse sand with a trace to some silt and clay, and have the Unified Soil Classification System (USCS) symbols of SP, SP-SM, and SM. The clay confining layer is generally classified as clay with a USCS symbol of CL

According to the rigid-wall falling head permeability testing (U.S. Army Corps of Engineers Method EM 1110-2-1906 (VII)), the permeability of the clay confining layer ranged from 1.7×10^{-8} cm/s (centimeters per second) to 2.4×10^{-8} cm/s based on relatively undisturbed Shelby tube samples. Liquid and plasticity limits ranged from 28-30% and 11-14%, respectively (Table 3).

As discussed in Section 3.4, the results of the flexible-wall hydraulic conductivity/permeability tests (ASTM D5084) are not available at this time. These results will be submitted to the U.S. EPA on April 19, 1996.

PILOT TEST CELL BORINGS

In accordance with the expedited Pre-Design Work Plan, sheet piling will be used to construct two small tests cells for conducting pilot studies. One test cell will be constructed in the waste in the Still Bottoms/Treatment Lagoon area on the ACS site, and the other will be constructed in the waste area in the Off-Site Containment Area. Four soil borings were made at each location to evaluate the subsurface conditions and aid in the design of the test cells. Soil borings, SB145 through SB148, were advanced approximately two feet into the clay confining layer in the Still Bottoms/Treatment Lagoon Area and soil borings (SB224 through SB227) were advanced in the Off-Site Containment Area for the pilot test cell locations. The locations of the pilot test cells and borings are presented in Figure 6. Soil boring logs for the Pilot Test Cell borings are presented in Appendix B2.

Based on Standard Penetration Tests (i.e., blow counts), conducted during boring installation (ASTM D1586), the soil materials at both pilot cell locations was classified as loose to medium dense granular soils. Field lithologic logging identified the soils at the Still Bottoms/Treatment Lagoon Area pilot test cell plots as fine to coarse sands with little silt, and generally fine sands and fill material in the Off-Site Containment Area.

Both locations for test cells were selected to be in known waste areas. As expected, some obstructions were encountered during the boring program at both locations. In the Still Bottoms/Treatment Lagoon area, several 1.5 foot thick concrete slabs were encountered one to two feet below the ground surface. As a result of the auger refusal, the borings were moved to the east from the originally planned location. Figure 6 shows the location of the borings that were made to the clay confining layer. In the Off-Site Containment area, several partially-intact metal objects (5 gallon containers and possible drums) were observed in the fill material generally 5 to 8 feet below ground surface.

SCHEDULE FOR BARRIER WALL CONSTRUCTION

A milestone and deliverable date schedule for barrier wall construction is presented in Table 4. The schedule is based on assumed review times by the U.S. EPA. Concurrent with submittal of this Technical Memorandum to the U.S. EPA, an RFP will be submitted to subcontractors soliciting proposals for barrier wall construction technologies.

Following U.S. EPA approval of the proposed barrier wall alignment, the design of the barrier wall systems will commence. The barrier wall systems include the barrier wall, the groundwater extraction systems, and the performance monitoring system. In addition, the design of the test cells to be used for the SVE and material handling/low temperature thermal desorption pilot tests will be included with the barrier wall systems. A 50 Percent Design and 100 Percent Design will be submitted to U.S. EPA and IDEM for review. As discussed with and approved by the U.S. EPA, the 50 Percent and 100 Percent design documents will meet the requirements for the 30, 60 and 95 Percent design submittals included in the SOW.

The 50 Percent Design document will be submitted once the barrier wall technology and contractor have been selected. That selection is expected to be made on June 19,1996. The submittal will include the following:

1. A draft of the design basis for all the systems listed above. The design basis will provide a brief description of the design criteria, rationale for major decisions, major equipment, permits/approvals required, effects on groundwater flow patterns, operational procedures, and management of waste and residuals. The design basis will not be complete at this stage since many aspects of the designs will not be resolved or finalized.

2. Barrier Wall Design

- The performance specification used to solicit contractor bids
- Drawings showing the final alignment and cross sections
- A Technical Memorandum presenting the selected barrier wall technology (this will actually be part of the design basis)

3. Extraction System Design

- A plan drawing showing the layout of the extraction systems
- A plan drawing showing the conveyance piping
- Draft details of the extraction wells/trenches

- 4. Performance Monitoring System Design
 - A draft of the Performance Standard Verification Plan (PSVP)
 - A plan drawing showing the location of the monitoring wells/piezometers
- 5. Test Cell Design
 - A draft of the specification for the test cells
 - A plan drawings of the test cell
 - A geologic cross-section (if needed)
 - Draft details of the sheet pile construction
- 6. A draft Health and Safety Plan for the construction
- 7. A draft Construction Quality Assurance Plan (CQAP)
- 8. Preliminary Construction Schedule
 - Pre-construction meeting
 - Site preparation and/or workbench construction
 - Start of construction
 - Completion of construction
 - Site restoration

The 100 Percent Design document will be submitted on August 12, 1996 and it will incorporate comments on the 50 Percent Design as well as the finalized designs of the various systems and associated plans. Specifically, the submittal will include the following:

- 1. The final design basis for the various systems
- 2. Barrier Wall Design
 - The final design drawings
- Extraction System Design
 - Final drawings of the extraction wells/trenches, sump or wellhead completions, conveyance piping and tie-ins to the treatment system, and electrical power supply and instrumentation.
- 4. Performance Monitoring System Design
 - Final drawings showing the locations and construction details for the piezometers/monitoring wells.
 - The final PSVP including the sampling program, a QAPP addendum, and a Health and Safety Plan addendum.
- 5. Test Cell Design
 - Final design drawings for the test cell layout, location, and construction details
 - A performance specification for dewatering the test cell

- 6. The final Health and Safety Plan
- 7. The final CQAP
- 8. Detailed Construction Schedule
 - Pre-construction meeting
 - Site preparation and/or workbench construction
 - Start of construction
 - Completion of construction
 - Site restoration

The final design of the barrier wall will incorporate all known underground and overhead utilities, pipelines, sewers and drains in the area. Figure 7 shows the final alignment of the wall and all known potentially affected utilities in the vicinity of the ACS facility. Based on deliverable dates established on a milestone basis, the construction of the barrier wall will be completed by February 1997 (Table 4).

J:\4077\TECHMEMO\BAR-WALL\BAR-REPT.DOC

£3

Table 1 Soil Boring Location and Elevation Information American Chemical Service, Inc. Barrier Wall Investigation On-Site Containment Area

Number Northing Easting Elevation (mst) To Clay (ft) Elevat	Clay	
SB-102 6873.7 5269.6 637.8 21.0 61 SB-103 6835.1 5287.1 637.8 21.0 61 SB-104 6838.3 5304.1 637.8 20.0 61 SB-105 6817.9 5321.3 637.8 20.0 61 SB-106 6802.1 5339.3 637.8 20.3 61 SB-107 6782.4 5356.8 637.8 19.5 61 SB-108 6764.6 5372.8 637.8 19.5 61 SB-109 7027.3 5307.5 638.0 18.5 61 SB-109 7027.3 5307.5 638.0 18.5 61 SB-110 6751.9 5660.5 638.8 21.8 6 SB-111 6688.6 5524.4 638.4 19.0 61 SB-113 7065.9 5422.2 637.8 17.6 62 SB-114 7072.6 5374.8 638.1 19.3 61	Elevation (msl)	
SB-103 6855.1 5287.1 637.8 21.0 61 SB-104 6838.3 5304.1 637.8 20.0 61 SB-105 6817.9 5321.3 637.8 20.0 61 SB-106 6802.1 5339.3 637.8 20.3 61 SB-107 6782.4 5356.8 637.8 19.5 61 SB-108 6764.6 5372.8 637.6 18.5 61 SB-109 7027.3 5307.5 638.0 18.5 61 SB-110 6751.9 5660.5 638.8 21.8 6 SB-111 6688.6 5524.4 638.4 19.0 61 SB-112 6935.0 5575.9 639.7 19.5 62 SB-113 7065.9 5422.2 637.8 17.6 62 SB-114 7072.6 5374.8 638.1 19.3 61 SB-115 7071.4 5328.2 638.3 19.3 61	18.4	
SB-104 6838.3 5304.1 637.8 20.0 61 SB-105 6817.9 5321.3 637.8 20.0 61 SB-106 6802.1 5339.3 637.8 20.3 61 SB-107 6782.4 5336.8 637.8 19.5 61 SB-108 6764.6 5372.8 637.6 18.5 61 SB-109 7027.3 5307.5 638.0 18.5 61 SB-110 6751.9 5660.5 638.8 21.8 6 SB-111 6688.6 5524.4 638.4 19.0 61 SB-112 6935.0 5575.9 639.7 19.5 62 SB-113 7065.9 5422.2 637.8 17.6 62 SB-114 7072.6 5374.8 638.1 19.3 61 SB-115 7071.4 5328.2 638.3 19.8 61 SB-116 7054.4 5472.4 637.5 18.6 61	16.8	
SB-105 6817.9 5321.3 637.8 20.0 61 SB-106 6802.1 5339.3 637.8 20.3 61 SB-107 6782.4 5356.8 637.8 19.5 61 SB-108 6764.6 5372.8 637.6 18.5 61 SB-109 7027.3 5307.5 638.0 18.5 61 SB-110 6751.9 5660.5 638.8 21.8 6 SB-111 6688.6 5524.4 638.4 19.0 61 SB-112 6935.0 5575.9 639.7 19.5 62 SB-113 7065.9 5422.2 637.8 17.6 62 SB-114 7072.6 5374.8 638.1 19.3 61 SB-115 7071.4 5328.2 638.3 19.8 61 SB-115 7071.4 5328.2 638.3 19.8 61 SB-115 7071.4 5328.2 638.3 19.8 61	6.8	
SB-105 6817.9 5321.3 637.8 20.0 61 SB-106 6802.1 5339.3 637.8 20.3 61 SB-107 6782.4 5356.8 637.8 19.5 61 SB-108 6764.6 5372.8 637.6 18.5 61 SB-109 7027.3 5307.5 638.0 18.5 61 SB-110 6751.9 5660.5 638.8 21.8 6 SB-111 6688.6 5524.4 638.4 19.0 61 SB-112 6935.0 5575.9 639.7 19.5 62 SB-113 7065.9 5422.2 637.8 17.6 62 SB-114 7072.6 5374.8 638.1 19.3 61 SB-115 7071.4 5328.2 638.3 19.8 61 SB-116 7054.4 5472.4 637.5 18.6 61 SB-117 6929.2 5219.9 637.9 18.5 61	17.8	
SB-106 6802.1 5339.3 637.8 20.3 61 SB-107 6782.4 5356.8 637.8 19.5 61 SB-108 6764.6 5372.8 637.6 18.5 61 SB-109 7027.3 5307.5 638.0 18.5 61 SB-110 6751.9 5660.5 638.8 21.8 6 SB-111 6688.6 5524.4 638.4 19.0 61 SB-112 6935.0 5575.9 639.7 19.5 62 SB-113 7065.9 5422.2 637.8 17.6 62 SB-114 7072.6 5374.8 638.1 19.3 61 SB-115 7071.4 5328.2 638.3 19.8 61 SB-116 7054.4 5472.4 637.5 18.6 61 SB-117 6929.2 5219.9 637.9 18.5 61 SB-117 6929.2 5219.9 637.9 18.5 61	7.8	
SB-107 6782.4 5356.8 637.8 19.5 61 SB-108 6764.6 5372.8 637.6 18.5 61 SB-109 7027.3 5307.5 638.0 18.5 61 SB-110 6751.9 5660.5 638.8 21.8 6 SB-111 6688.6 5524.4 638.4 19.0 61 SB-112 6935.0 5575.9 639.7 19.5 62 SB-113 7065.9 5422.2 637.8 17.6 62 SB-114 7072.6 5374.8 638.1 19.3 61 SB-115 7071.4 5328.2 638.3 19.8 61 SB-116 7054.4 5472.4 637.5 18.6 61 SB-117 6929.2 5219.9 637.9 18.5 61 SB-118 6721.5 5620.5 639.1 24.8 61 SB-129 6742.0 5280.7 637.7 20.0 61	17.5	
SB-108 6764.6 5372.8 637.6 18.5 61 SB-109 7027.3 5307.5 638.0 18.5 61 SB-110 6751.9 5660.5 638.8 21.8 6 SB-111 6688.6 5524.4 638.4 19.0 61 SB-112 6935.0 5575.9 639.7 19.5 62 SB-113 7065.9 5422.2 637.8 17.6 62 SB-114 7072.6 5374.8 638.1 19.3 61 SB-115 7071.4 5328.2 638.3 19.8 61 SB-116 7054.4 5472.4 637.5 18.6 61 SB-117 6929.2 5219.9 637.9 18.5 61 SB-118 6721.5 5620.5 639.1 24.8 61 SB-119 6708.8 5567.4 638.8 21.7 61 SB-120 6742.0 5280.7 637.7 20.0 61	18.3	
SB-109 7027.3 5307.5 638.0 18.5 61 SB-110 6751.9 5660.5 638.8 21.8 6 SB-111 6688.6 5524.4 638.4 19.0 61 SB-112 6935.0 5575.9 639.7 19.5 62 SB-113 7065.9 5422.2 637.8 17.6 62 SB-114 7072.6 5374.8 638.1 19.3 61 SB-115 7071.4 5328.2 638.3 19.8 61 SB-116 7054.4 5472.4 637.5 18.6 61 SB-117 6929.2 5219.9 637.9 18.5 61 SB-117 6929.2 5219.9 637.9 18.5 61 SB-118 6721.5 5620.5 639.1 24.8 61 SB-119 6708.8 5567.4 638.8 21.7 61 SB-120 6742.0 5280.7 637.7 20.0 61	9.1	
SB-110 6751.9 5660.5 638.8 21.8 6 SB-111 6688.6 5524.4 638.4 19.0 61 SB-112 6935.0 5575.9 639.7 19.5 62 SB-113 7065.9 5422.2 637.8 17.6 62 SB-114 7072.6 5374.8 638.1 19.3 61 SB-115 7071.4 5328.2 638.3 19.8 61 SB-116 7054.4 5472.4 637.5 18.6 61 SB-117 6929.2 5219.9 637.9 18.5 61 SB-118 6721.5 5620.5 639.1 24.8 61 SB-119 6708.8 5557.4 638.8 21.7 61 SB-120 6742.0 5280.7 637.7 20.0 61 SB-121 6673.0 5476.0 638.1 19.1 6 SB-122 6971.7 5248.3 638.1 19.1 6 <t< td=""><td>9.5</td></t<>	9.5	
SB-111 6688.6 5524.4 638.4 19.0 61 SB-112 6935.0 5575.9 639.7 19.5 62 SB-113 7065.9 5422.2 637.8 17.6 62 SB-114 7072.6 5374.8 638.1 19.3 61 SB-115 7071.4 5328.2 638.3 19.8 61 SB-116 7054.4 5472.4 637.5 18.6 61 SB-117 6929.2 5219.9 637.9 18.5 61 SB-118 6721.5 5620.5 639.1 24.8 61 SB-119 6708.8 5557.4 638.8 21.7 61 SB-120 6742.0 5280.7 637.7 20.0 61 SB-121 6673.0 5476.0 638.1 21.5 61 SB-122 6971.7 5248.3 638.1 19.1 6 SB-123 7001.1 5274.0 638.1 19.5 61	17	
SB-113 7065.9 5422.2 637.8 17.6 62 SB-114 7072.6 5374.8 638.1 19.3 61 SB-115 7071.4 5328.2 638.3 19.8 61 SB-116 7054.4 5472.4 637.5 18.6 61 SB-117 6929.2 5219.9 637.9 18.5 61 SB-118 6721.5 5620.5 639.1 24.8 61 SB-119 6708.8 5567.4 638.8 21.7 61 SB-120 6742.0 5280.7 637.7 20.0 61 SB-121 6673.0 5476.0 638.1 21.5 61 SB-121 6673.0 5476.0 638.1 19.1 6 SB-123 7001.1 5274.0 638.1 19.5 61 SB-124 7023.1 5521.0 638.6 18.5 62 SB-125 6855.0 5622.8 638.4 19.0 61	9.4	
SB-113 7065.9 5422.2 637.8 17.6 62 SB-114 7072.6 5374.8 638.1 19.3 61 SB-115 7071.4 5328.2 638.3 19.8 61 SB-116 7054.4 5472.4 637.5 18.6 61 SB-117 6929.2 5219.9 637.9 18.5 61 SB-118 6721.5 5620.5 639.1 24.8 61 SB-119 6708.8 5567.4 638.8 21.7 61 SB-120 6742.0 5280.7 637.7 20.0 61 SB-121 6673.0 5476.0 638.1 21.5 61 SB-122 6971.7 5248.3 638.1 19.1 6 SB-123 7001.1 5274.0 638.1 19.5 61 SB-124 7023.1 5521.0 638.6 18.5 62 SB-125 6855.0 5622.8 638.4 19.0 61	20.2	
SB-114 7072.6 5374.8 638.1 19.3 61 SB-115 7071.4 5328.2 638.3 19.8 61 SB-116 7054.4 5472.4 637.5 18.6 61 SB-117 6929.2 5219.9 637.9 18.5 61 SB-118 6721.5 5620.5 639.1 24.8 61 SB-119 6708.8 5567.4 638.8 21.7 61 SB-120 6742.0 5280.7 637.7 20.0 61 SB-121 6673.0 5476.0 638.1 21.5 61 SB-122 6971.7 5248.3 638.1 19.1 6 SB-123 7001.1 5274.0 638.1 19.5 61 SB-124 7023.1 55521.0 638.6 18.5 62 SB-124 7023.1 55521.0 638.6 18.5 62 SB-125 6855.0 5622.8 638.3 19.0 61	20.2	
SB-115 7071.4 5328.2 638.3 19.8 61 SB-116 7054.4 5472.4 637.5 18.6 61 SB-117 6929.2 5219.9 637.9 18.5 61 SB-118 6721.5 5620.5 639.1 24.8 61 SB-119 6708.8 5567.4 638.8 21.7 61 SB-120 6742.0 5280.7 637.7 20.0 61 SB-121 6673.0 5476.0 638.1 21.5 61 SB-121 6673.0 5476.0 638.1 21.5 61 SB-122 6971.7 5248.3 638.1 19.1 6 SB-123 7001.1 5274.0 638.1 19.5 61 SB-124 7023.1 5521.0 638.6 18.5 62 SB-124 7023.1 5521.0 638.6 18.5 62 SB-125 6855.0 5622.8 638.3 19.0 61	8.8	
SB-116 7054.4 5472.4 637.5 18.6 61 SB-117 6929.2 5219.9 637.9 18.5 61 SB-118 6721.5 5620.5 639.1 24.8 61 SB-119 6708.8 5567.4 638.8 21.7 61 SB-120 6742.0 5280.7 637.7 20.0 61 SB-121 6673.0 5476.0 638.1 21.5 61 SB-122 6971.7 5248.3 638.1 19.1 6 SB-123 7001.1 5274.0 638.1 19.5 61 SB-124 7023.1 5521.0 638.6 18.5 62 SB-125 6855.0 5622.8 638.4 19.0 61 SB-126 6907.2 5615.2 638.3 19.5 61 SB-127 6960.9 5597.7 638.3 19.0 61 SB-128 6803.1 5653.1 638.9 24.5 61	8.5	
SB-117 6929.2 5219.9 637.9 18.5 61 SB-118 6721.5 5620.5 639.1 24.8 61 SB-119 6708.8 5567.4 638.8 21.7 61 SB-120 6742.0 5280.7 637.7 20.0 61 SB-121 6673.0 5476.0 638.1 21.5 61 SB-122 6971.7 5248.3 638.1 19.1 6 SB-123 7001.1 5274.0 638.1 19.5 61 SB-124 7023.1 5521.0 638.6 18.5 62 SB-125 6855.0 5622.8 638.4 19.0 61 SB-126 6907.2 5615.2 638.3 19.5 61 SB-127 6960.9 5599.7 638.3 19.0 61 SB-128 6803.1 5653.1 638.9 24.5 61 SB-129 6712.4 5268.4 636.9 18.5 61	8.9	
SB-118 6721.5 5620.5 639.1 24.8 61 SB-119 6708.8 5567.4 638.8 21.7 61 SB-120 6742.0 5280.7 637.7 20.0 61 SB-121 6673.0 5476.0 638.1 21.5 61 SB-122 6971.7 5248.3 638.1 19.1 6 SB-123 7001.1 5274.0 638.1 19.5 61 SB-124 7023.1 5521.0 638.6 18.5 62 SB-125 6855.0 5622.8 638.4 19.0 61 SB-126 6907.2 5615.2 638.3 19.0 61 SB-127 6960.9 5599.7 638.3 19.0 61 SB-128 6803.1 5653.1 638.9 24.5 61 SB-129 6712.4 5268.4 636.9 18.5 61 SB-130 6652.2 5448.6 637.9 19.5 61	9.4	
SB-119 6708.8 5567.4 638.8 21.7 61 SB-120 6742.0 5280.7 637.7 20.0 61 SB-121 6673.0 5476.0 638.1 21.5 61 SB-122 6971.7 5248.3 638.1 19.1 6 SB-123 7001.1 5274.0 638.1 19.5 61 SB-124 7023.1 5521.0 638.6 18.5 62 SB-125 6855.0 5622.8 638.4 19.0 61 SB-126 6907.2 5615.2 638.3 19.5 61 SB-127 6960.9 5599.7 638.3 19.0 61 SB-128 6803.1 5653.1 638.9 24.5 61 SB-129 6712.4 5268.4 636.9 18.5 61 SB-130 6652.2 5448.6 637.9 19.5 61 SB-131 6826.5 5088.9 636.7 18.0 61	4.3	
SB-120 6742.0 5280.7 637.7 20.0 61 SB-121 6673.0 5476.0 638.1 21.5 61 SB-122 6971.7 5248.3 638.1 19.1 6 SB-123 7001.1 5274.0 638.1 19.5 61 SB-124 7023.1 5521.0 638.6 18.5 62 SB-125 6855.0 5622.8 638.4 19.0 61 SB-126 6907.2 5615.2 638.3 19.5 61 SB-127 6960.9 5599.7 638.3 19.0 61 SB-128 6803.1 5653.1 638.9 24.5 61 SB-129 6712.4 5268.4 636.9 18.5 61 SB-130 6652.2 5448.6 637.9 19.5 61 SB-131 6826.5 5088.9 636.7 18.0 61 SB-132 6756.4 5174.5 637.0 19.0 6 <	7.1	
SB-121 6673.0 5476.0 638.1 21.5 61 SB-122 6971.7 5248.3 638.1 19.1 6 SB-123 7001.1 5274.0 638.1 19.5 61 SB-124 7023.1 5521.0 638.6 18.5 62 SB-125 6855.0 5622.8 638.4 19.0 61 SB-126 6907.2 5615.2 638.3 19.5 61 SB-127 6960.9 5599.7 638.3 19.0 61 SB-128 6803.1 5653.1 638.9 24.5 61 SB-129 6712.4 5268.4 636.9 18.5 61 SB-130 6652.2 5448.6 637.9 19.5 61 SB-131 6826.5 5088.9 636.7 18.0 61 SB-132 6756.4 5174.5 637.0 19.0 6 SB-133 6670.7 5352.5 637.3 20.0 61 <	7.7	
SB-122 6971.7 5248.3 638.1 19.1 6 SB-123 7001.1 5274.0 638.1 19.5 61 SB-124 7023.1 5521.0 638.6 18.5 62 SB-125 6855.0 5622.8 638.4 19.0 61 SB-126 6907.2 5615.2 638.3 19.0 61 SB-127 6960.9 5599.7 638.3 19.0 61 SB-128 6803.1 5653.1 638.9 24.5 61 SB-129 6712.4 5268.4 636.9 18.5 61 SB-130 6652.2 5448.6 637.9 19.5 61 SB-131 6826.5 5088.9 636.7 18.0 61 SB-132 6756.4 5174.5 637.0 19.0 6 SB-133 6670.7 5352.5 637.3 20.0 61 SB-134 6667.5 5402.1 637.7 20.5 61 <	6.6	
SB-123 7001.1 5274.0 638.1 19.5 61 SB-124 7023.1 5521.0 638.6 18.5 62 SB-125 6855.0 5622.8 638.4 19.0 61 SB-126 6907.2 5615.2 638.3 19.5 61 SB-127 6960.9 5599.7 638.3 19.0 61 SB-128 6803.1 5653.1 638.9 24.5 61 SB-129 6712.4 5268.4 636.9 18.5 61 SB-130 6652.2 5448.6 637.9 19.5 61 SB-131 6826.5 5088.9 636.7 18.0 61 SB-132 6756.4 5174.5 637.0 19.0 6 SB-133 6670.7 5352.5 637.3 20.0 61 SB-134 6667.5 5402.1 637.7 20.5 61 SB-135 6737.0 5230.1 637.1 18.5 61	19	
SB-124 7023.1 5521.0 638.6 18.5 62 SB-125 6855.0 5622.8 638.4 19.0 61 SB-126 6907.2 5615.2 638.3 19.5 61 SB-127 6960.9 5599.7 638.3 19.0 61 SB-128 6803.1 5653.1 638.9 24.5 61 SB-129 6712.4 5268.4 636.9 18.5 61 SB-130 6652.2 5448.6 637.9 19.5 61 SB-131 6826.5 5088.9 636.7 18.0 61 SB-132 6756.4 5174.5 637.0 19.0 6 SB-133 6670.7 5352.5 637.3 20.0 61 SB-134 6667.5 5402.1 637.7 20.5 61 SB-135 6737.0 5230.1 637.1 18.5 61 SB-136 6903.5 5146.0 637.5 18.5 6 <	8.6	
SB-125 6855.0 5622.8 638.4 19.0 61 SB-126 6907.2 5615.2 638.3 19.5 61 SB-127 6960.9 5599.7 638.3 19.0 61 SB-128 6803.1 5653.1 638.9 24.5 61 SB-129 6712.4 5268.4 636.9 18.5 61 SB-130 6652.2 5448.6 637.9 19.5 61 SB-131 6826.5 5088.9 636.7 18.0 61 SB-132 6756.4 5174.5 637.0 19.0 6 SB-133 6670.7 5352.5 637.3 20.0 61 SB-134 6667.5 5402.1 637.7 20.5 61 SB-135 6737.0 5230.1 637.1 18.5 61 SB-136 6903.5 5146.0 637.5 18.5 6 SB-137 6985.7 5225.5 637.6 17.5 62 <	0.1	
SB-126 6907.2 5615.2 638.3 19.5 61 SB-127 6960.9 5599.7 638.3 19.0 61 SB-128 6803.1 5653.1 638.9 24.5 61 SB-129 6712.4 5268.4 636.9 18.5 61 SB-130 6652.2 5448.6 637.9 19.5 61 SB-131 6826.5 5088.9 636.7 18.0 61 SB-132 6756.4 5174.5 637.0 19.0 6 SB-133 6670.7 5352.5 637.3 20.0 61 SB-134 6667.5 5402.1 637.7 20.5 61 SB-135 6737.0 5230.1 637.1 18.5 61 SB-136 6903.5 5146.0 637.5 18.5 6 SB-137 6985.7 5225.5 637.6 17.5 62 SB-138 6636.5 5397.5 637.6 18.5 61 <	9.4	
SB-127 6960.9 5599.7 638.3 19.0 61 SB-128 6803.1 5653.1 638.9 24.5 61 SB-129 6712.4 5268.4 636.9 18.5 61 SB-130 6652.2 5448.6 637.9 19.5 61 SB-131 6826.5 5088.9 636.7 18.0 61 SB-132 6756.4 5174.5 637.0 19.0 6 SB-133 6670.7 5352.5 637.3 20.0 61 SB-134 6667.5 5402.1 637.7 20.5 61 SB-135 6737.0 5230.1 637.1 18.5 61 SB-136 6903.5 5146.0 637.5 18.5 6 SB-137 6985.7 5225.5 637.6 17.5 62 SB-138 6636.5 5397.5 637.6 18.5 61 SB-139 6865.6 5117.2 637.4 18.5 61 <	8.8	
SB-128 6803.1 5653.1 638.9 24.5 61 SB-129 6712.4 5268.4 636.9 18.5 61 SB-130 6652.2 5448.6 637.9 19.5 61 SB-131 6826.5 5088.9 636.7 18.0 61 SB-132 6756.4 5174.5 637.0 19.0 6 SB-133 6670.7 5352.5 637.3 20.0 61 SB-134 6667.5 5402.1 637.7 20.5 61 SB-135 6737.0 5230.1 637.1 18.5 61 SB-136 6903.5 5146.0 637.5 18.5 6 SB-137 6985.7 5225.5 637.6 17.5 62 SB-138 6636.5 5397.5 637.6 20.0 61 SB-139 6865.6 5117.2 637.4 18.5 61 SB-140 6956.3 5179.7 637.6 18.5 61	9.3	
SB-129 6712.4 5268.4 636.9 18.5 61 SB-130 6652.2 5448.6 637.9 19.5 61 SB-131 6826.5 5088.9 636.7 18.0 61 SB-132 6756.4 5174.5 637.0 19.0 6 SB-133 6670.7 5352.5 637.3 20.0 61 SB-134 6667.5 5402.1 637.7 20.5 61 SB-135 6737.0 5230.1 637.1 18.5 61 SB-136 6903.5 5146.0 637.5 18.5 6 SB-137 6985.7 5225.5 637.6 17.5 62 SB-138 6636.5 5397.5 637.6 20.0 61 SB-139 6865.6 5117.2 637.4 18.5 61 SB-140 6956.3 5179.7 637.6 18.5 61	4.4	
SB-130 6652.2 5448.6 637.9 19.5 61 SB-131 6826.5 5088.9 636.7 18.0 61 SB-132 6756.4 5174.5 637.0 19.0 6 SB-133 6670.7 5352.5 637.3 20.0 61 SB-134 6667.5 5402.1 637.7 20.5 61 SB-135 6737.0 5230.1 637.1 18.5 61 SB-136 6903.5 5146.0 637.5 18.5 6 SB-137 6985.7 5225.5 637.6 17.5 62 SB-138 6636.5 5397.5 637.6 20.0 61 SB-139 6865.6 5117.2 637.4 18.5 61 SB-140 6956.3 5179.7 637.6 18.5 61		
SB-131 6826.5 5088.9 636.7 18.0 61 SB-132 6756.4 5174.5 637.0 19.0 6 SB-133 6670.7 5352.5 637.3 20.0 61 SB-134 6667.5 5402.1 637.7 20.5 61 SB-135 6737.0 5230.1 637.1 18.5 61 SB-136 6903.5 5146.0 637.5 18.5 6 SB-137 6985.7 5225.5 637.6 17.5 62 SB-138 6636.5 5397.5 637.6 20.0 61 SB-139 6865.6 5117.2 637.4 18.5 61 SB-140 6956.3 5179.7 637.6 18.5 61		
SB-132 6756.4 5174.5 637.0 19.0 6 SB-133 6670.7 5352.5 637.3 20.0 61 SB-134 6667.5 5402.1 637.7 20.5 61 SB-135 6737.0 5230.1 637.1 18.5 61 SB-136 6903.5 5146.0 637.5 18.5 6 SB-137 6985.7 5225.5 637.6 17.5 62 SB-138 6636.5 5397.5 637.6 20.0 61 SB-139 6865.6 5117.2 637.4 18.5 61 SB-140 6956.3 5179.7 637.6 18.5 61		
SB-133 6670.7 5352.5 637.3 20.0 61 SB-134 6667.5 5402.1 637.7 20.5 61 SB-135 6737.0 5230.1 637.1 18.5 61 SB-136 6903.5 5146.0 637.5 18.5 6 SB-137 6985.7 5225.5 637.6 17.5 62 SB-138 6636.5 5397.5 637.6 20.0 61 SB-139 6865.6 5117.2 637.4 18.5 61 SB-140 6956.3 5179.7 637.6 18.5 61	18	
SB-134 6667.5 5402.1 637.7 20.5 61 SB-135 6737.0 5230.1 637.1 18.5 61 SB-136 6903.5 5146.0 637.5 18.5 6 SB-137 6985.7 5225.5 637.6 17.5 62 SB-138 6636.5 5397.5 637.6 20.0 61 SB-139 6865.6 5117.2 637.4 18.5 61 SB-140 6956.3 5179.7 637.6 18.5 61	7.3	
SB-135 6737.0 5230.1 637.1 18.5 61 SB-136 6903.5 5146.0 637.5 18.5 6 SB-137 6985.7 5225.5 637.6 17.5 62 SB-138 6636.5 5397.5 637.6 20.0 61 SB-139 6865.6 5117.2 637.4 18.5 61 SB-140 6956.3 5179.7 637.6 18.5 61	7.2	
SB-136 6903.5 5146.0 637.5 18.5 6 SB-137 6985.7 5225.5 637.6 17.5 62 SB-138 6636.5 5397.5 637.6 20.0 61 SB-139 6865.6 5117.2 637.4 18.5 61 SB-140 6956.3 5179.7 637.6 18.5 61	8.6	
SB-137 6985.7 5225.5 637.6 17.5 62 SB-138 6636.5 5397.5 637.6 20.0 61 SB-139 6865.6 5117.2 637.4 18.5 61 SB-140 6956.3 5179.7 637.6 18.5 61	19	
SB-138 6636.5 5397.5 637.6 20.0 61 SB-139 6865.6 5117.2 637.4 18.5 61 SB-140 6956.3 5179.7 637.6 18.5 61	0.1	
SB-139 6865.6 5117.2 637.4 18.5 61 SB-140 6956.3 5179.7 637.6 18.5 61	7.6	
SB-140 6956.3 5179.7 637.6 18.5 61	8.9	
	9.1	
SB-141 6999.3 5199.7 637.6 18.5 61	9.1	
	9.3	
	8.1	
Brancon divini, con de la compressión de la contraction de la contraction de la co	20	
	6.1	
	5.6	
	5.7	
	17	
	8.7	
* · · · · · · · · · · · · · · · · · · ·	18	
	8.8	
	8.2	

Table 1 Soil Boring Location and Elevation Information American Chemical Service, Inc. Barrier Wall Investigation Off-Site Containment Area

Boring	Coordinates Ground			Depth	Clay	
Number	Northing	Easting	Elevation (msl)	To Clay (ft)	Elevation (msl)	
SB-201	5674.8	4984.8	647.5	NA	NA	
SB-202	6059.9	5011.5	640.4	NA	NA	
SB-202A	6077.4	5014.5	639.9	22.0	617.9	
SB-203	6029.0	5011.5	641.0	22.0	619	
SB-204	5964.5	5012.0	641.9	21.8	620.1	
SB-205	5913.8	5014.2	643.4	22.5	620.9	
SB-205A	5930.6	4988.6	645.9	26.5	619.4	
SB-206	5856.2	5013.4	644.6	24.0	620.6	
SB-207	5801.1	4978.0	646.9	25.0	621.9	
SB-208	5763.9	4960.8	646.8	25.5	621.3	
SB-209	5715.5	4942.1	647.4	28.0	619.4	
SB-210	5690.0	4988.9	647.2	26.0	621.2	
SB-211	5663.6	5186.0	650.9	29.5	621.4	
SB-212	5758.7	5453.6	649.4	28.0	621.4	
SB-213	5637.8	5388.9	653.1	31.0	622.1	
SB-214	5946.4	5523.4 647.2		26.0	621.2	
SB-215	6126.2	5615.5 647.9		28.5	619.4	
SB-216	6325.7	5662.3 645.9		26.0	619.9	
SB-217	6444.1	5602.8 639.5		22.0	617.5	
SB-218	6517.4	5411.0	634.7	16.0	618.7	
SB-219	6606.9	5299.9			619	
SB-220	6496.9	5175.7 635.4		16.0	619.4	
SB-221	6353.9	5138.1	634.0	13.0	621	
SB-222	6223.4	5069.4	638.6	18.5	620.1	
SB-223	6729.8	5059.2 638.5		20.0	618.5	
SB-224	6197.5			27.0	619.9	
SB-225	6208.5	5283.1	647.3	27.0	620.3	
SB-226	6192.7	5286.9	647.5	27.0	620.5	
SB-227	6212.0	5297.6	646.9	27.1	619.8	

Notes:

Coordinates and ground surface elevations surveyed by Area Survey, February 16, 1996.

NA = Not Applicable. Soil boring abandoned before reaching clay confining layer due to refusal.

msl = Mean Sea Level

Table 2
Summary of Soil Borings and Sample Analysis
Conducted Along the Final Barrier Wall Alignment
American Chemical Service, Inc.
Griffith, Indiana

Soil	Sample	PCB Analy	tical Results	VOC Analytical Results		
Boring Depth (ft)		1 1		Fleid GC IEA L		
Number	Interval Results (ppm)		Results (ppm)	Results (ppm)	Results (ppm)	
SB109	13 to 15	ND	NA	1.3	NA	
SB113	7 to 9	17.3	4.13	42	NA	
SB113	9 to 11	ND	NA	2.3	NA	
SB114	3.5 to 5.5	1.9	NA	1.1	NA	
SB114	8.5 to 10.5	1.4	NA	1	NA	
SB115	3.5 to 5.5	ND	NA	2	NA	
SB115	6 to 8	ND	NA	NA	NA	
SB116	1 to 3	NA	NA	106	NA	
SB116	3.5 to 5.5	ND	NA	NA	NA	
SB116	6 to 8	1.5	NA	ND	NA	
SB124	6 to 8	ND	NA	NA	NA	
SB124	8.5 to 10.5	5.2	6.11	NA	NA	
SB124	11 to 13	NA	NA	51.6	NA	
SB126	3.5 to 5.5	NA	NA	206.8	NA	
SB126	11 to 13	7.6	NA	269.3	NA	
SB127	6 to 8	8.5	44	NA	NA	
SB127	8.5 to 10	ND	NA	352.7	NA	
SB131	6 to 8	ND	NA	NA	NA	
SB131	8.5 to 10	NA	NA	NA	N.A	
SB131	13.5 to 15.5	NA	NA	11	NA	
SB136	5 to 7	ND	NA	NA	NA	
SB136	17 to 19	NA	NA	25.6	NA	
SB139	6 to 8	2.8	NA	NA	NA	
SB139	16 to 18	NA	NA	26	NA	
SB140	6 to 8			ND	NA	
SB140	8.5 to 10.5	ND	NA	NA	NA	
SB141	3.5 to 5.5	NA NA		1.2	NA	
SB141	6 to 8	ND	NA	NA	NA	
SB141	8.5 to 10.5	1.5	NA	NA	NA	
SB142	6 to 8	ND	NA	5,168	335	
SB142	8.5 to 10.5	ND	NA	NA	NA	
SB143	6 to 8	13.9	2.9	11,583	0.76	
SB143	8.5 to 10.5	16.4	1.99	11.9	NA	
SB144	8.5 to 10.5	8.3	NA	141	NA	
SB144	11 to 13	7.4	NA	NA	NA	
SB149	8.5 to 10.5	10.1	0.86	6.1	NA	
SB149	16 to 18			NA	NA	
SB150	6 to 8	>50	0.69	ND	NΛ	
SB151	5 to 7	14.4	ND	NA	NA	
SB151	9 to 11	13.9	ND	NA	NA	
SB151	19 to 21			70		
SB152	7 to 9	15.0	ND	NA	NA	
SB152	9 to 11	33.0	ND	NA	NA	

Table 2 continued

Summary of Soil Borings and Sample Analysis Conducted Along the Final Barrier Wall Alignment American Chemical Service, Inc.

Griffith, Indiana

Soil	Sample	Sample PCB Analytical Results VOC Analytical R			
Boring	Depth (ft)	Field PCB	IEA Lab	Field GC	IEA Lab
Number	Interval	Results (ppm)	Results (ppm)	Results (ppm)	Results (ppm)
SB202A	13.5 to 15.5	ND	NA	NA	NA
SB202A	16 to 18	ND	NA	0.9	NA
SB203	13.5 to 15.5	1.1	NA .	2.7	NA
SB203	16 to 18	ND	NA	3.2	NA
SB204	13.5 to 15.5	ND	NA	1.1	NA
SB204	16 to 18	ND	NA	2.7	NA
SB205	3.5 to 5.5	NA	NA	111,639	NA
SB205	6 to 8	NA	NA	937	NA
SB206	5 to 7	ND	NA	4	NA
SB206	7 to 9	ND	NA	3.6	NA
SB207	13.5 to 15.5	ND	NA	ND	NA
SB207	16 to 18	ND	NA	1.1	NA
SB207	21 to 23	ND	NA	1.1	NA
SB208	11 to 13	1.2	NA	ND	NA
SB208	23.5 to 25.5	ND	NA	ND	NA
SB209	16 to 18	ND	NA	0.4	NA
SB209	18.5 to 20.5	ND	NA	2.6	NA
SB210	16 to 18	ND	NA	5.1	NA
SB210	18.5 to 20.5	ND	NA	3	NA
SB211	8.5 to 10.5	ND	NA	0.3	NA
SB211	18.5 to 20.5	ND	NA	0.8	NA
SB212	19 to 21	ND	NA	6	NA
SB212	23 to 25	NA	NA	16	NA
SB213	23.5 to 25.5	ND	NA	0.9	NA
SB213	26 to 28	NA	NA	4.4	NA
SB214	13.5 to 15.5	10.6	2.7	NA	NA
SB214	16 to 18	NA	NA	2.2	NA
SB214	18.5 to 20.5	ND	NA	NA	NA
SB214	21 to 23	NA	NA	9.5	NA
SB215	17 to 19	ND	NA	397	NA
SB215	19 to 21	ND	NA	1.7	NA
SB216	13.5 to 15.5	ND	NA	13	NA
SB220	8.5 to 10.5	ND	NA	3	NA
SB220	11 to 13	ND	NA	7.4	NA
SB221	9 to 11	ND	NA	152	NA
SB221	11 to 13	ND	NA	89	NA
SB222	13.5 to 15.5	ND	NA	65	NA
SB223	18.5 to 20.5	7.3	NA	1	NA

Notes:

Concentrations reported in parts per million (ppm)

NA - Not Analyzed

ND - Not Detected

Bold indicates an exceedence of the waste criteria as defined in the Barrrier Wall Work Plan

Table 3
Geotechnical Laboratory Results Summary
Barrier Wall Alignment Report
American Chemical Service, Inc.
Griffith, Indiana

Soil	Sample	Coord	inates	Sample	Liquid	Plasticity	Gravel	Sand	P200		
Boring	Number	Northing	Easting	Depth	Limit	Index	Content	Content	Content	USCS	Permeability
Number				(ft)	(%)	(%)	(%)	(%)	(%)		(cm/s)
SB-212	SS4	5759	5454	7-9	NA	NA	0.0	86.9	_13.1	SM	NA
SB-212	SS9	5759	5454	17-19	NA	NA _	5.5	87.1	7.4	SW-SM	NA
SB-215	SS5	6126	5615	9-11	NA	NA	4.0	87.5	8.5	SP-SM	NA NA
SB-215	SS10	6126	5615	19-21	NA	NA	19.8	76.5	3.7	SP	NA
SB-217	SS4	6444	5603	7-9	NA	NA	32.4	62.1	5.5	SP-SM	NA
SB-217	SS10	6444	5603	19-21	NA_	NA	0.9	83.9	15.2	SM	NA
SB-206	SS4	5856	5013	7-9	NA	NA	0.2	92.0	7.8	SP-SM	NA
SB-206	SS7	5856	5013	13-15	NA	NA	0.0	90.9	9.1	SP-SM	NA
SB-151	SS5	6764	5890	9-11	NA	NA _	14.2	82.4	3.4	SP	NA
SB-151	SS7	6764	5890	13-15	NA	NA	9.2	87.6	3.2	SP	NA
SB-152	SS3	6607	5819	5-7	NA	NA	5.7	87.2	7.1	SP-SM	NA
SB-152	SS10	6607	5819	19-21	NA	NA	11.5	76.3	12.2	SM	NA
SB-221	SS2	6354	5138	3-5	NA	NA	0.0	90.5	9.5	SP-SM	NA
SB-221	SS5_	6354	5138	9-11	NA	NA	0.2	87.5	12.3	SM	NA
SB-109	SS3	7027	5308	5-7	NA	NA	0.0	96.6	3.4	SP	NA
SB-109	SS8	7027	5308	15-17	NA	NA	11.4	80.6	8.0	SP-SM	NA
SB-136	SS2	6904	5146	3-5	NA	NA	2.0	93.0	5.0	SP-SM	NA
SB-136	SS6	6904	5146	11-13	NA	NA	4.2	88.4	7.4	SP-SM	NA
SB-113	SS5	7066	5422	9-11	NA	NA	0.5	92.3	7.2	SP-SM	NA
SB-113	SS6	7066	5422	11-13	NA	NA	8.4	88.0	3.6	SP	NA
SB-112	SS5	6935	5576	9-11	NA	NA	8.1	74.9	17.0	SM	NA
SB-112	SS8	6935	5576	15-17	NA	NA	0.4	95.0	4.6	SP	NA
SB-109	ST	7027	5308	19-21	30	14	1.9	7.9	90.2	CL	1.70E-08
SB-151	ST	6764	5890	23-25	29	11	0.9	12.1	_87.0	ar.	2.00E-08
SB-206	ST	5856	5013	25.5-27.5	28	12	3.3	14.3	82.4	CL	1.80E-08
SB-212	ST	5759	5454	29-31	28	11	0.7	10	89.3	RP	2.40E-08

Notes:

ST = Shelby tube sample

NA = Test not applicable to this sample

j w077\0075\TARLE3 XLS TABA#VLAB 3/29/96

(

Table 4

Schedule for Barrier Wall Construction

American Chemical Services, Inc.

Griffith, Indiana

Deliverable/Event	Proposed Due Date	Comment
Submit Barrier Wall Alignment Report to EPA	1-Apr-96	
Approval of Alignment Report / Authorization to Proceed	21-Apr-96	20 Days after submitting report
Receive Proposals from Subcontractors	9-May-96	
Select Subcontractor and Barrier Technology	29-May-96	
Submit "50% Design" Document to U.S. EPA	19-Jun-96	59 days after Approval of Alignment Report
U.S. EPA provides Review Comments on "50 Design"	19-Jul-96	30 days after receiving 50% Design
Submit 100% Design to EPA	12-Aug-96	24 days after EPA Receipt of Comment
Receive EPA Approval of 100% Design	26-Aug-96	EPA reviews Final Design in 14 Days
Complete Barrier Wall Construction	1-Feb-97	159 days after EPA Approval of Design

Note:

Dates after April 1, 1996 are based on assumed EPA review times.

SB137-SB1416 **9**58123 SB144 SB140* SB112 •SB126 SB136* SB139* SB131e -SB128 SB/10• •SB151 SB1320 SB120 • SB223 SB135 SB129 \$8119 • SB118 \$8138 SB130 • SB219 ●SB218¥ ◆ SB220 ·S8217 • SB221 \$8216 SB222+ **●58215** SB202A* **•**SB203 ●SB204 SB205A* • SB205 58206 • SB207 -SB212 SB208 • SB209 4.5 • SB210 S8201® *SB211 - •SB213

PILOT TEST CELL SB222 BARRIER WALL SOIL BORING LOCATION AND NUMBER RAILROAD TRACK --- TOPOGRAPHIC CONTOUR

NOTES

- BASE MAP DEVELOPED FROM AN AERIAL SURVEY MAP OF THE SITE FLOWN ON MARCH 8, 1994 BY GEONEX CHICAGO AERIAL SURVEY, INC.
- 2. VERTICAL DATUM IS U.S.G.S. DATUM, CONTOUR INTERVAL IS 2 FEET.
- SOIL BORINGS PERFORMED JANUARY 17, 1996 THROUGH FEBRUARY 12, 1996, BY ENVIRONMENTAL AND FOUNDATION DRILLING.
- SOIL BORING ELEVATIONS AND LOCATIONS SURVEYED ON FEBRUARY 12 AND 16, 1996, BY AREA SURVEY.


200 400 SCALE IN FEET

FIGURE

3/28/96

OLF.

4077.0075 **B1** MISON



PILOT TEST CELL

. SB222 BARRIER WALL SOIL BORING LOCATION AND NUMBER

ZCZZZZZZZ APPROXIMATE LOCATION OF BARRIER WALL

RAILROAD TRACK

--- TOPOGRAPHIC CONTOUR

NOTES

- 1. BASE MAP DEVELOPED FROM AN AERIAL SURVEY MAP OF THE SITE FLOWN ON MARCH 8, 1994 BY GEONEX CHICAGO AERIAL SURVEY, INC.
- 2. VERTICAL DATUM IS U.S.G.S. DATUM. CONTOUR INTERVAL IS 2 FEET.
- 3. FINAL BARRIER WALL LOCATION IS BASED ON RESULTS OF SOIL BORING PROGRAM.
- SOIL BORINGS PERFORMED JANUARY 17, 1996 THROUGH FEBRUARY 12, 1996, BY ENVIRONMENTAL AND FOUNDATION DRILLING.
- SOIL BORING ELEVATIONS AND LOCATIONS SURVEYED ON FEBRUARY 12 AND 16, 1996, BY AREA SURVEY.




FIGURE 2

BARRER WALL ALGHNENT INVE BARRER WALL ALGHNENT INVE AMERICAN CHEMICAL SERVICE, IN PL SITE GRIFFITH, INDIANA

₽ P.V

Drowing Number 4077.0075 B2 MONTGOMERY WASSON

WATER OF

SB141 SB140 SB139 _ SB131 SB223 ◆ 5B220 SB221 SB216 SB222 SB202A SB203 SB204 SB205A+ SB205 SB206 SB207 58208 SB209 SB210

PILOT TEST CELL

S8222 BARRIER WALL SOIL BORING LOCATION AND NUMBER

RALROAD TRACK

TOPOGRAPHIC CONTOUR

CROSS SECTION LOCATION


NOTES

- 1. BASE MAP DEVELOPED FROM AN AERIAL SURVEY MAP OF THE SITE FLOWN ON MARCH 8, 1994 BY GEONEX CHICAGO AERIAL SURVEY, INC.
- 2. VERTICAL DATUM IS U.S.G.S. DATUM. CONTOUR INTERVAL IS 2 FEET.
- SOIL BORINGS PERFORMED JANUARY 17, 1996 THROUGH FEBRUARY 12, 1996, BY ENVIRONMENTAL AND FOUNDATION DRILLING.
- SOIL BORING ELEVATIONS AND LOCATIONS SURVEYED ON FEBRUARY 12 AND 16, 1996, BY AREA SURVEY.



FIGURE 3

4077.0075 B3 MONTGOMETY WATSON



SB224 PILOT TEST CELL SOIL BORING LOCATION AND NUMBER

RAILROAD TRACK

TOPOGRAPHIC CONTOUR

NOTES

- BASE MAP DEVELOPED FROM AN AERIAL SURVEY MAP OF THE SITE FLOWN ON MARCH 8, 1994 BY GEONEX CHICAGO AERIAL SURVEY, INC.
- 2. VERTICAL DATUM IS U.S.G.S. DATUM. CONTOUR INTERVAL IS 2 FEET.
- SOIL BORINGS PERFORMED JANUARY 17, 1996 THROUGH FEBRUARY 12, 1996, BY ENVIRONMENTAL AND FOUNDATION DRILLING.
- SOIL BORING ELEVATIONS AND LOCATIONS SURVEYED ON FEBRUARY 12 AND 16, 1996, BY AREA SURVEY.





FIGURE 6


PILOT TEST CELL BOIL BORING LOCATIC BARRIER WALL ALIGNMENT INVESTIGATI AMERICAN CHEMICAL SERVICE, INC. NPL SITE

4077.0075 **B4**

Drown By DIF, LCL

FIGUR





LEGEND

- SAND WITH LOW SILT AND CLAY CONTENT (SP OR SW), MAY ALSO INCLUDE SW-SM, SW-SC, SP-SM AND SP-SC
- SILTY SAND (SM), MAY ALSO INCLUDE SP-SM AND SW-SM
- SAND AND GRAVEL WITH LOW SILT AND CLAY CONTENT (SP/GP OR SW/GW), MAY ALSO INCLUDE SW-SM/GW-GM, SW-SC/GW-GC, SP-SM/GP-GM, AND SP-SC/GP-GC
- SAND AND GRAVEL, SOME SILT (SM/GM), MAY ALSO INCLUDE SW-SM/GW-GM, SP-SM/GP-GM AND SM/GM
- TOPSOI
- FILL
- REFUSE
- SILT, NON-PLASTIC OR LOW PLASTICITY (ML)
- SILTY CLAY, LOW PLASTICITY (CL-ML)
- LEAN CLAY, MODERATE PLASTICITY (CL)
- · —

 WATER TABLE

NOTES


- 1. THE STRATUM LINES ARE BASED ON INTERPOLATION BETWEEN BORINGS AND MAY NOT REPRESENT ACTUAL SUBSURFACE CONDITIONS.
- 2. FOR THE PURPOSE OF ILLUSTRATING SUBSOIL CONDITIONS ON THE CROSS SECTIONS, SOME OF THE BORING LOGS HAVE BEEN SIMPLIFIED. FOR A DETAILED DESCRIPTION OF SUBSURFACE CONDITIONS AT INDIVIDUAL BORINGS, REFER TO SOIL BORING LOGS, APPENDIX B OF TEXT.
- HORIZONTAL DISTANCES ARE MEASURED WITH RESPECT TO THE CENTER OF EACH SOIL BORING LOCATION.
- 4. EXISTING GROUND SURFACE WAS TAKEN FROM DRAWING 4077.0075-B3, FIGURE 3.
- 5. ELEVATIONS ARE SHOWN IN REFERENCE TO U.S.G.S. DATUM.
- 6. WATER TABLE ELEVATIONS ARE AN AVERAGE WATER LEVEL THAT WAS CALCULATED FROM WATER LEVELS OBSERVED DURING THE RI FROM AUGUST 17, 1989 TO SEPTEMBER 13, 1990.
- 7. SOIL BORINGS PERFORMED JANUARY 17, 1996 THROUGH FEBRUARY 12, 1996, BY ENVIRONMENTAL AND FOUNDATION DRILLING.
- 8. SOIL BORING ELEVATIONS AND LOCATIONS SURVEYED ON FEBRUARY 12, AND 16, 1996, BY AREA SURVEY.

CROSS SECTION SCALE

O 100 200

SCALE IN FEET

VERTICAL EXAGGERATION: TWENTY TIMES




LEGEND

- SAND WITH LOW SILT AND CLAY CONTENT (SP OR SW), MAY ALSO INCLUDE SW-SM, SW-SC, SP-SM AND SP-SC
- SILTY SAND (SM), MAY ALSO INCLUDE SP-SM AND SW-SM
- SAND AND GRAVEL WITH LOW SILT AND CLAY CONTENT (SP/GP OR SW/GW), MAY ALSO INCLUDE SW-SM/GW-GM, SW-SC/GW-GC, SP-SM/GP-GM, AND SP-SC/GP-GC
- SAND AND GRAVEL, SOME SILT (SM/GM), MAY ALSO INCLUDE SW-SM/GW-GM, SP-SM/GP-GM AND SM/GM
- TOPSOIL
- FILL
- REFUSE
- SILT, NON-PLASTIC OR LOW PLASTICITY (ML)
- SILTY CLAY, LOW PLASTICITY (CL-ML)
- LEAN CLAY, MODERATE PLASTICITY (CL)
- water table

NOTES

- THE STRATUM LINES ARE BASED ON INTERPOLATION BETWEEN BORINGS AND MAY NOT REPRESENT ACTUAL SUBSURFACE CONDITIONS.
- FOR THE PURPOSE OF ILLUSTRATING SUBSOIL CONDITIONS ON THE CROSS SECTIONS, SOME OF THE BORING LOGS HAVE BEEN SIMPLIFIED. FOR A DETAILED DESCRIPTION OF SUBSURFACE CONDITIONS AT INDIVIDUAL BORINGS, REFER TO SOIL BORING LOGS, APPENDIX B OF TEXT.
- 3. HORIZONTAL DISTANCES ARE MEASURED WITH RESPECT TO THE CENTER OF EACH SOIL BORING LOCATION.
- 4. EXISTING GROUND SURFACE WAS TAKEN FROM DRAWING 4077.0075-B3, FIGURE 3.
- 5. ELEVATIONS ARE SHOWN IN REFERENCE TO U.S.G.S. DATUM.
- WATER TABLE ELEVATIONS ARE AN AVERAGE WATER LEVEL THAT WAS CALCULATED FROM WATER LEVELS OBSERVED DURING THE RI FROM AUGUST 17, 1989 TO SEPTEMBER 13, 1990.
- 7. SOIL BORINGS PERFORMED JANUARY 17, 1996 THROUGH FEBRUARY 12, 1996, BY ENVIRONMENTAL AND FOUNDATION DRILLING.
- 8. SOIL BORING ELEVATIONS AND LOCATIONS SURVEYED ON FEBRUARY 12, AND 16, 1996, BY AREA SURVEY.



CROSS SECTION SCALE

5

0

100

200

SCALE IN FEET

VERTICAL EXAGGERATION: TWENTY TIMES

FIGURE 5

t

A AREA SURVEY REPORT

11340 West 159th Street Orland Park, Illinois 60462 • Phone (708) 349-7364 • FAX (708) 349-7372

MARCH 20, 1996

MR. DAVID PIECZYNSKI MONTGOMERY WATSON

ENCLOSED PLEASE FIND THE SOIL BORING REPORT FOR AMERICAN CHEMICAL SERVICES IN GRIFFITH, IND.

ON MARCH 20, 1996, THIS REPORT WAS FAXED TO KEITH SCHILING AT MONTGOMERY WATSON.

JAN

SOIL BORING LOCATION REPORT AMERICAN CHEMICAL SERVICES, INC. GRIFFITH, INDIANA

PAGE 1

BORING	NORTH	EAST	ELEVATION
101	6892.9	5253.7	637.9
102	6873.7	·5269.6	637.8
103	6855.1	5287.1	637.8
104	6838.3	5304.1	637.8
105	6817.9	5321.3	637.8
106	6802.1	5339.3	637.8
107	6782.4	5356.8	637.8
108	6764.6	5372.8	637.6
109	7027.3	5307.5	638.0
110	6751.9	5660.5	638.8
111	6688.6	5524.4	638.4
112	6935.0	5575.9	639.7
113	7065.9	5422.2	637.8
114	7072.6	5374.8	638.1
115	7071.4	5328.2	638.3
116	7045.4	5472.4	637.5
117	6929.2	5219.9	637.9
118	6721.5	5620.5	639.1
119	6708.8	5567.4	638.8
120	6742.0	5280.7	637.7
121	6673.0	5476.0	638.1
122	6971.7	5248.3	638.1
123	7001.1	5274.0	638.1
124	7023.1	5521.0	638.6
125	6855.0	5622.8	638.4
126	6907.2	5615.2	638.3
127	6960.9	5599.7	638.3
128	6803.1	5653.1	638.9

SOIL BORING LOCATION REPORT AMERICAN CHEMICAL SERVICES, INC. GRIFFITH, INDIANA

PAGE 2

BORING	NORTH	EAST	ELEVATION
129	6712.4	5268.4	636.9
130	6652.2	5448.6	637.9
131	6826.5	`5088.9	636.7
132	6756.4	5174.5	637.0
133	6670.7	5352.5	637.3
134	6667.5	5402.1	637.7
135	6737.0	5230.1	637.1
136	6903.5	5146.0	637.5
137	6985.7	5225.5	637.6
138	6636.5	5397.5	637.6
139	6865.6	5117.2	637.4
140	6956.3	5179.7	637.6
141	6999.3	5199.7	637.6
142	6885.6	5641.6	638.3
143	7078.6	5430.1	637.6
144	6996.0	5565.6	639.7
145	6797.4	5603.5	639.6
146	6783.8	5610.0	639.6
147	6777.3	5597.9	639.7
148	6785.2	5620.0	639.5
149	6833.6	5764.9	638.2
150	6452.9	5749.4	639.0
151	6763.8	5890.1	638.8
152	6606.8	5818.6	639.2
201	5674.8	4984.8	647.5
202	6059.9	5011.5	640.4
202A	6077.4	5014.5	639.9
203	6029.0	5011.5	641.0

SOIL BORING LOCATION REPORT AMERICAN CHEMICAL SERVICES, INC. GRIFFITH, INDIANA

PAGE 3

BORING	NORTH	EAST	ELEVATION
204	5964.5	5012.0	642.0
205	5913.8	5014.2	643.4
205A	5930.6	`4988.6	646.0
206	5856.2	5013.4	644.6
207	5801.1	4978.0	646.9
208	5763.9	4960.8	646.8
209	5715.5	4942.1	647.4
210	5690.0	4988.9	647.2
212	5758.7	5453.6	649.4
213	5637.8	5388.9	653.1
214	5946.4	5523.4	647.2
215	6126.2	5615.5	647.9
216	6325.7	5662.3	645.9
217	6444.1	5602.8	639.5
218	6517.4	5411.0	634.7
219	6606.9	5229.9	633.0
220	6496.9	5175.7	635.4
221	6353.9	5138.1	634.0
222	6223.4	5069.4	638.6
223	6729.8	5059.2	638.5
224	6197.5	5301.8	646.9
225	6208.5	5283.1	647.3
226	6192.7	5286.9	647.5
227	6212.0	5297.6	646.9

B1

SOIL BORING LOGS – PROPOSED FINAL ALIGNMENT



B1

SOIL BORING LOGS – PROPOSED FINAL ALIGNMENT



Depth to Cave in

transition may be gradual.

The stratification lines represent the approximate boundary between soil types and the

LOG OF TEST BORING

Project American Chemical Service, Inc.
Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No.
Job No.

SB109 4077,0075

638.0

Sheet

Drill Method 4 1/4" I.D. HSA

J\4077\Gint\40770_ID_CHICAGO

1 of 2

Surface Elevation Northing: 702

Northing: **7027.3** Easting: **5307.5**

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 **SAMPLE** SOIL PROPERTIES VISUAL CLASSIFICATION PID Rec. Mois-Depth and Remarks (ap) Value (ft.) (ppm) No. (in.) ture Remarks (tsf) Brown Fine SAND (SP), Trace Gravel 20 M/W Orange Brown, Fine SAND (SP), Grades into 4.0 1 5 Olive Gray Silt from 2 to 2.2 ft, Then into a Olive Gray Fine Sand, Sweet Musty Odor Present Dark Gray to Brown Stained Fine SAND and 25.0 2 20 M 8 SILT (SM), Grades into Dark Gray Stained Fine Sand at 4.5 ft Gray Stained Fine SAND (SP), Trace Organics (Roots), Musty odor Present 3 20 W 9 5.0 Brown Fine SAND (SP), Trace Silt, Grades into W 55.0 4 16 10 Gray Stained Fine Sand, Some Black Stained Layers, Musty Odor Present Gray Stained Fine SAND (SP) to 10.5 ft, 75.0 5 W 16 12 Grades into Gray Brown, Fine to Coarse SAND, Musty Odor Present 10 Gray Fine SAND (SP), Trace Silt and Clay, W 87.0 6 18 13 Fine to Coarse Sand at 12.5 to 13.0 ft W Gray Fine to Coarse SAND and GRAVEL 49.0 Field analysis 7 16 13 for VOCs and (SP/GP), Little Black Staining at 14.5 to 15.0 **PCBs** ft, Musty Odor Present **GENERAL NOTES** WATER LEVEL OBSERVATIONS ft. Upon Completion of Drilling ft. 1/19/96 End 1/19/96 Start While Drilling Rig CME 55 Time After Drilling Driller E&F Chief GH Logger DAP Editor **PMS** Depth to Water



LOG OF TEST BORING

Project American Chemical Service, Inc.
Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No.

SB109 4077.0075

Job No. Sheet

2 of 2

Surface Elevation 638.0

Northing:

7027.3 5307.5

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000

	S	AM	PLE		VISUAL CLASSIFICATION	SOIL	PROF	PERTIES
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
8	16	W	16	_	Gray, Fine to Coarse SAND and GRAVEL (SP/GP) to 16.0 ft, Grades into Gray Brown Fine Sand, Trace Silt and Clay, Musty Odor Present		14.0	
9	18	W/M		 	Gray, Fine to Coarse SAND (SP) from 17 to 17.5 ft, then Grades into Gray Brown Fine SAND, Musty Odor Present Hard, Gray Silty CLAY (CL-ML)	>4.0	64.0	
10	18	М		_				
				— 20— -	Hard, Gray Silty CLAY (CL-ML), Trace Fine to Coarse Sand, Fine Gravel			
					End of Boring at 21.0 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.			
				25-				
				30-				



LOG OF TEST BORING

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000

Project American Chemical Service, Inc.
Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No. SB113
Job No. 4077.0075
Sheet 1 of 2
Surface Elevation 637.8

Northing: **7065.9** Easting: **5422.2**

SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-PID Depth and Remarks (qa) No. (in.) ture Value (ft.) (ppm) Remarks (tsf) Brown Fine SAND and Fine to Coarse GRAVEL (GP) Brown Fine SAND (SP), Trace Medium to 0.0 20 M 6 Coarse Sand and Fine Gravel, Thin Gray Clayey Zone at 2.0 ft Black Fine SAND (SP), Some Silt, Organics 2 20 134.0 M 6 and Roots Present, Wood Chips from 2.6 to 2.7 ft. Sulfur and Solvent Odors Present Dark Gray to Black, Fine SAND (SP), Little 3 20 1285.0 5 Medium to Coarse Sand. Trace Fine Gravel. Solvent Odor Present Black/Gray, Fine to Coarse SAND (SP), Strong 4 20 $\overline{\mathbf{w}}$ 3875.0 Field analysis 11 Solvent Odor and Petroleum Sheen Present, for VOCs and Black Staining from 7.8 to 8.5 ft; Black Stained, **PCBs** Fine to Coarse Sand and Gravel from 8.1 to 9.0 Black and Gray-Brown, Petroleum Sheen 5 20 w 12 Field anslysis Stained, Fine to Coarse SAND (SP), Fine for VOCs and Gravel, Solvent Odor Present **PCBs** 10-Gray Stained, Fine to Coarse SAND and Fine 6 20 W 13 13.0 Gravel (SP) to 12.5 ft, Grades into Gray-Brown, Fine Sand, Solvent Odor Present Gray-Brown Fine SAND (SP), Trace Medium 7 20 W 0.0 10 to Coarse Sand and Fine Gravel, Slight Musty Solvent Odor Presnt WATER LEVEL OBSERVATIONS **GENERAL NOTES** Vhile Drilling ft. Upon Completion of Drilling Start 1/23/96 End 1/23/96 ime After Drilling Rig CME 55 Driller E&F Chief GH Logger DAP Depth to Water Editor **PMS** Drill Method 4 1/4" I.D. HSA Depth to Cave in

The stratification lines represent the approximate boundary between soil types and the transition may be gradual.

J:4977.Gint:40770_ID. UHICA3U



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No.

SB113 4077.0075

637.8

Job No. Sheet

2 of 2

Surface Elevation Northing:

7065.9

		<u> </u>			T	OO Corporate Drive, Addison, Illinois 60101, TEL. (708) 691	 1		
o.	Rec.	AM Mois-	N	Depth		VISUAL CLASSIFICATION and Remarks	SOIL qu (qs)	PID	PERTIES
В	20	W	Value 15	(ft.) - -		Gray-Brown Fine SAND (SP), Trace to Little, Medium to Coarse Sand, Fine Gravel, Slight Musty Odor	(tsf) 	(ppm) 67.0	Remarks
	22	W/M	17			Gray/Brown, Fine to Coarse SAND and GRAVEL (GP) Hard, Gray, Silty CLAY (CL-ML), Trace Fine to Coarse Sand	>4.5		PID reading sand PID reading clay
0				 - 20					,
				- - - - - - 25-		End of Boring at 20.0 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.			
				30-					



transition may be gradual.

LOG OF TEST BORING

Project American Chemical Service, Inc.
Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No. SB114
Job No. 4077.0075
Sheet 1 of 2
Surface Elevation 638.1

Northing: **7072.6** Easting: **5374.8**

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 **SOIL PROPERTIES** SAMPLE VISUAL CLASSIFICATION Rec. Mois-PID Depth and Remarks (qa) (in.) ture (ft.) (ppm) Value Remarks (tsf) Brown SAND and GRAVEL (GP) Dark Brown to Black Stained, Fine SAND and 498.0 14 M 6 SILT (SM), Organics (Roots) and Musty Solvent Odor Present Dark Gray to Black Stained, Fine SAND (SP), 22 M/W 904.0 Field analysis 2 Grades into Olive Gray Brown Fine SAND, for VOCs and Trace to Little Silt at 5 ft, Musty Solvent Odor **PCBs** Present 5 Gray Brown Fine SAND (SP), Trace Silt, 7 12 $\overline{\mathbf{w}}$ 8 66.0 Musty Solvent Odor Present Olive Gray Brown Fine SAND (SP), Trace 14 111.0 Field analysis 6 Medium to Coarse Sand and Silt, Musty Solvent for VOCs and Odor Present **PCBs** 10-Gray, Fine to Coarse SAND (SP), Trace Silt, 318.0 $\overline{\mathbf{w}}$ 9 16 Musty Odor Present Gray, Fine to Coarse SAND (SP), Trace Silt, 6 16 W 7 0.0 Musty Odor Present WATER LEVEL OBSERVATIONS **GENERAL NOTES** 7hile Drilling ft. Upon Completion of Drilling $\frac{T}{2}$ Start 1/23/96 End 1/23/96 E&F Chief GH .ime After Drilling Driller Rig CME 55 Logger DAP Depth to Water Editor **PMS** Drill Method 2 1/4" I.D. HSA Depth to Cave in The stratification lines represent the approximate boundary between soil types and the



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No.

SB114 4077.0075

638.1

Job No. Sheet

2 of 2

Surface Elevation

Northing: 7072.6 5374.8

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SOIL PROPERTIES SAMPLE VISUAL CLASSIFICATION Rec. Mois-Depth PID and Remarks (qa) (tsf) ture Value (ft.) (in.) (ppm) Remarks Gray Fine SAND (SP), Trace Medium to 18 W 12 34.0 Coarse Sand 1 in. Clay and Silt Lenses at 17 and 17.5 ft Gray Fine SAND (SP), Musty Odor Present to 19.3 ft 8 22 W/M 3282.0 Hard, Gray Silty CLAY (CL-ML) at 19.3 ft, >4.5 Trace Fine to Coarse Sand 9 6 M Hard, Silty CLAY (CL-ML), Trace Fine to >4.5 Blow-in sand on Coarse Sand top of clay in last spoon End of Boring at 22.0 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel. 25 30-



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No. Job No.

SB115 4077.0075

Sheet 1 of 2

Surface Elevation 638.3

Northing: 7071.4 5328.2 Easting:

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SOIL PROPERTIES SAMPLE VISUAL CLASSIFICATION Rec. Mois-Depth PID and Remarks (qa) No. 🖺 (in.) (ft.) ture Value (ppm) Remarks (tsf) Brown Sand and Gravel (FILL) 1 Brown Fine SAND (SP), Grades into Dark Gray 66.0 14 M 6 to Black Fine SAND (Stained), Trace Organics (Roots), Trace Small Pieces of Wood, Sweet Musty Odor Present Dark Gray Brown Fine SAND (SP), Trace 8 156.0 Field analysis 2 22 M Roots, Sweet Musty Odor Present for VOCs and **PCBs** 5-Dark Gray to Black Stained, Fine to Coarse 18 W 7 83.0 Field analysis SAND (SP), Trace Medium to Coarse Sand, for PCBs Sweet Musty Odor Present Grades into Brown, Fine to Coarse SAND (SP) 14 W 34.0 at 9.5 ft, Sweet Musty Odor Present 10-Gray, Fine SAND (SP), Trace Medium to $\overline{\mathbf{w}}$ 14 6 $7.\overline{0}$ Coarse Sand, Small Pieces of Wood from 12 to 12.5 ft, Sweet Musty Odor Present Grades into Gray Brown Fine to Coarse SAND 12 W 14 28.0 (SP) at 14.5 ft, Musty Odor Present WATER LEVEL OBSERVATIONS **GENERAL NOTES** Vhile Drilling ft. Upon Completion of Drilling 🛂 ft. Start 1/24/96 End 1/24/96 ime After Drilling Driller E&F Chief GH Rig CME 55 Logger DAP Editor Depth to Water **PMS** Drill Method 2 1/4" I.D. HSA Depth to Cave in The stratification lines represent the approximate boundary between soil types and the transition may be gradual.



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana Boring No. Job No.

SB115 4077.0075

2 of 2 Sheet Surface Elevation

638.3

Northing: 7071.4 5328.2

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SOIL PROPERTIES **SAMPLE** VISUAL CLASSIFICATION No. Rec. Mois-Depth PID and Remarks (qa) (tsf) ture Value (ft.) (ppm) Remarks (in.) Gray Brown, Fine to Coarse SAND (SP), Sweet 7 16 W 9 12.0 Musty Odor Present 18 W/M 12 9.0 Hard, Gray, Silty CLAY (CL-ML), Trace Fine to Coarse Sand and Fine Gravel >4.5 20 9 14 13 M >4.5 Hard, Gray Silty CLAY (CL-ML) End of Boring at 22.0 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel. 25-30-



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No.

SB116 4077.0075

Job No. Sheet

1 of 2

Surface Elevation

637.5

Northing: 7054.4 5472.4 Easting:

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SOIL PROPERTIES SAMPLE VISUAL CLASSIFICATION PID Rec. Mois-N Depth and Remarks (qa) No. Remarks (in.) (ppm) ture Value (ft.) (tsf) Gravel and Grav Slag, Some Brown Sand and Clay (FILL) 1 Dark Brown and Black Stained, Fine to Coarse 459.0 20 M 6 SAND (SP), Solvent Odor Present 20 M/W 6 7.0 Field analysis 2 Black Stained, Fine SAND (SP), Trace Silt and for VOCs and Organics (Roots) **PCBs** 5 Dark Gray to Black Stained, Fine SAND (SP), 38.0 Field analysis W 16 6 Grades to Gray-Brown at 7.0 ft, Solvent Odor for VOCs and Present **PCBs** Dark Gray, Fine to Coarse SAND and Fine 12 W 8 28.0 GRAVEL (SP), Black Staining at 9.8 to 10.0 ft, Solvent Odor Present 10-Grades into Gray/Brown, Fine to Coarse SAND 0.0 18 W 10 (SP), Little fine Gravel at 11.5 ft, Solvent Odor Present 1.0 Blow in 6 12 W 2 in. Thick Dark Gray, Fine to Coarse SAND and Fine GRAVEL (SP) Layer at 14 ft WATER LEVEL OBSERVATIONS **GENERAL NOTES** 1/24/96 End 1/24/96 'Vhile Drilling ft. Upon Completion of Drilling ft. Start Rig CME 55 Driller E&F Chief GH ime After Drilling Logger DAP Editor **PMS** Depth to Water Drill Method 2 1/4" I.D. HSA Depth to Cave in The stratification lines represent the approximate boundary between soil types and the transition may be gradual.



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No. Job No.

SB116 4077.0075

Sheet

2 of 2

Surface Elevation 637.5

Northing:

7054.4 5472.4

		W	V		21	Location Griffith, Indiana OO Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-50	Northing Easting:		54.4 72.4
No.	Rec.	Mois-	1	Depth	<u>'</u>	VISUAL CLASSIFICATION and Remarks	T	PID	PERTIES
7	20	W	Value	(ft.)		Gray/Brown Fine SAND (SP), Little to Some, Medium to Coarse Sand, Thin Clay Seam from 18.5 to 18.7 ft, Slight Musty Odor Present	(tsf) 	(ppm) 17.0	Remarks
8	22	М	11	- - - - 20-		Hard, Gray, Silty CLAY (CL-ML), Trace Fine to Coarse Sand and Fine Gravel	>4.5	17.0	PID from san
9				-		Sand Blow-in; Advanced Sampler Again Hard, Gray, Silty CLAY (CL-ML) End of Boring at 22.0 ft Borehole Backfilled with Bentonite Cement	>4.5		
				- 25- 		Grout. Topped with 6 inches of Gravel.			
				30 					



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon Location

Griffith, Indiana

Boring No.

SB123 4077.0075

638.1

Job No. Sheet

1 of 2

Surface Elevation Northing:

7001.1 5274.0

P4077:Gnt/40770_ID, CHICAGO =

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SOIL PROPERTIES SAMPLE VISUAL CLASSIFICATION Rec. Mois-Depth PID and Remarks (ap) No. (in.) ture (ft.) (ppm) Value Remarks (tsf) Brown Fine SAND and GRAVEL (SP/GP) 16 M/W 8 Brown Fine SAND (SP), Very Slight Solvent 7.0 Odor Present Grades into Gray Brown Fine SAND (SP), 366.0 Field anlaysis 2 18 6 Some Black Silty Fine Sand, Black Stained from for VOCs and 5 to 5.5 ft, Musty Propane Like Odor **PCBS** 5 Black Stained Fine SAND (SP), Sulfur Swampy 20 w 58.0 Field analysis 3 Odor (Rotten Egg Odor) for PCBs Dark Gray Fine SAND (SP), Slight Sulfur 37.0 4 10 w Swampy Odor 10-Grades into Gray, Fine to Coarse SAND (SP) at 73.0 W 5 10 11 ft, Slight Sulfur Odor Present Gray Fine SAND (SP), Grades into Gray, Fine 14 W 11 0.0 6 to Coarse Sand from 15 to 15.5 ft WATER LEVEL OBSERVATIONS GENERAL NOTES ft. Start 'Vhile Drilling ft. Upon Completion of Drilling 1/26/96 End 1/26/96 Rig CME 55 ime After Drilling Driller E&F Chief GH Logger DAP Editor **PMS** Depth to Water Drill Method 2 1/4" I.D. HSA Depth to Cave in

The stratification lines represent the approximate boundary between soil types and the transition may be gradual.



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No. Job No.

SB123 4077.0075

Sheet

2 of 2

Surface Elevation

638.1

Northing:

7001.1 5274.0

	S	AM.	PLE		VISUAL CLASSIFICATION	SOIL	. PROP	ERTIES
э.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tef)	PID (ppm)	Remarks
,	20	W	9	-			0.0	
	20	W/M	10	- - - 20	Gray, Fine to Coarse SAND and Fine GRAVEL (SP), Musty Odor Present Hard, Gray Silty CLAY (CL-ML), Trace Fine to Coarse Sand	 >4.5	5.0	
	8	М	13	- -	Hard Gray, Silty CLAY (CL-ML), Trace Fine to Coarse Sand	>4.5		
				- - - - 25-	End of Boring at 22.0 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.			
				- - - - - - - - -				



Depth to Cave in

The stratification lines represent the approximate boundary between soil types and the transition may be gradual.

LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No. SB124 Job No. 4077.0075 Sheet 1 of 2 Surface Elevation 638.6

Northing: 7023.1 5521.0

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SOIL PROPERTIES SAMPLE VISUAL CLASSIFICATION Rec. Mois-PID Depth and Remarks (qa) No. (in.) ture Value (ft.) (ppm) Remarks (tsf) Gravel and Gray Slag, Brown Fine Sand (FILL) Brown Fine SAND (SP), Grades into Dark 132.0 14 M 6 Brown to Black Fine Sand, Some Silt, Trace Organics, Small Gravel, Slight Solvent Odor Present Olive Gray Brown Fine SAND (SP), Slight 27.0 2 18 M/W Rusty Odor Present 5 Olive Gray Brown Fine SAND (SP), Black 247.0 Field analysis 3 W 18 8 Stained from 7 to 7.3 ft, Gray Stained from 7.3 for PCBs to 7.6 ft, Brown Fine Sand at 7.6 ft, Musty Odor Present Brown Fine SAND (SP), Grades into Dark W 198.0 Poor recovery, 4 Gray, Fine to Coarse SAND and GRAVEL at field analysis 10 ft, Musty Oily Odor Present for PCBs 10-Field analysis 5 20 $\overline{\mathbf{w}}$ Gray, Fine to Coarse SAND and GRAVEL 512.0 (GP), Grades into Brown, Fine to Coarse for VOCs SAND and GRAVEL at 12 ft, Sweet Musty Odor present 65.0 $\overline{\mathbf{w}}$ 9 Gray Brown, Fine to Coarse SAND (SP), Trace 14 6 Medium to Coarse Sand, Sweet Musty Propane Like Odor Present WATER LEVEL OBSERVATIONS **GENERAL NOTES** While Drilling ft. Upon Completion of Drilling Ψ ft. Start 1/26/96 End 1/26/96 Time After Drilling Driller E&F Chief GH Rig CME 55 Depth to Water DAP Editor **PMS** Logger Drill Method 2 1/4" I.D. HSA



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon Location

Griffith, Indiana

Boring No. Job No.

SB124 4077.0075

638.6

Sheet 2 of 2 Surface Elevation

Northing: 7023.1 5521.0

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000

_					2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-50	-		
	S	AM.	PLE		VISUAL CLASSIFICATION		. PROF	PERTIES
No.	Rec. (in.)		N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
7	18	w	13		Gray, Fine to Coarse SAND (SP), Little Fine Gravel, Grades into Gray Brown Fine Sand at 17 ft, Sweet Musty Propane-Like Odor Present		50.0	
8	22	М			Hard, Gray Silty CLAY (CL-ML), Trace Fine to Coarse Sand	>4.5		
					End of Boring at 20.5 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.			
				30-				



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No. Job No.

SB126 4077.0075

Sheet

1 of 2

Northing:

Surface Elevation 638.3 6907.2

/			w	ν 		2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-500	Easting:	5615	5.2
		S	٩M	PLE		VISUAL CLASSIFICATION	T	PROF	PERTIES
No.		ec. n.)	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
						Gravel and Gray Slag, Brown Fine Sand (FILL)			
1	1	16	M	8		Gray Brown, Fine to Coare SAND and Fine GRAVEL (SP/GP), Grades into Brown Fine Sand, Slight Solvent Odor Present		475.0	
2	1	.6	M	8	- 5-	Olive Gray Brown Fine SAND (SP), Grades into Fine to Coarse Sand, Gravel at 5.0 to 5.5 ft, Solvent Odor Present		604.0	Field analysis for VOCs
3	1	4 1	M/W	5		Olive Gray to Black Stained, Fine to Coarse SAND (SP), Little Fine Gravel, Solvent Odor Present		394.0	
4		0	W	1/24"	- - - - 10-	No Recovery			
5	1	2	W	7		Brown SAND and GRAVEL (SP/GP), Oily Stained Zone at 11.5 ft, Grades into Olive Brown, Fine to Coarse Sand and Gravel to 12.5 ft then into Gray Fine Sand (Solvent-Oily Odor Throughout Sample Interval)			Field analysis for VOCs and PCBs
6	1	4	W	6	- 15	Dark Brown Fine SAND (SP), Sweet Musty Propoane-Like Odor Present		132.0	
				W	ATE	LEVEL OBSERVATIONS GI	ENERAL	NOT	ES
D	ime A epth epth The s	Afte to to	lling er Dri Water Cave	in	represen	. Upon Completion of Drilling ft. Start 1/29 Driller E 8 Logger DA Drill Method	P Edito	r PMS	6 Rig CME 55



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No. Job No.

SB126 4077.0075

Sheet

2 of 2 Surface Elevation 638.3

Northing:

6907.2

5615.2 Easting:

					21	00 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-50	000 Lasung.		
			PLE			VISUAL CLASSIFICATION		-T	PERTIES
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)		and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
7	22	w	10			Gray Brown to Gray, Fine to Coarse SAND and Fine GRAVEL (SP/GP), Grades into Gray Brown Fine Sand at 18.0 ft, Sweet Musty Odor Present		627.0	
8	22	W/M	11	- - - - 20-		Gray, Fine to Coarse SAND (SP/GP), Gravel, Little Silt and Clay, Musty Odor Hard, Gray Silty CLAY (CL-ML), Trace Fine	4.0 >4.5	17.0	
9	16	М	18	-		to Coarse Sand at 19.5 ft Hard Silty CLAY (CL-ML)	>4.5		
				-		End of Boring at 22.0 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.			
				- 25 - -					
						•			
				30-					
		1	!	•			† :		



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No.

SB127 4077.0075

Job No. Sheet

1 of 2

Surface Elevation

638.3 6960.9

Northing: Easting:

5599.7

J/4077/Gint/40770_ID_CHICAGO . ..

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-Depth PID and Remarks (qa) (tsf) (in.) ture Value (ft.) (ppm) Remarks Gravel and Gray Slag (FILL) Black to Dark Gray Brown, Fine SAND (SP), 271.0 1 24 M 5 Sweet Musty Odor (Propane-Like) No Recovery, Brown Oily Sheen on Sampler 2 24 M 1/24" 494.0 5-No Recovery Field analysis 995.0 M/W 24 24 for PCBs Brown Oily Stained, Fine to Coarse SAND 4 2 1086.0 Sheen (SP), Some Medium to Coarse Sand and Fine Gravel, Sheen, Varnish Odor Present Field analysis 10for VOCs and **PCRs** Brown, Fine to Coarse SAND (SP), Some 1305.0 Sheen 5 Black to Dark Gray Staining, Trace Fine Gravel, Solvent Odor, Sheen Brown, Fine to Coarse SAND (SP), Grades into w 7 1051.0 Sheen 6 Brown Fine Sand, Solvent Odor WATER LEVEL OBSERVATIONS **GENERAL NOTES** ft. Start 1/29/96 End 1/29/96 Vhile Drilling ft. Upon Completion of Drilling 🛂 Driller E&F Chief ime After Drilling GH Rig CME 55 Depth to Water Logger DAP Editor **PMS** Drill Method 2 1/4" I.D. HSA Depth to Cave in The stratification lines represent the approximate boundary between soil types and the transition may be gradual.



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana Boring No. Job No.

SB127 4077.0075

Sheet

2 of 2

Surface Elevation

638.3

Northing:

6960.9 5599.7

		Ū	リ		21	Location Griffith, Indiana 00 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-500	Northing: Easting: 	5599	
_	S	ΑM	PLE			VISUAL CLASSIFICATION	SOIL	PROP	ERTIES
lo.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)		and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
•		W	10	- -		Brown Fine SAND (SP), Solvent Odor Present		994.0	
		W/M	13	-		Very Stiff, Gray Silty CLAY (CL-ML)		3.0	
				- 20- - -					
				-		End of Boring at 22.0 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.			
				— 25 —					
				- - -					
				 - 30–					
		1		-					



transition may be gradual.

LOG OF TEST BORING

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000

Project American Chemical Service, Inc.
Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No.

SB127

Job No. Sheet

1 of 2

Surface Elevation 638.3

Northing:

6960.9

_.1077/Gint.40770 ID, CHICAGO ...

Easting: **5599.7**

SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-PID Depth and Remarks (qa) (in.) ture No. Value (ft.) (ppm) Remarks (tsf) Gravel and Gray Slag (FILL) 1 24 Black to Dark Gray Brown, Fine SAND (SP), 271.0 M 5 Sweet Musty Odor (Propane-Like) No Recovery, Brown Oily Sheen on Sampler 2 24 M 1/24" 494.0 5-No Recovery 24 M/W 24 Field analysis 995.0 for PCBs Brown Oily Stained, Fine to Coarse SAND W 2 1086.0 4 Sheen (SP), Some Medium to Coarse Sand and Fine Gravel, Sheen, Varnish Odor Present Field analysis 10for VOCs and PCBs. Brown, Fine to Coarse SAND (SP), Some 5 W 5 1305.0 Sheen Black to Dark Gray Staining, Trace Fine Gravel, Solvent Odor, Sheen Brown, Fine to Coarse SAND (SP), Grades into 6 1051.0 Sheen Brown Fine Sand, Solvent Odor 15-WATER LEVEL OBSERVATIONS **GENERAL NOTES** 1/29/96 ft. Upon Completion of Drilling Start 1/29/96 End Vhile Drilling Rig CME 55 ime After Drilling Driller E&F Chief GH **PMS** Depth to Water Logger DAP Editor Drill Method 2 1/4" I.D. HSA Depth to Cave in The stratification lines represent the approximate boundary between soil types and the



LOG OF TEST BORING

Project American Chemical Service, Inc.
Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No.
Job No.
Sheet

Surface Elevation 638.3

Northing: **6960.9** Easting: **5599.7**

_					00 Corporate Drive, Addison	, Illinois 60101, TEL. (708) 691-	5000		
			PLE	,	VISUAL CLA	SSIFICATION			PERTIES
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)	and R	lemarks	qu (qa) (tsf)	PID (ppm)	Remarks
7		W	10		Brown Fine SAND (SP), Solvent Odor Present		994.0	
8		W/M	13	- - - - 20-	Very Stiff, Gray Silty C	CLAY (CL-ML)		3.0	
9						22.0.0			
					End of Bori Borehole Backfilled with Grout. Topped with 6 in				
				-					
				- - - - 30-					
				-					



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No.

SB131 4077.0075

Job No. Sheet

1 of 2

Surface Elevation 636.7

Northing:

6826.5

SAMPLE					VISUAL CLASSIFICATION	SOIL PROPERTIES			
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks	
					Gravel and Gray Slag (FILL)				
l	4	М	4	- -	Dark Brown to Black Fine SAND (SP), Piece of Slag in Spoon, Poor Recovery		6.0		
2	18	M	10	- 5-	Dark Brown to Dark Gray Brown Fine SAND (SP), Little Medium to Coarse Sand and Fine Gravel, Trace Roots and Silt		9.0		
3	16	W	9	-	Black Stained Fine SAND (SP), Grades to Brown to Gray Brown Fine Sand, Slight Musty Odor		3.0	Field analysis for PCBs	
4	14	W	6	 - - - 10	Dark Gray to Gray Fine SAND (SP), Trace Silt, Trace Roots (Organic Matter), Slight Sulfur Odor Present		11.0		
5	18	w	7		Dark Gray Fine SAND (SP), Silty Clay Seam from 12.0 to 12.5 ft, Grades into Fine to Caorse Sand and Gravel, Silty and Clay at 12.5 ft, Slight Sweet Musty Odor Present		5.0		
6	14	W	11	-	Gray Brown Fine SAND (SP), Trace Fine to Coarse Gravel, Sweet Propane-Like Odor Present		140.0	Field analysis for VOCs	
	1	l	W	– 15– ATFI	LEVEL OBSERVATIONS	GENERA	AL NO	TES	
. ir De	nile Dr ne Aft pth to pth to	er Dr Wate	<u>¥</u> illing r		. Upon Completion of Drillingft. Start Driller Logger	1/31/96 End E & F Chi DAP Edi ethod 2 1/4"	i 1/31/ ef GH tor PM:	96 Rig CME 5	



LOG OF TEST BORING

Project American Chemical Service, Inc.
Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No.
Job No. 4

4077.0075

SB131

636.7

Sheet

2 of 2

Surface Elevation Northing: 682

6826.5

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 5088.9 SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-Depth PID and Remarks (qa) ture Value (ft.) (ppm) Remarks (tsf) Gray Fine SAND, Grades into Gray, Fine to W 8 98.0 14 Coarse Sand to 17.0 ft, Sweet Musty Odor, Clay in Tip of Spoon at 18.0 ft Very Stiff, Gray Silty CLAY (CL-ML), Trace Fine to Coarse Sand 8 22 W 10 3.0 3.5 End of Boring at 20.5 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel. 25-30-



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No. Job No.

SB136 4077,0075

1 of 2 Sheet

Surface Elevation 637.5 6903.5

Northing: 5146.0

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 **SAMPLE** SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-PID Depth and Remarks (**a**p) (ft.) (in.) ture Value (ppm) Remarks (tsf) Gravel and Gray Slag, Fine Sand (FILL) 12 Black Fine SAND and SILT (FILL), Small 0.0 1 20 M Pieces of Wood, Grades into Olive Gray Brown Fine SAND at 2.5 ft, Musty Odor Present 2 20 M/W 0.0 Gray Brown Fine SAND (SP), Some Black Staining, Some Black Silt at 4 to 4.5 ft, Musty Odor Present Field analysis 3 22 W 6 Dark Gray Brown to Black Stained, Fine SAND 10.0 for PCBs (SP), Slight Musty Odor Present Gray Brown Fine SAND (SP), Trace Black $\widetilde{\mathbf{W}}$ 4 20 6 11.0 Staining, Slight Musty Odor Present Dark Gray, Fine to Coarse SAND (SP), Little 5 W 4.0 20 Silt and Clay, Silt and Clay Lense from 11 to 11.5 ft, Dark Gray Fine to Coarse Sand and 10-Gravel, Slight Musty odor Present Gray, Fine to Coarse SAND and Fine 20 14 22.0 6 GRAVEL (SP), Some Silt, Slight Musty Odor Present Gray, Fine to Coarse SAND (SP), Grades into 7 22 W 13 15.0 Gray Brown Fine Sand at 14.0 ft WATER LEVEL OBSERVATIONS GENERAL NOTES 2/5/96 ft. Upon Completion of Drilling 2/1/96 End Vhile Drilling ft. Start Rig CME 55 GH . ime After Drilling E&F Chief Driller **PMS** Depth to Water Logger DAP Editor Drill Method 4 1/4" I.D. HSA Depth to Cave in

The stratification lines represent the approximate boundary between soil types and the transition may be gradual.

J:4077:Gint:40778 (C. CHICAGE ...



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No. Job No.

SB136 4077.0075

Sheet

2 of 2

Surface Elevation Northing: 6903

tion 637.5 6903.5

Easting: **5146.0**

					210	00 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-500	0		
	SAMPLE					VISUAL CLASSIFICATION		PERTIES	
No.	Rec.	Mois- ture	1	Depth (ft.)		and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
8	22	W	13			Gray Brown, Fine to Coarse SAND (SP) to 16.5 ft, Then into Gray Brown Fine Sand, Sweet Propane Like Odor Present		109.0	
9	22	W/M	12	 - _		Gray Brown, Fine to Coarse SAND (SP), Solvent Like Odor Present	>4.5	1012.0	Field analysis for VOCs
	- 10			_		Very Stiff to Hard, Gray Silty CLAY (CL-ML) Hard, Gray, Silty CLAY (CL-ML), Trace Fine			
10	18	М	14	- 20-		to Coarse Sand and Gravel	>4.5	4.0	
						End of Boring at 20.5 ft			!
				_		Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.			
				<u> </u>			ļ		
				_ 25_					
									1
				— 30— -					
1				-					
			!			!		;	



LOG OF TEST BORING

Project American Chemical Service, Inc.
Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No.

SB139 4077,0075

637.4

Job No.
Sheet

1 of 2

Surface Elevation

Northing:

6865.6

Easting: 5117.2 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000

	S	AM	PLE		VISUAL CLASSIFICATION	SOIL	PROF	PERTIES
No.	Li .	Mois-	N Value	Depth (ft.)	and Remarks	qu (qa)	PID (ppm)	Remarks
					Gray Slag and Gravel (FILL)	(tsf)	· · ·	
1	6	М	26		Gray Brown Fine SAND (SP), Over Black Silt and Fine Sand, Trace Fine to Coarse Gravel, No Odors Present		0.0	
2	18	M	10		Light Brown Fine SAND (SP), Trace Fine Gravel, Very Slight Musty Odor Present		104.0	
3	20	w	7		Dark Gray to Black Stained, Fine SAND (SP), Musty Sulfur Odor Present		113.0	Field analysis for PCBs
4	20	w	5	-	Black Fine SAND (SP), Musty Sulfur Odor Present		198.0	
5	16	w	6		Dark Gray Fine SAND (SP), Grades into Fine to Coarse SAND at 12.0 ft, Musty Sulfur Odor Present		101.0	
6	16	W	7		Gray, Fine to Coarse SAND (SP), Grades into Gray Brown Fine Sand, Musty Propane-Like Odor Present		30.0	
		L	W	I.	LEVEL OBSERVATIONS G	ENERAL	NOT	ES
∵ir De De	nile Dr ne Aft pth to pth to	ter Dr Wate Cave	<u></u> illing r in		Upon Completion of Drillingft. Start 2/ Driller E Logger D	5/96 End & F Chief OAP Editor od 2 1/4" I.	r PMS	Rig CME 55

The stratification lines represent the approximate boundary between soil types and the transition may be gradual.



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No. Job No.

SB139 4077.0075

637.4

Sheet

2 of 2

Surface Elevation Northing:

6865.6

J	AM	PLE		VISUAL CLASSIFICATION		SOIL PROPERTIES				
	Mois-	N Value	Depth	and Remarks		qu (qa) (tsf)	PID (ppm)	Remarks		
7 20	w	8		Gray Brown Fine SAND (SP), Musty Propar Like Odor Present	ne		434.0	Field analysi for VOCs		
8 24	M	13		Very Stiff to Hard, Gray, Silty CLAY (CL-ML), Trace Fine to Coarse Sand and Gravel at 18.5 ft						
				End of Boring at 20.5 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.						



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No.

SB140 4077.0075

Job No. Sheet

1 of 2

637.6 Surface Elevation

Northing:

6956.3 5179.7

	S	AM	PLE		VISUAL CLASSIFICATION	SOIL	PRO	PERTIES
No.	Rec.	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
					Gray Slag and Gravel (FILL)	(1017		
1	12	М	8	_	Gray Brown Fine SAND (SP), Grades into Dark Brown Fine Sand at 2.5 ft		0.0	
2	20	M	5	- 5-	Dark Brown to Black Fine SAND (SP) and Silt, Trace Organics, Grades into Brown Fine Sand, Slight Musty Odor Present		0.0	
3	18	w	7	-	Dark Gray Fine SAND (SP), Musty Odor Present, Trace Roots		10.0	Field analysis for VOCs
4	16	w	4	- - - - - 10-	Dark Brown to Black Stained (Creosote Like Odor), Fine SAND (SP) to 9.5 ft, Grades into Light Gray Brown, Fine to Coarse Sand, Musty Odor Present		5.0	Field analysis for PCBs
5	16	w	6	_	Gray Brown Fine SAND (SP), Grades into Gray Fine to Coarse Sand and Fine Gravel at 12.5 ft, Sweet Musty Odor Present		9.0	
6	16	W	6		Gray Brown Fine SAND (SP), Trace Medium to Coarse Sand and Fine Gravel, Sweet Musty Odor Present		0.0	
			W	- 15- ATEI	LEVEL OBSERVATIONS (GENERA	L NOT	TES
. in De _l De _l	nile Dr ne Aft pth to pth to	er Dr Wate: Cave	<u>∑</u> illing r in		Upon Completion of Drillingft. Start 2 Driller E Logger	./6/96 End E & F Chief DAP Edito and 2 1/4" I	r PMS	Rig CME 55



LOG OF TEST BORING

Project American Chemical Service, Inc.
Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No.
Job No.

SB140 4077.0075

Sheet 2 of 2

Surface Elevation 637.6

Northing: **6956.3** Easting: **5179.7**

					 ·	00 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000			
		ΑM				VISUAL CLASSIFICATION		PROF	PERTIES
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)		and Remarks	qu (qa) (tsf)	PID (ppm)	Remerks
7	16	w	10	-		Gray Brown Fine SAND (SP), Little to Some, Medium to Coarse Sand, Trace Fine Gravel, Sweet Musty Odor Present		0.0	
8	22	W	9			Very Stiff, Gray, Silty CLAY (CL-ML), Trace Fine to Coarse Sand and Gravel		0.0	
				-		End of Boring at 20.5 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.			
				25 -					
		23	:	30-					



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No. SB141 Job No. 4077.0075

Sheet 1 of 2

637.6 Surface Elevation

.__ 1:4077'Gint 40770, iD. CHICAGO ...

Northing: 6999.3 5199.7

(PLE			VISUAL CLASSIFICATION	N	ļ	SOIL	PRO	PERTIES
No.	Rec. (in.)		N Value	Depth (ft.)		and Remarks			qu (qa) (tsf)	PID (ppm)	Remarks
						Gray Slag and Gravel (FILL)					
1	16	M	7	-		Brown Fine SAND (SP), Grades into Dar Brown Fine Sand, Solvent Odor at 2.5 to Zone				67.0	
2	18	M	6	 - 5-		Gray Fine SAND (SP), Sulfur Odor Prese Little Black Staining at 5.2 to 5.5 ft	ent,			2348.0	Field analysis for VOCs
				-		T. 16 1 17 0117 (07) . (56					
3	18	W	6	- - -		Black Stained Fine SAND (SP) to 6.5 ft, 6 into Dark Gray Fine Sand to Olive Gray Fine Sand at 7.5 ft, Musty Odor Present				21.0	Field analysis for PCBs
4	14	W	6	- - - 10-		Gray Fine SAND (SP), Little Brown to Bl Staining from 9.5 to 10.0 ft, Musty Odor Present	ack			164.0	Field analysis for PCBs
5	12	W	4	-		Gray Fine SAND (SP), Trace Medium to Coarse Sand and Fine Gravel, Musty Odo Present				22.0	
6	16	W	8	- 15		Gray, Fine to Coarse SAND (SP) to 14.5 Grades into Gray Brown Fine Sand, Thin Lense at 14.7 to 14.8 ft, Sweet Propane-L Odor Present	Silt			7.0	
		L	W		RL	EVEL OBSERVATIONS		GEN	ERAL	NO1	ES
De De	nile Dr ne Aft pth to pth to The strai	er Dr Wate Cave	illing r in	represen	ft.		Start Driller Logger Drill Me	2/6/96 E & F DAP	End Chief Editor 2 1/4" I.	2/6/9 GH r PMS	6 Rig CME 55



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

SB141 Boring No. Job No.

4077.0075

2 of 2 Sheet Surface Elevation 637.6

6999.3 Northing: 5199.7

	SAMPLE				VISUAL CLASSIFICATION	1	. PROP	ERTIES
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
7	16	w	12	-	Gray Brown Fine SAND (SP), Trace Medium to Coarse Sand and Fine Gravel, Sweet Propane Like Odor Present		6.0	
8	22	М	11		Very Stiff to Hard Gray, Silty CLAY (CL-ML), Trace Fine to Coarse Sand and Gravel	4.0- >4.5		
				- 25-	End of Boring at 20.5 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.			
				30-				



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No. SB142 4077.0075 Job No. Sheet 1 of 2 Surface Elevation 638.3

J:4077:Gint 40770 IC: USSCAGO

Northing: 6885.6 Easting: 5641.6

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-Depth PID and Remarks (qa) No. (in.) ture Value (ft.) (ppm) Remarks (tef) Gray Slag and Gravel (FILL) Dark Brown Fine SAND (SP), Some Light 1 4 $\overline{\mathbf{M}}$ 10 $\overline{0.0}$ Brown Fine Sand Gray and Brown, Fine to Coarse SAND (SP), 2 12 1145.0 M 4 Solvent Odor Present 5 Olive Brown, Fine to Coarse SAND (SP) to 6.5 W 1534.0 Field analysis 3 16 ft, Then into Brown Fine Sand, Sheen and for VOCs and Solvent Odor Present **PCBs** Olive Gray Brown, Fine to Coarse SAND (SP), 4 W 1435.0 Field analysis 14 Solvent Odor Present for PCBs 10-Olive Brown, Fine to Coarse SAND (SP) to 5 12 W 361.0 11.5 ft. Then into Gray Brown Fine Sand. Sweet Propane Like Odor Present Gray Brown Fine to Coarse SAND (SP), 12 $\overline{\mathbf{w}}$ 505.0 6 8 Grades into Gray Brown Fine Sand at 14.0 ft, Sweet Propane Like Odor Present 15-WATER LEVEL OBSERVATIONS **GENERAL NOTES** While Drilling ft. Upon Completion of Drilling Start 2/6/96 End 2/6/96 ime After Drilling Rig CME 55 Driller E & F Chief GH Depth to Water DAP Editor **PMS** Logger Drill Method 2 1/4" I.D. HSA Depth to Cave in The stratification lines represent the approximate boundary between soil types and the transition may be gradual.



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No. Job No.

SB142 4077,0075

638.3

Sheet

2 of 2

Surface Elevation

Northing:

6885.6

5641.6

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SOIL PROPERTIES **SAMPLE** VISUAL CLASSIFICATION Rec. Mois-PID N Depth and Remarks (ap) (ppm) Remarks (in.) ture Value (ft.) (tsf) Gray Brown Fine SAND (SP), Trace Medium 240.0 7 14 W 10 to Coarse Sand, Fine Gravel, Sweet Propane Like Odor Present, Some Fine to Coarse Sand in Tip of Spoon 2.5-3.5 4.0 8 18 W/M 11 Gray Clayey SILT (CL-ML), Grades to Very Stiff, Silty Clay, Trace Fine to Coarse Sand and Gravel 20 Stiff, Gray Silty CLAY (CL-ML), Trace Fine to 9 10 M 8 Coarse Sand and Gravel 2.5-3.0 End of Boring at 22.5 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel. 25-30-



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No. SB144 Job No.

4077.0075

JAGITYGINIMOTTO ID. CHICAGO

639.7

Sheet 1 of 2 Surface Elevation

Northing: 6996.0 5565.6

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 **SAMPLE** SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-Depth PID and Remarks (ap) (in.) ture (ft.) Value (ppm) Ramarks (tsf) Gray Slag Gravel and Fine Sand (FILL) Split Spoon Refusal, Drilled to 3.5 ft, Soil 0.0 M 1 Cuttings were Brown SAND (SP) at 1.0 ft, Green/Gray Sand at 2.0 ft, Black Sand at 3.0 ft Crushed Grayish Green Gravel to 3.8 ft, Then 2 16 M 14 1708.0 into Black Fine SAND (SP), Musty Odor Present 5~ Dark Olive Gray/Brown Fine SAND (SP), 333.0 3 18 w 8 Swampy, Musty Odor Present Olive Gray Brown Fine SAND (SP), Grades 4 7 1867.0 Field analysis 16 into Black Brown, Oily Stained, Fine to Coarse for VOCs and Sand at 9.5 to 9.8 ft and from 10.2 to 10.5 ft, **PCBs** Solvent Oily Odor Present 10-Olive Gray Brown Fine SAND (SP), Grades 1860.0 Field analysis 5 18 into Black/Brown Oil Stained, Fine to Coarse for PCBs Sand from 12.2 to 13.0 ft, Sheen Present Dark Gray, Fine to Coarse SAND (SP), Black 324.0 6 16 W Stained Zone from 14.0 to 14.3 ft and 14.8 to 15.0 ft, Musty Odor Present - 15-WATER LEVEL OBSERVATIONS **GENERAL NOTES** 2/6/96 End ft. Upon Completion of Drilling ft. Start 2/6/96 Vhile Drilling E&F Chief Rig CME 55 GH Time After Drilling Driller Logger DAP Editor **PMS** Depth to Water Drill Method 2 1/4" I.D. HSA Depth to Cave in

The stratification lines represent the approximate boundary between soil types and the

transition may be gradual



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana Boring No.

SB144 4077.0075

Job No. Sheet

2 of 2

Surface Elevation

639.7

Northing:

6996.0

				Location Griffith, Indiana 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 69	Fast	Northing: 6996.0 Easting: 5565.6					
		AM			VISUAL CLASSIFICATION	S	SOIL PROPERTIES				
ło.	Rec.	Mois- ture	N Value	Depth (ft.)	and Remarks	1 (qa) (sf)	PID (ppm)	Remarks		
7	14	W	13		Dark Gray Fine to Coarse SAND (SP), Grades into Gray Brown Fine Sand at 17.0 ft, Musty Sweet Propane Like Odor Present			181.0			
3	20	W/M	8	~	Dark Gray Brown, Fine to Coarse SAND and GRAVEL (SP)			535.0			
				— 20 –	Hard Gray Brown Silty CLAY (CL-ML), Trace Fine to Coarse Sand at 19.7 ft	4	.5				
9	18	М	8	-	Hard, Gray Brown Silty CLAY (CL-ML)	>	4.5				
				-	End of Boring at 22.5 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.						
		The state of the s		25 							
				-							
				30-							



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No. Job No.

SB149 4077.0075

638.2

Sheet

1 of 2

Surface Elevation Northing:

6833.6

	S	ΑM	PLE		VISUAL CLASSIFICATION	SO	L PRO	PERTIES
No.		Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
				_	Gray Slag, Gravel (FILL)			
Ī	12	М	6	-	Dark Brown, Fine SAND (SP), Grades into Gray/Black Fine Sand, Musty Solvent Odor Present	-	216.0	
-				<u> </u>	Dark Gray to Gray Fine SAND (SP), Little Silt,			
2	14	М	6		Musty Solvent Odor Present		145.0	
				5~ _	Dark Gray to Gray Brown Fine SAND (SP), Sweet Odor, Little Black Staining from 6.5 to			
2	16	W	6		6.8 ft		313.0	Field analysis
					Grayish Green/Brown, Fine to Coarse SAND and Fine GRAVEL (SP), Musty Odor Present			for PCBs
4	16	W	7	_	Dark Olive Brown Fine to Coarse SAND (SP), Fine Gravel, Musty Odor		465.0	Field analysis for VOCs an PCBs
_	20	w	11	— 10— - —	Gray, Olive Brown Fine SAND (SP), Musty		218.0	
5	20	**	11	_	Sulfur Odor Present		210.0	
				_	Black Stained Fine SAND (SP) at 16.8 ft,			
6	20	W	11		Musty Sulfur Like Odor Present		75.0	
			\A/	- 15- ATE	LEVEL OBSERVATIONS	GENERA	NO.	TFS
 Vì	ule Dr	illing			Upon Completion of Drillingft. Start	2/12/96 End		··
rii De	ne Aft pth to pth to	er Dr Wate	illing r	-	Driller Logger	E&F Chi	ef GH tor PM	I Rig CME S



LOG OF TEST BORING

Project American Chemical Service, Inc.
Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No. Job No. SB149 4077.0075

638.2

Sheet

2 of 2

Surface Elevation

Northing:

6833.6

Easting: 5764.9

,		AM			VISUAL CLASSIFICATION			PROPERTIES		
lo.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)	and Rema	rks qq (qq (ts	PiD (ppm)	Remarks		
7		W	14	-			0.0			
8	20	W/M	10	- -	Dark Gray, Fine to Coarse SA ft, Musty Odor Present	ND (SP) to 19.5	11.0			
				- — 20-	Stiff to Very Stiff, Gray, Clayer CLAY (CL-ML)	ey SILT to Silty 3.0-4	5			
9	20	M	11	-	Stiff, Gray Clayey SILT (CL-1	ML) 2.5	0.0			
				- 25-	End of Boring at 2 Borehole Backfilled with Bento Grout. Topped with 6 inches of	onite Cement				
				30-						



LOG OF TEST BORING

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000

Project American Chemical Service, Inc.
Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No. SB150
Job No. 4077.0075
Sheet 1 of 2
Surface Elevation 639.0

Northing: **6452.9** Easting: **5749.4**

SOIL PROPERTIES SAMPLE VISUAL CLASSIFICATION PID Rec. Mois-N Depth and Remarks (ap) No. 🖺 (in.) ture (ft.) (ppm) Remarks Brown Sand, Gray Slag, Gravel (FILL) Brown, Fine to Coarse SAND and GRAVEL 0.0 M N/A (FILL), Split Spoon Refusal Yellow Brown, Fine to Coarse SAND and 3.0 2 M 16 6 GRAVEL (FILL), Some Olive Gray Staining from 4.5 to 5.5 ft Olive Gray to Dark Silver-Gray Stained, Fine to 16 M/W 1648.0 Field analysis 3 Coarse SAND and GRAVEL (FILL), Creosote for VOCs and Like Odor **PCBs** Olive Gray to Dark Silver-Gray Stained, Fine to W 5 79.0 4 10 Coarse SAND and GRAVEL (FILL), Creosote Like Odor 40.0 W Dark Gray, Fine to Coarse SAND (SP) to 12.0 5 10 6 ft, Grades into Gray Brown Fine Sand, Trace Medium to Coarse Sand, Slight Solvent Odor Gray Brown, Fine to Coarse SAND (SP), $\overline{\mathbf{w}}$ 50.0 14 6 Musty Odor WATER LEVEL OBSERVATIONS **GENERAL NOTES** ft. Upon Completion of Drilling Ψ ft. Start 2/13/96 While Drilling 2/13/96 End ime After Drilling Driller E&F Chief GH Rig CME 55 Logger DAP Editor Depth to Water **PMS** Drill Method 2 1/4" I.D. HSA Depth to Cave in The stratification lines represent the approximate boundary between soil types and the transition may be gradual.



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No.

SB150 4077.0075

Job No. Sheet

2 of 2

Surface Elevation Northing:

639.0

6452.9 5749.4

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SOIL PROPERTIES SAMPLE VISUAL CLASSIFICATION Rec. Mois-PID Depth and Remarks (qa) (tsf) No. ture Value (ft.) (ppm) Remarks (in.) Gray Brown, Fine to Coarse SAND (SP), With W 11 0.0 7 18 Fine Gravel, Propane-Like Odor Gray Brown, Fine to Coarse SAND (SP), Clay Seam at 20 to 20.3 ft (SP) 8 W 9 7.0 18 20-Stiff to Very Stiff, Gray Brown, Silty CLAY 2.0-4.0 0.0 9 22 M 7 (CL-ML), Trace Fine to Coarse Sand and Gravel End of Boring at 23.0 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel. 25 30-



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana Boring No.

SB151 4077.0075

Job No. Sheet

1 of 2

Surface Elevation 638.8 6763.8

Northing:

		W	<i>y</i>		100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691	Eastin	g: 589	00.1
	S	AM	PLE		VISUAL CLASSIFICATION		IL PRO	PERTIES
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)		Remarks
				_	Gray Crushed Gravel, Slag (FILL)			
1	12	M	14	F	Yellow Brown, Fine SAND (SP), Little Fine to Coarse Sand		7.0	
2	22	M	6	-	Orange Brown, Fine to Coarse SAND (SP), Little Fine Gravel, Grades to Olive Gray Staining at 4.2 ft		11.0	
3	20	M/W	6	5- - -	Black Stained, Fine to Coarse SAND and GRAVEL (GP), Becomes Olive Gray Stained, Fine to Coarse Gravel at 6 ft, Solvent Odor near Black Staining		15.0	Field analysis for PCBs
4	22	W	6	 	Gray/Green/Brown Stained, Fine to Coarse SAND and GRAVEL (GP), Grades into Dark Brown Fine to Medium Sand at 8.0 ft		30.0	
5	12	W	5		Olive Brown, Fine to Coarse SAND and GRAVEL (GP), Grades into Dark Gray, Fine to Coarse Sand and Fine Gravel, Swampy Odor		166.0	Field analysis for PCBs
6	20	W	10	- - -	Gray Brown, Fine to Coarse SAND and GRAVEL (GP), Grades into Gray Brown, Fine to Medium Sand at 12.0 ft, Little Black Staining and Swampy Odor		180.0	
7	20	W		-	Gray Brown, Fine to Coarse SAND and Fine GRAVEL (GP) to 14.0 ft, Grades into Gray Brown Fine Sand		39.0	
	<u></u>		W	15- Δ TF	LEVEL OBSERVATIONS	GENER	AL NO	ΓES
ir De De	nile Dr ne Aft pth to pth to	er Dr Wate Cave	¥ illing r in		Upon Completion of Drilling ft. Start Driller Logger	2/13/96 Er E & F Cl	nd 2/13/9 nief GH litor PMS	96 Rig CME 55



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

SB151 Boring No. Job No. 4077.0075

2 of 2 Sheet

Surface Elevation 638.8 Northing: 6763.8

\geq		A B 4			210	O Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-500	1	DD ^	
о.		AM Mois- ture	PLE N Value	Depth		VISUAL CLASSIFICATION and Remarks	Qu (qa) (tsf)	PID (ppm)	PERTIES
8	20	W	18			Gray Brown, Fine to Coarse SAND and GRAVEL (GP), Grades into Gray Brown Fine Sand, Black Stained from 16.5 to 17.0 ft		40.0	
9	18	W	21	- -		Gray, Fine to Coarse SAND and GRAVEL (GP), Musty Odor Present		19.0	
0	20	W/M	18	-		Gray, Fine to Coarse SAND (SP), Very Strong Sour Odor Present		3251.0	Field analyst for VOCs
				20- -		Hard, Gray Brown, Clayey SILT to Silty CLAY (CL-ML), Black Staining Present	>4.0		
11	20	М		_			3.0		
						Very Stiff, Gray Brown, Clayey SILT to Silty CLAY (CL-ML), Very Strong Sour Odor in Clay			
12	24			- - - - 25-		Gravel in Shelby Tube			
			-	-		End of Boring at 25.0 ft			
				- 	1 1	Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.			
				-					
				 30	-				
		1		<u> </u>			· .	1	



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No. Job No.

SB152 4077.0075

Sheet

1 of 2

Surface Elevation 639.2

Northing:

6606.8 5818.6

		W	"		100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-	Easting:	5818	.6
	S	AM	PLE		VISUAL CLASSIFICATION		PROP	ERTIES
No.	LK.	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
					Gray Slag, Gravel Followed by Brown Fine Sand (FILL)			
1	22	М	12		Light Brown Fine SAND (SP), Front Line at 2.5 ft		1.0	
2	24	M/W	4		Light Brown Fine SAND (SP), Some Black Streaks, Grades into Orange Brown, Fine to Coarse SAND and GRAVEL from 4.5 to 5.0 ft		1.0	
3	22	W	4	- 5- -	Orange Brown to Brown, Fine to Coarse SAND and Fine GRAVEL (SP/GP), Some Rust Staining		1.0	
4	12	w	2		Gray, Olive/Green, Fine to Coarse SAND and GRAVEL (SP/GP), Grades to Black Staining from 8.0 to 9.0 ft, Solvent/Gasoline Like Odor Present		250.0 F	Field analysis for PCBs
5	20	w	10	 10-	Grades into Dark Gray Fine SAND (SP) at 10.0		1395.0 F	Field analysis for PCBs
6	18	W	15	-	ft, Solvent Odor Present Dark Gray/Green, Fine to Coarse SAND and GRAVEL (SP/GP) to 11.5 ft Gray Brown Fine SAND and GRAVEL (SP/GP) from 11.5 to 12.0 ft Gray Brown Fine SAND (SP), Propane Like		143.0	
7	16	W	9		Odor Present Gray Green Fine to Coarse SAND and GRAVEL (SP/GP), Gray Brown Fine Sand, Propane Like Odor Present		74.0	
		i	W		LEVEL OBSERVATIONS	GENERAL	. NOTE	S
De De	hile Da me Aft epth to the stra transition	er Dr Water Cave	illing r in	represen	Driller Logger	2/13/96 End E & F Chief DAP Editor thod 4 1/4" I.	PMS D. HSA	Rig CME 55



LOG OF TEST BORING

Project American Chemical Service, Inc.
Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No.

SB152 4077.0075

Job No. Sheet

2 of 2

6606.8

5818.6

Surface Elevation

639.2

Northing: Easting:

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-Depth PID and Remarks No. (qa) (in.) ture (ft.) (ppm) Remarks (tsf) 20 13 Gray Brown Fine SAND (SP), Some Fine to 88.0 Coarse Gravel from 15.0 to 15.5 ft Gray Brown, Fine to Coarse SAND (SP), W 9 22 13 69.0 Propane Like Odor, 1 in. Clay Seam from 18.9 to 19.0 ft Gray Brown, Fine to Coarse SAND (SP), Trace 10 20 W 24 4.0 Silt and Clay, Propane Like Odor Present 20-11 22 W 23 Stiff, Gray Clayey SILT (CL-ML) to SILT, 2.0 0.0 Slight Sour Odor Present 2.5 End of Boring at 23.0 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel. 25-30-



Depth to Cave in

The stratification lines represent the approximate boundary between soil types and the transition may be gradual.

LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Contaminent Area Location

Griffith, Indiana

Boring No.

SB201/A 4077.0075

Job No. Sheet

1 of 1

Surface Elevation

647.5

Northing:

Drill Method 3 1/4" I.D. HSA

JI40771Gint 40270 ID. CHICAGO

5674.8 4984.8

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SOIL PROPERTIES SAMPLE VISUAL CLASSIFICATION Rec. Mois-PID Depth and Remarks (qa) Value (ft.) (ppm) Remarks (tef) Dirt/Grass Surface over Silty Sand (TOPSOIL) REFUSE 1 $\overline{\mathbf{M}}$ 5 2 3 Auger Refusal and End of Boring at 8.0 ft Abandoned Borehole with Bentonite Cement 10-Grout. Topped at the Surface with Bentonite Chips. **GENERAL NOTES** WATER LEVEL OBSERVATIONS ft. Upon Completion of Drilling Ψ Start 1/17/96 End 1/17/96 **Vhile Drilling** Driller E & F Chief Logger PMS Editor Rig CME ime After Drilling JE DAP 850 Depth to Water



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Contaminent Area Location

Griffith, Indiana

Boring No. SB202 Job No. 4077.0075

Sheet 1 of 1

640.4 Surface Elevation 6059.9 Northing:

		W	<i>y</i> 		1 21	OO Corporate Drive, Addison, Illinois 60101, TEL.	(708) 691-	Ea	sting:	5011	.5
	S	ΑM	PLE		Ī	VISUAL CLASSIFICATIO			SOIL	PROP	ERTIES
No.	Rec. (in.)	Mois- ture	N euleV	Depth (ft.)		and Remarks			qu (qa) (tsf)	PID (ppm)	Remarks
				_		Dirt/Grass Surface over Silty Sand (FILL))				
1	12	М	31			Gravel, Wood, Glass, Silt, Clay and Sand (FILL)					
2		М	6	-		Waste					
3			52/3"	— 5 —		Waste: Split Spoon was wet at 8 ft					
				- 10-		Auger Refusal and End of Boring at 7.0 ft Abandoned Borehole with Bentonite Cemel Grout. Topped at the Surface with Bentonic Chips.					
			W		1	EVEL OBSERVATIONS		GEN	ERAL	NOTE	S
De	hile Dr me Aft epth to epth to The stra transitio	er Dr Wate Cave	illing r in	represen				PMS	Chief Editor 1/4" I.I	D. HSA	Rig CME 850



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Contaminent Area Location

Griffith, Indiana

SB202A Boring No. 4077.0075

Job No. Sheet 1 of 2

639.9 Surface Elevation

Northing: 6077.4 Easting: 5014.5

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 **SOIL PROPERTIES** SAMPLE VISUAL CLASSIFICATION PID Rec. Mois-Depth and Remarks (ap) (ppm) Remarks (in.) (ft.) Blind Drilled to 6 ft 0.0 12 W WASTE: Paper, Plastic, Trace silt 1 13 Dark Gray Brown, Silty, Fine to Medium 2 12 W 0.5 SAND (SP) 10-Trace to Some Fine GRAVEL and Coarse 3 18 W 5.0 16 SAND (SP) from 11 to 11.5 ft 11.0 Field analysis 24 7 for VOCs and **PCBs** WATER LEVEL OBSERVATIONS **GENERAL NOTES** $\frac{2}{8.5}$ ft. Upon Completion of Drilling $\frac{2}{8.5}$ Start 1/17/96 End 1/18/96 While Drilling Time After Drilling Driller E&F Chief JE Rig CME Logger PMS Editor DAP 850 Depth to Water Depth to Cave in Drill Method 3 1/4" I.D. HSA The stratification lines represent the approximate boundary between soil types and the transition may be gradual. JM077\Gint\40770_ID_CHICAGO___



LOG OF TEST BORING

Project American Chemical Service, Inc.
Off-Site Containment Area

Location Griffith, Indiana

Boring No.

SB202A

Job No. Sheet 4077.0075 2 of 2

Surface Elevation

639.9

Northing:

6077.4 5014.5

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SOIL PROPE

		AM			VISUAL CLASSIFICATION		PRO	PERTIES
No.	Rec.	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
5	24	W	12		Brown Gray, Silty, Fine to Medium SAND (SP), Trace Fine to Medium Gravel 1/2 in. Thin Gray Clay Stringers from 17.5 to 18 ft		6.0	Field analysis for VOCs and PCBs
6	24	W	15	_	Brown Gray, Silty Fine SAND (SP), Grading into Silt at 19.5 ft, Trace Gray Clay		0.0	
				20- -	Gray Clayey SILT (ML) Gray Fine SAND (SP)			
7	24	М	20		Negative Hydrophobic Dye Test Brown Gray CLAY (CL)	4.0	0.0	
				- 25- - 25- 	End of Boring at 23.0 ft Abandoned Bachole with Bentonite Cement Grout. Topped at the Surface with Bentonite Chips.			



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area

Location Griffith, Indiana Boring No.

SB203

Job No.

4077.0075

Sheet

1 of 2 Surface Elevation 641.0

Northing:

6029.0 5011.5

		W	ν ——		i 21	100 Corporate Drive, Addison, Illinois 60101, TEL.	(708) 691-500	Easting: _	501	11.5	/
	S	AM	PLE		 	VISUAL CLASSIFICATION			PRO	PERTIES	`\
No.	A.	Mois- ture	N Value	Depth (ft.)		and Remarks		qu (qa) (tsf)	PID (ppm)	Remarks	
						Grass Surface Over Municipal REFUSE					
1		W		_		REFUSE					
2		W	9	_ _ _ 5~		REFUSE: Wood, Paper, Grass, Plastic					
3		w	13	_		REFUSE					
4		w	26	- - - - 10-		REFUSE: Trace Paper and Plastic					
5	18	w	19	- 		REFUSE: Black Clay Mixed with Wood a Paper	nd	,	1.0		
						Gray, Silty Fine SAND (SM) Light Brown, Silty, Fine to Medium SANI (SM), Trace Coarse Sand and Fine Gravel					
6	12	W	17	_		Brown, Silty Fine SAND (SM)			42.0	Field analysi for VOCs an PCBs	
	1		W	ATEF	t	EVEL OBSERVATIONS	GE	NERAL	TON.	res	
De _l De _l	ile Dr ne Aft oth to the strai	er Dri Water Cave	¥ illing ·		ft.	Upon Completion of Drillingft.		/96 End F Chief IS Editor 3 1/4" I.	1/18/9 JE DAF D. HSA	P6 Rig CME 850	



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area

Griffith, Indiana Location

Boring No.

SB203 4077.0075

Job No. Sheet

2 of 2

641.0

Northing:

Surface Elevation

6029.0 5011.5

		Ü	IJ		21	Location Griffith, Indiana OO Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-500	Northing Easting:		11.5
			PLE	·		VISUAL CLASSIFICATION	1	PERTIES	
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)		and Remarks	(qa) (tsf)	(ppm)	Remarks
7	24	W	17	-		Brown, Silty Fine SAND (SM)		37.0	Field analysis for VOCs and PCBs
8	24	W	24			Brown, Silty Fine SAND (SM)		31.0	
9	24	W	21			Stiff, Gray Silty CLAY (CL)	4.0	21.0	
				- - - - - -		End of Boring at 23.0 ft Abandoned Borehole with Bentonite Cement Grout. Topped at the Surface with Bentonite Chips.			
				30-					



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area Location

Griffith, Indiana

Boring No.

SB204 4077.0075

Job No. Sheet

1 of 2

Surface Elevation

641.9

Northing: Easting:

5964.5 5012.0

July 2/42/2/Cott/40/22 do. uhiteAbd

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 **SAMPLE** SOIL PROPERTIES VISUAL CLASSIFICATION PID Rec. Mois-Depth and Remarks (ga) No. (in.) ture Value (ft.) (ppm) Remarks (tsf) REFUSE: Black Clayey Soil with Wood, Plastic and Paper 1 M Two attempts made to move away from REFUSE: Wood, Moved South 2 ft refusal **REFUSE** 2 M 43 **REFUSE** 3 M 7 REFUSE 4 15 M w 27 5 24 Brown, Silty, Fine to Medium SAND, Trace Fine to Coarse Gravel (SM) Brown, Silty, Fine to Medium SAND, Trace 8.0 Field analysis 24 W 6 11 Fine to Coarse Gravel (SM) for VOCs and **PCBs GENERAL NOTES** WATER LEVEL OBSERVATIONS 1/18/96 End 1/18/96 Start hile Drilling ft. Upon Completion of Drilling Rig CME Driller E&F Chief JE ime After Drilling 850 DAP Logger PMS Editor Depth to Water Drill Method 3 1/4" I.D. HSA Depth to Cave in

The stratification lines represent the approximate boundary between soil types and the

transition may be gradual



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area Location

Griffith, Indiana

Boring No.

SB204 4077.0075

Job No. Sheet

2 of 2

Surface Elevation

641.9

Northing: Easting:

5964.5 5012.0

					21	00 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5	00	o -	201	2.0	
			PLE	,		VISUAL CLASSIFICATION		<u> </u>		PERTIES	
No.	Rec.	Mois-	N Value	Depth (ft.)		and Remarks		qu (qa) (tsf)	PID (ppm)	Remarks	
7	24	w	17	_		Gray, Silty, Fine to Medium SAND (SM)		(151)	17.0	Field analysis for VOCs and PCBs	
8	24	W	19	 - - - 20-		Gray, Silty, Fine to Medium SAND (SM), Trace Medium to Coarse Gravel			5.0		
9	24	w	20	-)		Gray Silty CLAY (CL-ML)		3.5-4.0	3.0	
				- 25-		End of Boring at 23.0 ft Abandoned Borehole with Bentonite Cement Grout. Topped at the Surface with Bentonite Chips.					
				30-							



transition may be gradua

LOG OF TEST BORING

Project American Chemical Service, Inc.
Off-Site Containment Area

Location

Griffith, Indiana

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000

Boring No.

SB205

Job No.

4077.0075 1 of 2

Sheet 1 o
Surface Elevation

643.4

Northing: Easting:

5913.8 5014.2

_A011:Gm:A0112_D.Gh:2ACD.

SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-PID Depth and Remarks (qa) No. (in.) ture Value (ft.) (ppm) Remarks (tsf) REFUSE: Grass Surface REFUSE: Brown, Silty, Fine to Medium Sand 1 39 45.0 M with Some Debris $\overline{\Delta}$ 2 $\overline{\mathbf{w}}$ 5 18 Brown, Silty, Fine to Medium SAND (SM) 592.0 Field analysis for VOCs 18 $\overline{\mathbf{w}}$ 4 1062.0 Field analysis for VOCs Grades to Fine, Silty SAND (SM), Stained 18 W 530.0 4 Brown, Silty, Fine SAND (SM) Brown Stained, Silty, Fine SAND (SM), Trace Clay 20 $\overline{\mathbf{w}}$ 25.0 11 Rust Coloration at 12 ft 6 18 $\overline{f w}$ 19 Grades to Gray, Silty, Fine to Medium SAND 27.0 (SM) WATER LEVEL OBSERVATIONS **GENERAL NOTES** ₹ 3.5 ft. Upon Completion of Drilling ₹ 1/19/96 End 1/19/96 ile Drilling ft. Start .ime After Drilling Driller E&F Chief JE Rig CME Depth to Water Logger **PMS** Editor DAP 850 Drill Method 3 1/4" I.D. HSA Depth to Cave in The stratification lines represent the approximate boundary between soil types and the



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area

Location Griffith, Indiana

Boring No.

SB205 4077.0075

Job No. Sheet

2 of 2

Surface Elevation 5913.8

643.4

Northing:

Fine to Coarse Sand and Gravel from 15 to 15.5	qu (qa) (tsf)	PROPERTIE PID (ppm) Remar
Fine to Coarse Sand and Gravel from 15 to 15.5 The same of the	(tsf)	(ppm) Remar
7 18 W 26 Gray, Silty, Fine SAND (SM), No Black		11.0
7 18 W 26 Gray, Silty, Fine SAND (SM), No Black		11.0
8 18 W 12 Gray, Silty, Fine SAND (SM), No Black Staining Present		88.0
9 24 W/M 19 Gray, Silty, Fine to Medium SAND (SM)		62.0
Gray, Clayey SILT (ML), Trace Fine Sand		
Gray, Silty CLAY (CL-ML)		
10 M 15	4.0 3	39.0
End of Boring at 25.5 ft		
Abandoned Borehole with Bentonite Cement Grout. Topped at the Surface with Bentonite Chips.		: : :
- 30-		
		: : :
	:	



transition may be gradual

LOG OF TEST BORING

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000

Project American Chemical Service, Inc.
Off-Site Containment Area

Location Griffith, Indiana

Boring No. SB205A Job No. 4077.0075

Sheet 1 of 2

Surface Elevation 646.0

JAOILSed ACILL 1, DECAGE

Northing: **5930.6** Easting: **4988.6**

SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION Mois-N Depth PID and Remarks No. Value (in.) ture (ft.) (ppm) Remarks FILL: Gravel, Sand, Clay and Silt 1 24 M 46 20.0 2 12 M 15 6.0 FILL: Brown, Silty, Fine to Coarse Sand, Trace Gravel and Clay FILL: Dark Brown, Silty, Fine to Coarse Sand, 3 18 34 6.0 M Some Fine to Medium Gravel and Clay Coarse Gravel Lens from 7.5 to 8 ft FILL: Dark Brown, Silty Clay and Sand and 4 12 M 6 Field analysis for PCBs Gray/Blue Clay from 9 to 9.5 ft Wood/Paper Mixed with Clay and Silt from 9.5 to 10.5 ft FILL: Wood and Fabric in Tip of Spoon, No 5 M/W 0.0 Recovery FILL: Wood in Split Spoon, Poor Recovery 6 M/W 17 13.0 $\overline{\Delta}$ WATER LEVEL OBSERVATIONS **GENERAL NOTES** ft. Start 1/24/96 End 1/24/96 hile Drilling 14.0 ft. Upon Completion of Drilling \(\frac{1}{2}\) E&F Rig CME . me After Drilling Driller Chief JE DAP 850 Depth to Water Logger PMS Editor Drill Method 3 1/4" I.D. HSA Depth to Cave in The stratification lines represent the approximate boundary between soil types and the



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area

Location

Griffith, Indiana

Boring No.

SB205A 4077.0075

Job No. Sheet

2 of 2

Surface Elevation

646.0

Northing:

5930.6 4988.6

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-N PID Depth and Remarks (qa) No. (in.) ture Value (ft.) Remarks (ppm) FILL: Brown Silt, Clay, Gravel with Wood W 7 5.0 6 Pieces, Poor Recovery Dark Brown, Silty, Fine to Medium SAND (SM) Wood in Split Spoon, Poor Recovery $\overline{\mathbf{w}}$ 8 5 0.0 $\overline{\mathbf{w}}$ 21 6 60.0 10 W 17 Gray, Silty, Fine to Medium SAND (SM) 160.0 Field analysis 6 for VOCs and **PCBs** 25 Gray, Silty CLAY (CL-ML) 12 M 27 Gray, Silty, Fine to Medium SAND (SM) 10.0 11 Stiff, Gray, Silty CLAY (CL-ML), Trace Fine to Coarse Sand 12 0.0 18 18 4.0 M End of Boring at 30.0 ft Abandoned Borehole with Bentonite Cement Grout. Topped Surface with Bentonite Chips.



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area Griffith, Indiana Location

Boring No. SB206 Job No. 4077.0075 Sheet 1 of 2 Surface Elevation

644.6

5856.2 Northing: 5013.4

<u> 314077 Cint A</u>2772 (D. 1002Au c

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000

	S	AM	PLE		}	VISUAL CLASSIFICATION		PRO	PERTIES
No.	MI.	Mois- ture	N Value	Depth (ft.)		and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
				_		REFUSE: Grass/Gravel Surface, Silty Fine to Medium Sand, Trace Silt, Clay and Fine Gravel			
1	24	M	16	-		Thin Paper Layer at 2.8 ft		99.0	3" split spoon utilized for sample collection this borehole
2	24	M	15	-		Brown Gray, Silty, Fine to Medium SAND (SP) Fine to Coarse SAND and GRAVEL Layer (SP/GP) Brown Gray, Silty, Fine to Medium SAND (SM)		161.0	
3	24	W	7	- 5- - -				330.0	Field analysis for VOCs and PCBs
4	20	М	9			Light Brown, Fine to Medium SAND (SP) Dark Brown with Light Brown Bands, Silty,		192.0	Field analysis for VOCs and PCBs
5	18	М	12	- 10-		Pine to Medium SAND (SP) Dark Brown, Silty, Fine to Medium SAND		192.0	. !
				ĺ) (3	SM), Trace Clay		1	:
6	20	M/W	25			Brown/Light Gray, Silty, Fine to Medium AND (SM)		70.0	
7	18	W	15			rown/Light Gray, Silty, Fine to Medium AND (SM)		7.0	!
	Ī		W	- 15- ATER	LEV	VEL OBSERVATIONS GE	NERAL	NOT	ES
Dep Dep	ile Dr ne Afte oth to	er Dri Water Cave	<u>¥</u> Iling	f		_	/96 End F Chief IS Editor	1/22/9 JE DAP	06 Rig CME 850

The stratification lines represent the approximate boundary between soil types and the transition may be gradual.



LOG OF TEST BORING

Project American Chemical Service, Inc.
Off-Site Containment Area

Location Griffith, Indiana

Boring No.

SB206 4077.0075

Job No. Sheet

2 of 2

Surface Elevation

644.6

Northing:

5856.2 5013.4

	S	AM	PLE		VISUAL CLASSIFICATION	1	_ PROF	PERTIES
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
8	20	W	12	_	171 171 171 171 171 171 181		7.0	
9	18	W	28	-	Gray, Silty, Fine to Coarse SAND and GRAVEL (SM/GM) Gray, Silty, Fine to Coarse SAND (SM)		23.0	
10	20	W	5	- - - - 20-	Sand and Gravel Lens from 19 to 19.5 ft		38.0	
11	24	W	18	- - -	Gray, Silty, Fine to Medium SAND (SM), Trace Gravel		7.0	
12	24	W/M	17	- - - -	1/2" Silt Seam at 22.5 ft 1" silt Seam at 22.8 ft Grades to Fine to Coarse Silty SAND and CLAY		1.0	
13				- 25 -	Gray Silty CLAY (CL) CLAY (CL)	>4.0		
				- 30-	End of Boring at 27.5 ft Abandoned Borehole with Bentonite Cement Grout. Topped at the Surface with Bentonite Chips.			
		:				i		



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area

Griffith, Indiana Location

Boring No. Job No.

SB207 4077.0075

646.9

Sheet

1 of 2

Surface Elevation Northing:

5801.1

2 6 M	N Depth	VISUAL CLASSIFICAT			DDC	DEDTIES
No. E (in.) ture V	1 ' 1		\bigcirc 14		. rnc	OPERTIES \
2 6 M	PS	and Remarks		qu (qa) (tsf)	PID (ppm)	Remarks
2 6 M		Grass/Gravel Surface				
	25	REFUSE: Black Silty and Clayey Sand Gravel with Cinders, Paper and Wood	and		0.0	
	5 - 5-	REFUSE: Paper, Plastic, Mostly Cinde and Gravel	rs, Sand	-	0.0	
3 18 M	6	Dark Gray to Brown, Silty, Fine to Med SAND (SM)	ium		7.0	
		Color Change to Dark Brown and Black ft	at 7.8			
4 2 M 9	9 -	Black Silty SAND, Wood in Split Spoon Plastic Sheeting Also (SM)	Shoe,		0.0	
5 18 M/W 2	3					Difficulty retrieving spoon
6 18 W 2	3	Gray, Silty Fine SAND (SM), Changes	o Dark		38.0	Field analysis
	.9 [[[]]] - []]] - []]] - 15-[]]]	Gray at 14.5 ft, Black Staining at 14.8 a ft			38.0	for VOCs and PCBs
	1	LEVEL OBSERVATIONS		GENERAL	NO	ΓES
"hile Drilling ne After Drilling Depth to Water Depth to Cave in The stratification li transition may be g	ng	Upon Completion of Drillingf	Driller I Logger	/22/96 End E & F Chief PMS Editor nod 3 1/4" I.	DAI	Rig CME P 850



LOG OF TEST BORING

Project American Chemical Service, Inc.
Off-Site Containment Area

Location Griffith, Indiana

Boring No.

SB207

Job No. Sheet 4077.0075 2 of 2

Surface Elevation

646.9

Northing:

5801.1 4978.0

		MA			VISUAL CLASSIFICATION		L PRO	PERTIES
No.	Rec.	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
7	18	W	33	-	Brown, Silty, Fine to Coarse SAND (SM), Trace Fine Gravel Brown/Gray Silty, Fine to Medium SAND (SM)		84.0	Field analysis for VOCs and PCBs
8	15	w	24	- - - 20-	Gray, Silty, Fine to Medium SAND (SM)		23.0	
9	18	w	28		1" Gray Silt in Tip of Spoon		69.0	Field analysis for VOCs and PCBs
10	12	W	24	-	Gray, Silty, Fine to Medium SAND (SM)	-	23.0	
				- 25-	Gray, Clayey SILT (ML), Grades into Gray, Silty Sand			
11	18	W/M	28	-	Gray CLAY (CL)	4.0	33.0	
12		M		_		>4.0	0.0	
				30-	End of Boring at 30.0 ft Abandoned Borehole with Bentonite Cement Grout. Topped Surface with Bentonite Chips.		;	



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area

Location Griffith, Indiana Boring No.

SB208 4077.0075

Job No. Sheet

1 of 2

Surface Elevation

646.8

Northing:

5763.9 4960.8

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois PID Depth and Remarks (qa) (in.) ture Value (ppm) Remarks No. (ft.) (tsf) Gravel/Grass Surface with Brown Soil Over Black, Silty and Clayey, Fine to Medium Sand 16.0 18 M 5 FILL: Dark Gray/Brown/Black CLAY with Paper, Fabric and Plastic, Trace Cinders and FILL: Wood, Cinders, Black, Silty Clay, Some 2 18 M 39 116.0 Fine to Medium Gray Sand FILL: Wood, Trace to Some Black, Fine to 3 M/W 26 83.0 Coarse Sand, Poor Recovery FILL: Wood and Clay, Poor Recovery 4 2 w 13 116.0 10 Field analysis Light to Dark Brown, Silty Fine SAND (SM) 3810.0 16 W 13 for VOCs and **PCBs** Light to Dark Brown, Silty Fine SAND (SM) 83.0 18 W 21 WATER LEVEL OBSERVATIONS GENERAL NOTES Start 1/23/96 End 1/23/96 hile Drilling E&F Chief Rig CME . ime After Drilling Driller JE 850 DAP Depth to Water Logger PMS Editor Drill Method 3 1/4" I.D. HSA Depth to Cave in The stratification lines represent the approximate boundary between soil types and the transition may be gradual. J'4077 Gmt/40770 JU. HICAGO.



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area

Location Griffith, Indiana

Boring No. Job No.

SB208 4077.0075

2 of 2 Sheet Surface Elevation

646.8

Northing:

5763.9 4960.8

		W	u		Eastin 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000	•	960.8
No.		Mois-	PLE N Value	Depth		PID	PERTIES
7	18	W	21		Gray, Silty, Fine to Medium SAND (SM), Trace to Some, Fine to Medium Gravel from 16 to 16.5 ft	249.0	
8	20	W	17	- - - 20-	Fine to Coarse SAND and Fine GRAVEL (SP/GP) Dark Brown/Gray, Silty, Fine to Medium SAND (SM)	250.0	
9	24	W	18		Fine to Coarse SAND and Fine GRAVEL (SP/GP), Trace Silt Gray/Brown, Silty, Fine to Medium SAND (SM), Trace Clay	50.0	
10	18	w	21	- - - 25-	Gray, Silty, Fine to Medium SAND (SM), Grades to Fine, Silty Sand Clayey Silt/Silty CLAY in Tip of Spoon	830.0	Field analysis for VOCs and PCBs
11	19	W	19		Gray Silty CLAY (CL-ML) 3.5->4.	7.0	
				- 30-	End of Boring at 28.0 ft Abandoned Borehole with Bentonite Cement Grout. Topped at the Surface with Bentonite Chips.		
		;		- :			



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area Griffith, Indiana Location

Boring No. Job No.

SB209 4077.0075

Sheet 1 of 2 Surface Elevation

647.4

Northing:

5715.5 4942,1

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION N Rec. Mois-Depth PID and Remarks (qa) (in.) ture Value (ft.) No. (ppm) Remarks (tsf) Grass/Gravel/Soil Surface FILL: Brown, Clayey Silt, Glass, Paper, Plastic 1 18 $\overline{\mathbf{M}}$ 4 0.0 FILL: Black, Silty, Fine to Medium Sand, 18 10 0.0 M Paper and Plastic FILL: Wood, Paper, Plastic, etc. M/W 0.0 2 $\overline{\mathbf{w}}$ 13 FILL: Wood Only, No Sample Collected, Not 0.0 Enough Volume 10 No Recovery - Refuse in tip of Spoon 5 W 42 0.0 $\underline{\nabla}$ Fabric in Tip of Spoon - No Recovery W 14 0.0 6 WATER LEVEL OBSERVATIONS **GENERAL NOTES** ile Drilling 12.0 ft. Upon Completion of Drilling ft. Start 1/23/96 End 1/23/96 1 me After Drilling Driller E & F Rig CME Chief JE. Depth to Water Logger PMS Editor DAP 850 Depth to Cave in Drill Method 3 1/4" I.D. HSA The stratification lines represent the approximate boundary between soil types and the transition may be gradual .4077:Gmi.40770 ..D., 519.5AG-J



LOG OF TEST BORING

Project American Chemical Service, Inc.
Off-Site Containment Area

Location Griffith, Indiana

Boring No.

SB209

Job No. Sheet 4077.0075 2 of 2

Surface Elevation

647.4

Northing: Easting:

5715.5 4942.1

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-Depth and Remarks (qa) (tsf) ture Value (ft.) (in.) (ppm) Remarks Dark Gray, Silty, Fine to Coarse SAND and Fine Gravel (SM) 149.0 Field analysis 14 $\overline{\mathbf{w}}$ 35 for VOCs and **PCBs** Brown Staining from 17 to 17.3 ft Dark Brown/Gray, Silty, Fine to Coarse SAND 18 26 150.0 Field analysis and Fine GRAVEL (SM) for VOCs and **PCBs** Dark Brown/Gray, Silty, Fine to Coarse SAND 9 12 W 21 140.0 and Fine GRAVEL (SM) Gray, Silty, Fine to Medium SAND (SM), 10 12 $\overline{\mathbf{w}}$ 21 10.0 Trace to Little Clay, Silt Increases with Depth 11 18 W 21 0.0 1 in. Thin Silt Seam from 27 to 27.2 ft Brown, Clayey Silt in Tip of Spoon Gray, Silty CLAY, Trace Fine Gravel (CL-ML) 12 20 M 21 4.0 0.0 30 End of Boring at 30.0 ft Abandoned Borehole with Bentonite Cement Grout. Topped Surface with Bentonite Chips.



Depth to Water

Depth to Cave in

transition may be gradual

The stratification lines represent the approximate boundary between soil types and the

LOG OF TEST BORING

Project American Chemical Service, Inc.
Off-Site Containment Area

Location Griffith, Indiana

Boring No. Job No.

SB210 4077,0075

Sheet

1 of 2

Surface Elevation Northing: **5690.0** 647.2

Easting:

Logger PMS Editor

Drill Method 3 1/4" I.D. HSA

DAP

J.4022:Cont.40220 Ib. LHICAGO.

850

4988.9

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 **SAMPLE** SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-Ν Depth PID and Remarks (qa) (in.) ture Value (ft.) (ppm) Remarks (tsf) REFUSE: Wood and Paper in Spoon 1 $\bar{2}$ M 14 5.0 REFUSE: Plastic and Wood 2 M 17 $\overline{0.0}$ REFUSE: Wood and Paper, Trace Clay 3 2 M 4 23.0 REFUSE: Black, Trace to Little, Fine to 12 350.0 4 M Medium Sand 5 12 M/W 18 Light Brown, Fine to Coarse SAND (SP), Some 122.0 Fine Gravel $\bar{\Delta}$ 6 12 $\overline{\mathbf{w}}$ 14 Gray, Silty, Fine to Medium SAND (SM) 80.0 WATER LEVEL OBSERVATIONS **GENERAL NOTES** ¥ 12.0 ft. Upon Completion of Drilling ¥ Start 1/23/96 End 1/23/96 ule Drilling 11me After Drilling Driller E&F Chief Æ Rig CME



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area Griffith, Indiana Location

Sheet Surface Elevation

Boring No.

Job No.

2 of 2 647.2

SB210

4077.0075

Northing: 5690.0 4988.9

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-PID Depth and Remarks (qa) ture Value (ft.) (ppm) Remarks (tsf) Gray, Silty, Fine to Coarse SAND (SM), Trace 7 W 10 283.0 Field analysis Fine to Coarse Gravel for VOCs and **PCBs** Gray Brown, Silty, Fine to Medium SAND 3 W 17 480.0 Field analysis (SM) for VOCs and **PCBs** Fine to Coarse, Fine to Medium GRAVEL (GP), Black Staining Light Brown, Silty, Fine to Medium SAND (SM) W 25 150.0 Gray, Silty, Fine to Coarse SAND (SM) Brown, Silty, Fine to Medium SAND (SM) 10 w 12 0.0 1/2 in. Silt Seam at 24.5 and 24.6 ft 25-Gray, Silty CLAY (CL-ML) 5.0 11 $\overline{\mathbf{w}}$ 19 4.0 End of Boring at 28.0 ft Abandoned Borehole with Bentonite Cement Grout. Topped at the Surface with Bentonite 30-Chips.



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area Griffith, Indiana Location

SB211 Boring No. 4077.0075 Job No. Sheet 1 of 2 Surface Elevation 651.0

Northing: 5663.6 5186.0

	S	AM			VISUAL CLASSIFICATION	<u> </u>	PRO	PERTIES
No.	Rec. (in.)	1	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
1	18	М	5		FILL: Brown to Black, Silty, Fine to Coarse Sand and Gravel, Some Clay, Cinders, Broken Glass		33.0	
2	14	M	2		FILL: Brown to Black, Silty, Fine to Coarse Sand and Gravel, Some Clay, Cinders, Broken Glass		73.0	
				- - 5-	Dark Brown to Gray, Silty, Fine to Coarse SAND (SM), Some Black Staining at 5 ft			
2	14	М	4	-	Light Brown, Silty, Fine to Medium SAND (SM)		20.0	
4	18	M/W	5	- - - ♀ ↓			60.0	Field analysis for VOCs and
				- 10	Grades to Gray, Silty, Fine to Coarse SAND (SM), Little to Some Clay from 10 to 10.3 ft			PCBs
5	17	W	7	(f.)	Light Brown, Silty, Fine to Medium SAND (SM), Some Gray Coloration		33.0	
6	18	W	8	- - - 15-	Light Brown, Silty, Fine to Medium SAND (SM), Some Gray Coloration, Propane-like Odor		5.0	
			W		LEVEL OBSERVATIONS GE	NERAL	NOT	TES
l'in Der Der	ile Dri ne Afte oth to to the strate ansition	er Dri Water Cave i	lling in ilines	represent	. Upon Completion of Drillingft. Start 1/24 Driller E & Logger PM Drill Method	IS Editor 3 1/4" I.I	D. HSA	Rig CME 850



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area

Griffith, Indiana Location

Boring No.

SB211 4077.0075

Job No. Sheet

2 of 2

Surface Elevation Northing: 5663.6

651.0

	S	ΑM	PLE		VICTIAL OF A COLLICATION	SOIL PROPERTIES					
No.	Rec.	Mois-	N Value	Depth	VISUAL CLASSIFICATION and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks			
					Light Brown, Silty, Fine to Medium SAND (SM), Some Gray Coloration						
7	24	W	10	-	Trace to Some, Fine to Coarse GRAVEL (GP)		73.0				
				_	Light Brown, Silty, Fine to Coarse SAND (SM)						
8	15	W	7	- - :	Black Stained, Medium to Coarse SAND (SP) to Fine Gravel, Trace Silt		233.0	Field analysis for VOCs and			
				- 20- -	Gray, Medium to Coarse, Silty SAND (SM)			PCBs			
9	20	w	16	-			180.0				
				-	Light Gray, Silty, Fine SAND (SM), Trace Medium to Coarse Sand						
10	18	w	26	_	Light Gray, Silty, Fine SAND (SM), Trace Medium to Coarse Sand		73.0				
				- - 25 -							
11	24	W	22	-	Light Gray, Silty, Fine to Medium SAND (SM)		33.0				
		:		-	Gray Clayey Silt from 27.8 to 28 ft						
12	18	w		-			0.0				
				- - 30-	Gray Silty CLAY (CL-ML)	>4.0					
		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		_	End of Boring at 30.0 ft Abandoned Borehole with Bentonite Cement Grout. Topped Surface with Bentonite Chips.		! 				



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area

Griffith, Indiana Location

Boring No. Job No.

SB212

Sheet

4077.0075 1 of 2

Surface Elevation

649.4

Northing:

5758.7 5453.6

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION qu Rec. Mois-Depth PID and Remarks (**a**p) (in.) ture (ft.) (ppm) Value Remarks (tsf) FILL: Gravel Surface, Black, Silty, Clayey, Fine to Coarse Sand and Gravel 23 24 M 0.0 3" split spoon utilized for this soil boring Light Brown/Rust Silty Fine to Medium SAND (SM) Dark Brown Change in Color at 3 ft 2 24 M 15 0.0 9 3 18 M/W 0.0 2 in. Silt Seam 4 18 $\overline{\mathbf{M}}$ 12 Clayey Silt from 7 to 7.3 ft 0.0 Light Brown/Rust Silty Fine to Medium SAND (SM) Light Brown/Rust Silty Fine to Medium SAND 5 24 M 14 0.0 (SM) Dark Brown/Rust, Silty, Fine to Medium 6 24 M 17 0.0 SAND (SM) Grading to Fine to Coarse Sand, Trace Fine Gravel Dark Brown, Silty, Fine to Medium SAND 7 \overline{W} 22 0.0 18 (SM) Dark Brown, Silty, Fine to Coarse SAND (SM), Trace Clay and Gravel **GENERAL NOTES** WATER LEVEL OBSERVATIONS 1/25/96 End ft. Upon Completion of Drilling Ψ Start 1/25/96 hile Drilling Rig CME ime After Drilling Driller E&F Chief JE Logger PMS Editor DAP 850 Depth to Water Drill Method 3 1/4" I.D. HSA Depth to Cave in The stratification lines represent the approximate boundary between soil types and the



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area Griffith, Indiana Location

Boring No. SB212 Job No. 4077.0075 Sheet 2 of 2

Surface Elevation 5758.7

649.4

Northing:

		W	ע		Location 100 Corporat	te Drive,		, Indiana	, TEL. (708) 6	1 .	Norming Easting:	-	53.6
	S	AM	PLE		VIS	SUAL	_ CLAS	SSIFICA	TION			L PRO	PERTIES
No.	Rec.	ture	Value	Depth (ft.)				emarks			qu (qa) (tsf)	PID (ppm)	Remarks
8	18	W	9		(SM), T	race Cla	ay and Gr					280.0	
9	18	W	11	_	Black, S	ilty, Fin	ie to Coai	rse SAND (SM)			1440.0	
	10			_	Dark Gra Fine Gra			Coarse SA	ND and				
10	12	W	16	_)							726.0	Field analysis
				- 20 -				arse SAND Coarse Gra					for VOCs and PCBs
11	18	w	19	- [1486.0	
				- -	Grades to	Light (Gray in C	Color, Trace	Clay				
12	18	W	22	— j								1788.0	Field analysis for VOCs
13	12	W	17	- 25- - 25- -	Light Gra	ıy, Silty	, Fine to	Coarse SAI	ND (SM)			515.0	
14	18	W/M	23	- [Light Gra	ıy, Silty	, Fine to	Coarse SAI	ND (SM)			302.0	
				- 				ayey SILT (parse Sand	CL-ML),				:
15				—							>4.0	25.0	· · · · · · · · · · · · · · · · · · ·
				— зо <u>—</u>		End	of Boring	g at 30.0 ft					
				- -	1			Bentonite (with Bentonit		:		; ! :	
					:					1		,	



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area

Griffith, Indiana Location

Boring No.

SB213

Job No. Sheet

4077.0075 1 of 2

Surface Elevation

653.1

Northing: Easting:

5637.8 5388.9

24077 Gint 40770 JD 4 HICAGU

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 **SAMPLE** SOIL PROPERTIES VISUAL CLASSIFICATION PID Rec. Mois-Depth and Remarks (qa) (in.) ture Value (ft.) (ppm) Remarks (tsf) FILL 20 M 0.0 Light Brown, Silty, Fine to Medium SAND (SM) Light Brown, Silty, Fine to Medium SAND 0.0 2 19 M 6 (SM) Light Brown, Silty, Fine to Medium SAND 0.0 24 7 M (SM) Light Brown, Silty, Fine to Medium SAND 24 M/W 6 0.0 (SM) Rust Colored Banding Present from 11 to 13 ft 0.0 $\overline{\mathbf{W}}$ 24 ∇ Grades to Dark Brown, Silty, Fine to Medium 0.0 $\overline{24}$ $\overline{\mathbf{w}}$ SAND (SM) **GENERAL NOTES** WATER LEVEL OBSERVATIONS ft. Start $\stackrel{\checkmark}{\underline{\checkmark}}$ 13.0 ft. Upon Completion of Drilling $\stackrel{\checkmark}{\underline{\checkmark}}$ 1/25/96 End 1/25/96 hile Drilling Rig CME rime After Drilling Driller E & F Chief JE 850 Logger PMS Editor DAP Depth to Water Drill Method 3 1/4" I.D. HSA Depth to Cave in The stratification lines represent the approximate boundary between soil types and the transition may be gradual.



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area

Griffith, Indiana Location

Boring No.

SB213

Job No. Sheet

4077.0075 2 of 2

Surface Elevation Northing: 5637.8

653.1

					2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-500					
No.	Rec.	Mois	PLE N Value	Depth	VISUAL CLASSIFICATION and Remarks	SOIL F	PROPERTIES PID Remarks			
7	18	w	4		Brown/Rust, Silty, Fine to Coarse SAND (SM), Some Fine to Coarse Gravel		0.0			
8	18	W	21	- - -		(0.0			
				20- -	Light Brown, Silty, Fine to Coarse SAND and Fine GRAVEL (GS)					
٥	18	W	16	- - - -	Gray, Silty, Fine to Coarse SAND (SM), Trace Fine Gravel	19	9.0			
10	8	W	18	- - - 25-	Dark Gray, Silty, Fine to Coarse SAND (SM), Trace to Some, Fine to Coarse Gravel, Some Black Staining	10	6.0 Field analysis for VOCs and PCBs			
11	15	W	27	- - 1	Coarse Broken Limestone and Gravel, Poor Recovery	199	9.0 Field analysis for VOCs			
]]	Dark Gray, Silty, Fine to Medium SAND (SM)					
12	18	W	28	30-	Coarse Gravel Present Thin Clay Seams (1/4") from 29 to 30 ft CLAY (CL)	160	0.0			
			<u>-</u>	- E	End of Boring at 31.0 ft Abandoned Borehole with Bentonite Cement Grout. Topped Surface with Bentonite Chips.		:			



LOG OF TEST BORING

Project American Chemical Service, Inc.
Off-Site Containment Area

Location Griffith, Indiana

Boring No.

SB214

647.2

Job No. Sheet 4077.0075 1 of 2

T4027:Gent40220 it. ChiCAGO

Surface Elevation Northing: **5946**

5946.4 5523.4

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-Depth PID and Remarks (**ap**) No. (in.) ture Value (ft.) (ppm) Remarks (tsf) TOPSOIL/Scrub Surface 18 $\overline{\mathbf{M}}$ Light Brown, Silty, Fine to Medium SAND 0.0 4 Some Rust Coloration 2 24 0.0 M 24 M 9 0.0 Slightly Lighter in Color 0.0 24 M 15 Light Brown, Silty, Fine to Coarse SAND (SM) with Trace to Little Fine Gravel M 0.0 24 9 Trace Clay 767.0 | Field analysis 18 M/W for PCBs 唟 WATER LEVEL OBSERVATIONS **GENERAL NOTES** 14.5 ft. Upon Completion of Drilling ft. Start 1/26/96 End 1/26/96 nile Drilling Driller E&F Chief Rig CME JE Time After Drilling Logger PMS Editor DAP 850 Depth to Water Drill Method 3 1/4" I.D. HSA Depth to Cave in

The stratification lines represent the approximate boundary between soil types and the transition may be gradual.



LOG OF TEST BORING

Project American Chemical Service, Inc.
Off-Site Containment Area

Location Griffith, Indiana

Boring No.

SB214 4077.0075

Job No. Sheet

2 of 2

Surface Elevation

647.2

Northing: Easting:

5946.4 5523.4

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 **SAMPLE** SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-Ν Depth PID and Remarks (qa) (in.) ture Value (ft.) (ppm) Remarks (tsf) Gray with Brown Staining, Silty, Fine to Coarse SAND and Fine GRAVEL (SM/GM) w 12 480.0 Field analysis 7 12 for VOCs W 9 Gray, Silty, Fine to Coarse SAND and Fine 8 552.0 Field analysis 12 GRAVEL (SM/GM) for PCBs 1 in. Thin Clayey SILT Lens at 22.5 ft 9 w 9 552.0 18 Field analysis for VOCs 480.0 10 20 W 20 Gray, Silty Fine SAND (SM) 25-Clayey SILT (ML) 11 24 19 Gray, Silty CLAY, Trace Fine Gravel (CL-ML) 3.5 49.0 M >4.0End of Boring at 28.0 ft Abandoned Borehole with Bentonite Cement Grout. Topped at the Surface with Bentonite 30-Chips.



LOG OF TEST BORING

Project American Chemical Service, Inc.
Off-Site Containment Area

Location Griffith, Indiana

Boring No. Job No.

SB215 4077.0075

Sheet

1 of 2

Surface Elevation

647.9

Northing:

6126.2 5615.5

	S	AM	PLE		VISUAL CLASSIFICATION	SOIL	PROF	ERTIES
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
	-			-	Black TOPSOIL	(6377		
1	18	M	4	_			0.0	
1	10	141	-	_	Light Brown, Silty, Fine to Medium SAND (SM)		0.0	
				_				
2	20	М	7	 -	Trace Coarse Sand and Some Clay from 4.5 to 5.0 ft		0.0	
				-	Brown Organic Matter (Leaves at 4.0 ft)			
3	24	M	16	- 5-			0.0	
				- [1				
			}	- []	Trace to Some Clay at 6.4 ft			
4	24	М	15		Clayey SAND Seams at 8.0, 8.3, 8.5 and 8.8 ft		0.0	····
			}	- [1]				
	24	74	17	- -			0.0	
5	24	M	17	. (1			0.0	
			}	- 10-n	Light Brown, Silty, Fine to Coarse SAND (SM), Trace to Some Fine Gravel			
6	20	М	12		Light Brown, Silty, Fine to Medium SAND (SM), Grading to Fine to Coarse Sand with Fine		0.0	
			}	-	to Coarse Gravel, Trace to Some Clay from 12.5 to 13.0 ft			
				-	12.5 to 15.0 t			
7	18	M/W	4	-			0.0	
			ŀ	_]		1		
				_ ¥5_	1			
<u>-</u>			W	ATER	LEVEL OBSERVATIONS G	ENERAL	NOT	ES
	ile Dr			15.0_f		6/96 End & F Chief	1/26/96 JE	Rig CME
Dep	oth to	Water			Logger P	MS Editor d 3 1/4" 1.	DAP	850
T		fication	n lines	represent	e approximate boundary between soil types and the			to ID. Thicago.



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area

Griffith, Indiana Location

Boring No.

SB215

Job No. Sheet

4077.0075 2 of 2

Surface Elevation

647.9

Northing:

6126.2 5615.5

Easting: 0.00 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION Mois-Depth PID and Remarks (qa) (tsf) No. ture (in.) Value (44) (ppm) Remarks 0.0 12 W Gray, Silty, Fine to Coarse SAND (SM) 9 W 10 24 780.0 Field analysis for VOCs and **PCBs** Gray, Silty, Fine to Medium SAND Grading to Silty, Fine to Coarse Sand with Some Fine Gravel (SM/GM) 10 24 W 9 897.0 Field analysis for VOCs and **PCBs** 20-Free Product, Sheen on Split Spoon **Black Staining Present** 18 19 11 520.0 Dark Gray, Fine to Coarse SAND (SP), Trace to Little Silt 12 12 W 18 634.0 Trace to Some, Fine to Coarse Gravel (SP) 25 18 W 19 13 85.0 14 18 W/M 42 145.0 Gray, Silty CLAY (CL-ML), Trace Fine to Coarse Sand 15 18 46 M 5.0 End of Boring at 31.0 ft Abandoned Borehole with Bentonite Cement Grout. Topped Surface with Bentonite Chips.



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area Location

Griffith, Indiana

Boring No. Job No.

SB216 4077.0075

Sheet

1 of 2

Surface Elevation Northing:

645.9 6325.7

5662.3

J:4027:Gnt 40770 JU. CHICAGO .

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-Ν Depth PID and Remarks (qa) ture Value (ft.) (ppm) Remarks (tsf) Black, Silty, Clayey TOPSOIL 18 M 3 0.0 Light Brown, Silty, Fine to Medium SAND (SM) 0.0 2 18 M 0.0 3 18 M Silty, Fine to Coarse SAND with Trace Fine Gravel (SM) 20 M 6 0.0 5 18 M 3 415.0 Field analysis for PCBs Gray at 12.5 ft, Silty, Fine to Coarse SAND (SM) 6 18 M 3 Gray, Silty, Fine to Coarse SAND (SM), Trace 4120.0 Field analysis Fine to Medium Gravel for VOCs and **PCBs** WATER LEVEL OBSERVATIONS **GENERAL NOTES** hile Drilling ₹ 12.5 ft. Upon Completion of Drilling ₹ ft. Start 1/29/96 End 1/29/96 Driller E&F Chief .ime After Drilling JE Rig CME Depth to Water Logger PMS Editor DAP 850 Drill Method 3 1/4" I.D. HSA Depth to Cave in

The stratification lines represent the approximate boundary between soil types and the



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area

Griffith, Indiana Location

Boring No. Job No.

SB216

Sheet

4077.0075 2 of 2

Surface Elevation

645.9

Northing:

6325.7 5662.3

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 **SAMPLE** SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-N PID Depth and Remarks (qa) (tsf) (in.) ture Value (ft.) (ppm) Remarks 18 M/W 5 204.0 18 $\overline{\mathbf{w}}$ 8 205.0 Gray Silty, Fine to Medium SAND (SM) 12 $\overline{\mathbf{w}}$ 10 95.0 10 18 24 $\overline{\mathsf{W}}$ 5.0 Gray, Silty CLAY (CL-ML) 18 W/M 33 4.0 0.0 End of Boring at 28.0 ft Abandoned Borehole with Bentonite Cement Grout. Topped at the Surface with Bentonite 30-Chips.



LOG OF TEST BORING

Project American Chemical Service, Inc.
Off-Site Containment Area

Location Griffith, Indiana

Boring No. Job No.

SB220 4077,0075

635.4

Sheet

1 of 2

Surface Elevation

Northing: Easting:

6496.9 5175.7

JA211.Gmt.427.10 Jb. 1886AL J.

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-Ν Depth PID and Remarks (qa) (in.) ture Value (ft.) (ppm) Remarks (tsf) Grass Surface, Dark Brown TOPSOIL with Grass 18 4 0.0 M Brown Organic Rich, Silty Fine SAND (SM), Trace Clay 2 18 w 12 0.0 Dark Gray, Silty, Fine to Medium SAND (SM) Trace Clay 18 W 17 63.0 18 W 16 263.0 Field analysis 2 in. Silt Seam at 10.0 ft for VOCs and Some Black Discoloration from 9.0 to 10.5 ft **PCBs** Light Gray, Silty Fine to Medium SAND (SM) Field analysis 18 $\overline{\mathsf{w}}$ 21 1862.0 for VOCs and 2 in. Dark Gray, Silty CLAY/Clayey SILT **PCBs** Seam at 11.5 ft 1 in. Clayey SILT at 12.5 ft $\widetilde{\mathbf{w}}$ 20 10.0 6 18 1 in. SILT Lens from 14.0 to 14.5 ft WATER LEVEL OBSERVATIONS **GENERAL NOTES** 1/30/96 End ft. Upon Completion of Drilling \(\frac{1}{2}\) ft. Start 1/30/96 ule Drilling E & F Rig CME ame After Drilling Driller Chief JE **PMS** DAP 850 Depth to Water Logger Editor Drill Method 3 1/4" I.D. HSA Depth to Cave in

The stratification lines represent the approximate boundary between soil types and the transition may be gradual.



LOG OF TEST BORING

Project American Chemical Service, Inc.
Off-Site Containment Area

Location Griffith, Indiana

Boring No. Job No.

SB220

Sheet

4077.0075 2 of 2

Surface Elevation

tion 635.4 6496.9

Northing: Easting:

5175.7

	S	AM	PLE		VISUAL CLASSIFICATION	ſ	PROF	PERTIES
No.	Rec.	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
		-						
7	24	W	20	-	Gray Silty CLAY (CL-ML)	3.5	0.0	1
; ;				-		>4.0		
í				_	End of Boring at 18.0 ft			
				- - - 20-	Abandoned Borehole with Bentonite Cement Grout. Topped at the Surface with Bentonite Chips.			
				_				
		,		_				
				-				
				-				
				_				
				— 25— -				;
				_				:
				_				;
				_ 30_			:	
				-			i İ	:
				_		<u> </u>	1	
1	11	ļ		ı				



LOG OF TEST BORING

Project American Chemical Service, Inc.
Off-Site Containment Area
Location Griffith, Indiana

Boring No. SB221 Job No. 4077.0075 Sheet 1 of 2

Surface Elevation 634.0 Northing: 6353.9

Easting: 5138.1

		AM	,		VISUAL CLASSIFICATION		L PRC	PERTIES
No.	K.	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
				-	Black/Dark Brown, Clayey TOPSOIL	•		
1	18	w	10	_			0.0	
				- 	Dark Gray, Silty, Fine to Medium SAND (SM)			;
				-				
2	18	W	12	_	Dense, Clayey, Silty, Fine to Coarse SAND (SM)		0.0	
			ŀ		Dark Gray, Silty Fine SAND (SM)			
3	18	W	12	- 5-			45.0	
				- 	} 			
			-	-	7.77 子界 月.1 .3.1			
4	18	w	30	- II	[6] · 		514.0	
			-	_ !				
	10		33	-			2105 0	
5	18	W	32				3105.0	Field analysis for VOCs and PCBs
			-	- 10-				PCBS
6	18	w	43	-			1338.0	Field analysis
				· []	3 in. CLAY Lens at 12 ft over 1 in. SAND		, ; ;	for VOCs and PCBs
			-	.])	Lens		,	
7	24	М	43		2 in. CLAY Seam at 12.3 ft Gray, Silty CLAY (CL-ML)	>4.0	1264.0	
			-	-				i
				- 15-		, 		
			W	ATER	LEVEL OBSERVATIONS GEI	NERA	LNOT	ES
	nile Dr ne Aft		<u>⊊</u> lling	f	Upon Completion of Drilling ft. Start 1/31/9	96 End F Chiet	1/31/9 JE	Rig CME
De	pth to pth to	Water			Logger PMS Drill Method	S Edito	r DAP	850
	he strat	ification may b	n lines e gradu	represent al.	he approximate boundary between soil types and the			nza ili. Lausasu.



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area Location

Griffith, Indiana

Boring No.

SB221 4077.0075

Job No. Sheet

2 of 2

Surface Elevation

634.0

Northing:

6353.9 5138.1

SAMPLE			PLE	•	VISUAL CLASSIFICATION	SOIL PROPERTIE		
No.	Rec (in.	. Mois-	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
				-	End of Boring at 15.0 ft			
				-	Abandoned Borehole with Bentonite Cement Grout. Topped at the Surface with Bentonite Chips.			
				-				
!				-				
ļ				20-				
				_				
ĺ				_	·			
;				_				
				25-			; ;	
				_			:	
			ļ					
			i	- 30-			:	
ļ							;	
		1				! i		



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area

Griffith, Indiana Location

Boring No. Job No.

SB222 4077.0075

Sheet

1 of 2

Northing:

638.6 6223.4

Surface Elevation

		W	<i>y</i>		2	100 Corporate Drive, Addison, Illinois 60101, TEL.	(708) 691-5	Easting:	50	69.4
	S	AM	PLE			VISUAL CLASSIFICATIO		I	L PRC	PERTIES
No.	u.	Mois- ture	N Value	Depth (ft.)		and Remarks		qu (qa) (tsf)	PID (ppm)	Remarks
						Dark Brown, Silty Clayey TOPSOIL				
1	6	М	8	-		FILL: Black, Wood and Clayey, Poor Rec	covery		0.0	
2	8	M	15	-					0.0	
	0	141	13	 - 5 -		Black, Silty, Fine to Medium SAND (SM) Trace Coarse Gravel	,		0.0	
3	8	W	20	_		Gray, Silty, Fine to Medium SAND (SM)			0.0	
4	18	w	14	- - - 10-		Color Changing Dark Gray to Gray			15.0	
5	12	w	27	-		Dark Gray, Silty, Fine to Medium SAND ((SM)		81.0	
6	12	W	24	- - - 15-					3015.0	Field analysis for VOCs and PCBs
		•	W	ATEF	R L	EVEL OBSERVATIONS	G	ÉNERA	L NOT	ΓES
De _l De _l	ne After pth to pth to he strate ransition	er Dri Water Cave	in n lines	represent			Driller E Logger P	31/96 End & F Chief MS Edito ad 3 1/4" I	r DAF .D. HSA	Rig CME 850



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area

Griffith, Indiana Location

Boring No. Job No.

SB222 4077.0075

Sheet

2 of 2

Surface Elevation Northing:

638.6 6223.4

5069.4

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SOIL PROPERTIES SAMPLE VISUAL CLASSIFICATION qu (qa) (tsf) PID Rec. Mois-N Depth and Remarks No. (ppm) (in.) ture Value {ft.} Remarks 7 22 154.0 18 W Gray, Clayey SILT (ML) 1 in. Sand Seam at 17.5 ft Gray, Silty CLAY (CL-ML) 20 M 19 3.5 45.0 >4.0 End of Boring at 20.5 ft Abandoned Borehole with Bentonite Cement Grout. Topped at the Surface with Bentonite Chips. 25-30-



LOG OF TEST BORING

Project American Chemical Service, Inc.
On-Site Containment Area

Location Griffith, Indiana

Boring No.
Job No.

SB223 4077,0075

Sheet

1 of 2

Surface Elevation Northing: 672

tion 638.5 6729.8

Easting:

Drill Method 4 1/4" I.D. HSA

5059.2

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 **SAMPLE** SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois PID Depth and Remarks (ap) No. 🖺 (in.) ture Value (ft.) (ppm) Remarks (tsf) Gray Slag, Gravel, Black Sand and Gravel (FILL) Yellow Brown Fine SAND (SP), Trace Roots, Ī 14 M 5 0.0 Trace Fine Gravel Dark Yellow Brown to Brown, Fine SAND 2 M 4 6.0 16 (SP), Little Silt and Clay, Musty Propane-Like Odor Present 5 Light Olive Brown Fine SAND (SP), Musty 3 W 5 16 6.0 Odor Gray to Olive Gray Brown Fine SAND (SP), 4 14 W 8 3.0 Little Silt, Trace Medium to Coarse Sand and Gravel 10-Gray Fine SAND (SP), Trace Organics, Roots 5 14 W 33.0 Gray to Gray Brown Fine SAND (SP), Little W 9 14 6.0 6 Silt, Trace Medium to Coarse Sand and Fine Gravel, Sweet Propane Like Odor WATER LEVEL OBSERVATIONS **GENERAL NOTES** ft. Start 2/12/96 End While Drilling ft. Upon Completion of Drilling 2/12/96 ne After Drilling Driller E & F Chief GH Rig CME 55 DAP Editor **PMS** Depth to Water Logger

The stratification lines represent the approximate boundary between soil types and the transition may be gradual.

Depth to Cave in



LOG OF TEST BORING

American Chemical Service, Inc. Project On-Site Containment Area Griffith, Indiana Location

Boring No. Job No. Sheet

SB223 4077.0075

2 of 2

Surface Elevation Northing:

638.5 6729.8

5059.2

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION qu Rec. Mois-Ν PID Depth and Remarks (qa) ture Value (ft.) (ppm) Remarks (tsf) Gray Brown Fine SAND (SP), Sweet Propane 18 $\overline{\mathsf{w}}$ 13 3.0 Like Odor, Silt and Clay Lense from 17 to 17.2 Grades into Gray, Fine to Coarse SAND (SP) at W/M 3.5-4.0 18 51.0 19.5 to 20.0 ft Very Stiff, Gray Silty CLAY (CL-ML) 12 M 4.0 End of Boring at 22.5 ft Abandoned Borehole with Bentonite Cement Grout. Topped at the Surface with Bentonite Chips. 25 30-

B2

PILOT TEST CELL SOIL BORING LOGS



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana Boring No.

SB145

639.6

Job No. Sheet

4077.0075 1 of 2

Surface Elevation

Northing: 6797.4 5603.5

		W	<i>y</i>		100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691	Eas	sting:	560	3.5
	S	AM	PLE		VISUAL CLASSIFICATION		SOIL	PRO	PERTIES
No.	Rec.	1	N Value	Depth (ft.)	and Remarks		qu (qa) tsf)	PID (ppm)	Remarks
					Brown SAND and GRAVEL (GP)			·	
1	14	М	10		Light Brown Fine SAND (SP), Trace Fine Gravel			0.0	PID headspace not measured on samples
2	18	M/W	3	-	Brown Stained Fine SAND (SP), Grades into Gray Stained Fine Sand at 4.3 ft		-	0.0	
7	12	w	2	- 5- - - -	Brown Fine SAND (SP), Little Medium to Coarse Sand and Fine Gravel		-	0.0	
4	6	w		- -	Brown and Dark Brown Fine SAND (SP)		-	0.0	
5	8	w		- 10 - - -	Dark Brown Staining Present		-	0.0	
6	4	W	16		Light Blue Paint Like Substance and Some Fine SAND (SP)		_	0.0	
			W	– 15– ATEI	EVEL OBSERVATIONS	GENE	RAL	TON.	ES
Tir De De	nile Dr ne Aft pth to pth to	ter Dr Wate Cave	<u>¥</u> illing r in		Upon Completion of Drilling ft. Start Driller Logger Drill Me	2/8/96 E & F DAP	End Chief Editor	2/8/9 GH	6 Rig CME 55



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon Location Griffith, Indiana

Job No. Sheet Surface Elevation

Boring No.

SB145 4077.0075

2 of 2

639.6 Northing: 6797.4 5603.5

	C	ΑМ	DI E			SOI	PP∩□	ERTIES
о.	Rec.	Mois-	N Value	Depth	VISUAL CLASSIFICATION and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
7	18	w	12	- -	Light Blue Paint Like Substance Coating on White Rubber Material Brown Fine SAND (SP) at 17.0 ft		0.0	
	18	w	9	- - - - 20-	Light Blue Paint Stained Fine SAND (SP)		0.0	
	18	w	13	- - -	Gray Brown to Brown, Fine to Coarse SAND (SP), Gray Brown Silt at 22.2 to 22.5 ft		0.0	
0	18	М	12	 - _ - _ 25_	Hard, Gray Silty CLAY (CL-ML), Trace Fine to Coarse Sand	4.5	0.0	
					End of Boring at 25.5 ft Borehole Abandoned with Natural Cave In and Bentonite Chips from 5 ft to Surface.			
				- 30- - -				



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No. **SB146** Job No. 4077,0075 1 of 2 Sheet Surface Elevation 639.6

JM077/Gint/10770_ID: CHICAGO

6783.8 Northing: Easting: 5610.0

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 **SOIL PROPERTIES** SAMPLE VISUAL CLASSIFICATION PID Rec. Mois-Depth and Remarks (ap) (in.) ture (ft.) (ppm) Remarks Brown SAND and GRAVEL (GS) 17 PID headspace 12 M Gray Brown Fine SAND (FILL), Little Medium 0.0 to Coarse Sand and Gravel not measured on samples 2 Brown Fine SAND (SP) 0.0 10 M 5 Brown Stained Fine SAND (SP) 12 0.0 No Recovery 4 0 W NR 0.0 10-Brown, Fine to Coarse SAND (SP) to 11.5 ft, $\overline{0.0}$ 5 18 Becomes Fine to Coarse Sand and Gravel from 11.5 to 12.5 ft Gray Brown Fine SAND (SP), Thin Silt Seam 10 $\overline{\mathbf{w}}$ 12 0.0 6 from 14.2 to 14.3 ft WATER LEVEL OBSERVATIONS **GENERAL NOTES** 2/8/96 End 2/8/96 Vhile Drilling ft. Upon Completion of Drilling Start Time After Drilling Driller E & F GH Rig CME 55 Chief Logger DAP Depth to Water Editor **PMS** Drill Method 2 1/4" I.D. HSA Depth to Cave in The stratification lines represent the approximate boundary between soil types and the transition may be gradual.



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No.

SB146 4077.0075

Job No. Sheet

2 of 2

Northing:

639.6

6783.8 5610.0

Surface Elevation

				ا 21	100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 69	1-5000	Easting:	5610).0	
	S	AM	PLE			VISUAL CLASSIFICATION		SOIL	PROF	PERTIES
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)		and Remarks		qu (qa) (tsf)	PID (ppm)	Remarks
7	18	W	14	-		Gray Brown Fine SAND (SP), Little to Some, Medium to Coarse Sand and Fine Gravel			0.0	
8	16	W	12			Gray Brown Fine SAND (SP), Little Silt			0.0	
	18	w	12	- - -		Gray Brown, Fine to Coarse SAND and Fine GRAVEL (SP), Tip of Split Spoon had Clay in it			0.0	
10		w		-		Gray Brown, Fine to Coarse SAND (SP), Silt Seam from 23.5 to 23.6 ft				
11		М	18	 - 25 -		Very Hard to Stiff, Gray Silty CLAY (CL-ML), Trace Fine to Coarse Sand and Gravel		4.0- >4.5		
				- - - - - - - -		End of Boring at 26.0 ft Borehole Abandoned with Natural Cave In and Bentonite Chips from 5 ft to Surface.				
\		i		i	i :			; ;		



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana Boring No.

SB147 4077.0075

Job No. Sheet

1 of 2

Surface Elevation

639.7

JM027/Gin1M0770_ID, CHICAGO ____

Northing: 6777.3 5597.9

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SOIL PROPERTIES **SAMPLE** VISUAL CLASSIFICATION Rec. Mois-PID Depth and Remarks (qa) (tsf) (in.) ture (ft.) (ppm) Remarks Gray Brown Fine SAND (SP) 1 10 M 12 0.0 PID headspace not measured on samples Gray Stained Fine SAND (SP) 0.0 2 W 16 5 3 Olive Brown Fine SAND (SP) 0.0 W 16 2 Olive Brown to Brown Stained, Fine to Coarse W 0.0 4 16 SAND (SP) 10-Olive Brown to Brown Stained, Fine to Coarse 0.0 5 14 2 SAND (SP) Olive Brown to Brown Fine SAND (SP) 0.0 14 $\overline{\mathbf{w}}$ 6 WATER LEVEL OBSERVATIONS **GENERAL NOTES** ft. Upon Completion of Drilling 🛂 While Drilling ft. Start 2/8/96 End 2/8/96 Time After Drilling Driller E&F Chief GH Rig CME 55 Depth to Water Logger DAP Editor **PMS** Depth to Cave in Drill Method 2 1/4" I.D. HSA The stratification lines represent the approximate boundary between soil types and the transition may be gradual.



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana Boring No. Job No.

SB147 4077.0075

Sheet

Surface Elevation

2 of 2 639.7

Northing:

6777.3 5597.9

\geq					21	00 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-	5000 		5597	
SAMPLE Rec. Mois- N Depth					N Depth and Remarks			SOIL PROPERTI		
7	(in.)	W	Value	(ft.)		Olive Brown to Brown Fine SAND (SP)		(tsf) 	(ppm) 0.0	Remarks
8	18	w	9	- - - - 20-		Dark Gray Brown Fine SAND (SP), Some Medium to Coarse Sand and Fine Gravel			0.0	
า	14	w	14	 -		Gray, Fine to Coarse SAND (SP), Trace to Little Fine Gravel			0.0	
10	18	W/M	11	 - - 25-		Very Stiff, Gray Silty CLAY (CL-ML), Trace Fine to Coarse Sand and Fine Gravel				
						End of Boring at 26.0 ft Abandoned with Native Back Fill Cave-in, Bentonite Chips to Surface				
				- - - -						
	1				1					



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana Boring No.

SB148

639.5

Job No. Sheet

4077.0075 1 of 2

Surface Elevation Northing:

6785.2 5620.0

		W	<i>y</i>		í 21	00 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-500	Easting:	5620	0.0
	S	ΑM	PLE			VISUAL CLASSIFICATION	7	PROF	PERTIES
No.	Rec. (in.)	1	N Value	Depth (ft.)		and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
						Brown SAND and GRAVEL (GP)			
1			N/A	-		CONCRETE		0.0	PID headspace not measured on samples
				-		Brown, Fine to Medium SAND (SP), Solvent Odor Present			
2	12	M	8	-				0.0	
				5- 					
3	14	M	4	-		Brown, Fine to Coarse SAND (SP), Trace Fine Gravel		0.0	
				-					
4	0			-				0.0	
				- 10- -					
5	4	w	6	-		Brown to Dark Brown Stained, Fine to Coarse SAND and GRAVEL (SP)		0.0	
				_					
6	12	W	9	_		Gray Brown, Fine to Coarse SAND and Fine GRAVEL (SP) to 14.2 ft, Then into Gray Brown Fine Sand		0.0	
			W	– 15– ATFI	R L	EVEL OBSERVATIONS G	ENERAL	NOT	ES
fir De De	nile Dine Aft pth to pth to	er Dr Wate Cave	∑ illing r in		ft.	Upon Completion of Drilling ft. Start 2/9 Driller E & Logger DA Drill Method	/96 End & F Chief AP Editor	2/9/96 GH r PMS	
`\ t	ransitio	n may l	oe grad	ual.	ii iiic	approximate boundary between soil types and the		J/4027\Gmt/402	770 ID CHICAGO



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No. SB148 Job No. 4077.0075

2 of 2 Sheet

Surface Elevation 639.5

Northing: 6785.2 5620.0

						Location Griffith, Indiana 2100 Corporete Drive, Addison, Illinois 60101, TEL. (708) 691-50							
SAMPLE						VISUAL CLASSIFICATION							
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)		and Remarks	7	qu (qa) (tsf)	PID (ppm)	Remarks			
7	18	W	9	- - -		Gray Brown Fine SAND (SP)			0.0				
8	18	w	10	8	8	8	- - 20-		Gray Brown to Gray, Fine to Medium SAND (SP), Little Coarse Sand to 19.0 ft, Grades into Gray Brown Fine Sand, Gray Silt from 19.6 to 20.0 ft			0.0	
9	18	W			- - -		Gray, Fine to Coarse SAND (SP), Gray Clayey Silt in Tip of Spoon at 22.3 ft			0.0			
10	18	W/M	14	- - -		Stiff, Gray, Clayey SILT to Silty CLAY (CL-ML)		2.5-3.0	0.0				
				- 25 - - - - -		End of Boring at 25.0 ft Abandoned with Natural Cave in of Soils and Bentonite Chips from 6.0 to Surface, Topped at Surface with Gravel							
				_ - - 30- - -									



LOG OF TEST BORING

Project American Chemical Service, Inc.
Off-Site Contaminent Area
Location Griffith, Indiana

Boring No. SB224
Job No. 4077.0075
Sheet 1 of 2
Surface Elevation 646.9
Northing: 6197.5

Easting: 5301.8

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 **SAMPLE** SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-PID Depth and Remarks (qa)(in.) ture Value (ft.) (ppm) Remarks (tsf) Vegetation, Prairie Grass, Dark Brown Clay and Sand (FILL) Brown Sand, CLAY and GRAVEL (FILL) ī 14 10 0.0 M PID headpsace Olive Gray Clay from 2.0 to 2.5 ft not measured Dark Brown to Brown Fine SAND (FILL), 12 0.0 2 14 M Little Silt, Trace Fine to Coarse Gravel, Some Roots, Leaves, etc. Dark Brown Fine SAND (FILL), Trace Fine to 3 629.0 M N/A Coarse Gravel, Refusal No Recovery, Spoon all Dark Purple Brown 4 0 W N/A 0.0 Varnish (FILL) No Recovery, Dark Brown/Purple Paint on 0.0 0 W Spoon (FILL) Dark Brown SAND, SILT (FILL) Purple 0.0 3 Coated Spoon WATER LEVEL OBSERVATIONS **GENERAL NOTES** 2/7/96 End Vhile Drilling ft. Upon Completion of Drilling 2/7/96 ft. Start GH ime After Drilling Driller E&F Chief Rig CME 55 **PMS** DAP Editor Depth to Water Logger Drill Method 2 1/4" I.D. HSA Depth to Cave in

The stratification lines represent the approximate boundary between soil types and the



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Contaminent Area

Griffith, Indiana Location

Boring No. Job No.

SB224 4077.0075

Sheet 2 of 2

646.9

Surface Elevation Northing: 6197.5 5301.8

		W	V	·-	Location Griffith, Indiana 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-500	Northing: Easting: 0	5301	
	S	AM	PLE		VISUAL CLASSIFICATION	SOIL	PROP	ERTIES
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
7	12	w	2	-	Light Purple/Brown Coated Spoon, Light Brown to Yellow-Brown, Oily, Fine SAND (FILL)		0.0	
8	8	W	11	- - - - 20-	Light Olive Brown, Fine to Coarse SAND (SP)		0.0	
9	12	w	10	-	Brown to Olive Brown, Fine to Coarse SAND (SP), Trace fine to Coarse Silt and Fine Gravel		0.0	
10	12	w	7		Brown Fine SAND (SP), Some Dark Gray Staining from 24.5 to 25.0 ft		0.0	
1	16	W/M	8	25 - 	Brown Fine Sand (SP), Grading into Gray Brown Fine to Coarse SAND at 26.5 ft Very Stiff, Gray, Silty CLAY (CL-ML), Trace Fine to Coarse Sand	3.5	0.0	
12	0	М		- - 	Very Stiff, Gray Silty CLAY (CL-ML)	3.5-4.5	0.0	
				- 30- - -	End of Boring at 29.5 ft Borehole Backfilled with Natural Cave-in and Bentonite Chips			



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Contaminent Area Location Griffith, Indiana

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000

Boring No. **SB225** Job No. 4077.0075 Sheet 1 of 2 Surface Elevation 647.3

_J/4077/Gmt/40770_ID_CHICAGO ____

Northing: 6208.5 5283.1

SOIL PROPERTIES **SAMPLE** VISUAL CLASSIFICATION PID Rec. Mois-Depth and Remarks (qa) No. (in.) ture (ft.) (ppm) Value Remarks (tsf) Prairie Grass, Dark Brown Fine SAND and CLAY (FILL) 1 4 M 10 0.0 PID headspace not measured 2 3 $\overline{0.0}$ M White Paint Like Substance at 4.5 ft (FILL) Gray Green and White Paint Substance (FILL) 3 M/W 0.0 Possible buried drum Purple, Green, Brown Layered Substance M/W 0.0 4 (FILL) Gray, Dark Brown, Fine Sand and Silt (FILL) 0.0 5 M 6 Orange Brown Fine Sand at 12.0 ft Very Dark Reddish Brown Fine Sand, Silt, W 0.0 6 3 Sticky, Grades into Olive Brown Fine Sand at 14.5 ft (FILL) WATER LEVEL OBSERVATIONS **GENERAL NOTES** 2/7/96 End ft. Upon Completion of Drilling Ψ 2/7/96 'Vhile Drilling ft. Start Rig CME 55 ime After Drilling E & F Driller Chief GH **PMS** Depth to Water Logger DAP Editor Drill Method 2 1/4" I.D. HSA Depth to Cave in The stratification lines represent the approximate boundary between soil types and the transition may be gradual.



LOG OF TEST BORING

Project American Chemical Service, Inc.
Off-Site Contaminent Area
Location Griffith, Indiana

Location Griffith, Indiana Northing
Easting:
2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000

Boring No. SB225
Job No. 4077.0075

Sheet 2 of 2

Surface Elevation 647.3 Northing: 6208.5

Easting: 5283.1

	S	AM	PLE		VISUAL CLASSIFICATION	SOIL PROPERTIES		
No.	Rec.	Mois-	N eulaV	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
7	14	w	11		Dark Brown, Varnish Like Stained Fine Sand to 16.5 ft, Grades into Brown Fine Sand then to Olive Brown Fine Sand from 17.0 ft to 17.5 ft (FILL)		0.0	
8	16	w	10		Brown to Olive Brown Stained Fine SAND (SP)		0.0	
9	0	w	15	— 20— - — -	Brown to Olive Brown, Fine to Coarse SAND (SP), Trace Fine Gravel			
10	18	w	9	- - - - - 25-	Olive Gray, Brown Fine SAND (SP), Trace Medium to Coarse Sand and Fine Gravel, Thin Black Stained Layers, 1 in. Apart from 24.4 to 25.0 ft			
11	18	W/M	6		Olive Brown/Gray, Fine to Coarse SAND (SP), Little Fine Gravel Very Stiff, Gray Silty CLAY (CL-ML)	3.5		
12	16	M	11	- - -	Very Stiff, Gray Silty CLAY (CL-ML), Trace Fine to Coarse Sand	4.0-4.5		
				— 30— - —	End of Boring at 30.0 ft Borehole Backfilled with Cave-in and Bentonite Chips	-		



transition may be gradual

LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Contaminent Area Griffith, Indiana Location

Boring No. **SB226** Job No. 4077.0075 Sheet

1 of 2

Surface Elevation 647.5

J:4077:Gint:40770 ID. CHICAGO

Northing: 6192.7 Easting: 5286.9

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SOIL PROPERTIES **SAMPLE** VISUAL CLASSIFICATION PID Mois Depth and Remarks (qa) (tsf) No. 🖺 (in.) ture (ft.) (ppm) Value Remarks Gray Brown Clay and Fine Sand (FILL) M 5 PID headspace not measured Gray Brown Clay and Sand, Grades into Dark 2 8 M 9 Gray-Stained Fine Sand (FILL) Silty Clay, Metal, Plastic (FILL) 3 6 M 22 Dark Brown and Grayish White Stained, W 4 3 Fibrous Material (FILL) No Recovery (FILL) 5 0 6 Light Gray Stained Fine Sand and Silt (FILL) 10 W 12 6 Olive Brown Fine SAND (Native Soil) (SP) WATER LEVEL OBSERVATIONS **GENERAL NOTES** ft. Upon Completion of Drilling Ψ 2/7/96 Vhile Drilling Start 2/7/96 End ime After Drilling Driller E & F Rig CME 55 Chief GH Depth to Water Logger DAP Editor **PMS** Depth to Cave in Drill Method 2 1/4" I.D. HSA The stratification lines represent the approximate boundary between soil types and the



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Contaminent Area Griffith, Indiana Location

Boring No.

SB226 4077.0075

Job No. Sheet

2 of 2

647.5 Surface Elevation 6192.7

Northing:

	S	AM	PLE		VISUAL CLASSIFICATION		SOIL	. PROP	ERTIES
No.	Rec.	Mois- ture	N Value	Depth (ft.)	and Remarks	1	qu (qa) (tsf)	PiD (ppm)	Remarks
7	10	W	14		Brown to Olive Brown Fine SAND (SP), Some Dark Brown Staining				
8	14	w	10	- - - - 20-	Olive Gray Brown, Fine to Coarse SAND and Fine GRAVEL (SP)				
Q	16	w	16	-	Gray Brown Fine SAND (SP), Little to Some Fine Sand and Gravel	~-•			
10	14	w	14		Olive Gray Brown, Fine to Coarse SAND (SP), Little Medium to Coarse Sand and Gravel, Silt Seam from 24.3 to 24.6 ft	•			
11	18	W/M	11	-	Gray Fine SAND (SP), Little Medium to Coarse Sand Stiff to Hard, Silty CLAY (CL-ML)		4.0- >4.5		
12	16	M	12	-	Very Stiff, Gray, Silty CLAY (CL-ML), Trace Fine to Coarse Sand and Gravel		4.0 4.5		
				— 30— - —	End of Boring at 30.0 ft Borehole Backfilled with Cave-in and Bentonite Chips				



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Contaminent Area

Griffith, Indiana Location

Boring No.

SB227 4077.0075

Job No. Sheet

1 of 2

Surface Elevation Northing: 6212.0

646.9

		W	<i>y</i>		2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-500	Easting:	5297	.6
	S	AM	PLE		VISUAL CLASSIFICATION	1	PROP	ERTIES
No.	Rec.	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
				_	Prairie Grass and Brown Clay, Sand (FILL)			
1	10	M	9	_	Grayish Brown Clay Fill to 2.0 ft, Then into Orange Brown Fine Sand (FILL)			PID headspace not measured
2	2	M	9	- - - -	2" Recovery, Gray Brown Fine Sand and Clay (FILL)			
3	16	M	6	— 5— - —	Red, Blue, Green, Brown Stained Sand, Clay and Gravel (FILL)			
4	4	M	8	- -	Black Stained Clay, Some Fine to Coarse Sand (FILL)			
5	14	M/W	2	10- 	Dark Brown, Roots, Silt, Peat to 10.5 ft, Grades into Brown Fine Sand to 12.0 ft, Then into Gray Stained Fine Sand from 12 to 12.5 ft (FILL)			
6	18	w	7	- 15-	Dark Brown Varnish Stained, Fine SAND (SP), Grades into Brown, Fine Sand at 14.2 ft (Native			
		.1	W	1	R LEVEL OBSERVATIONS G	ENERA	LNOT	ES
D	hile Di ime Af epth to epth to The stra transitio	ter Dr Wate Cave	rilling r in	represer	Driller E	1/96 End & F Chief AP Edito d 2 1/4" I	r PMS .D. HSA	Rig CME 55



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Contaminent Area Location

Griffith, Indiana

Boring No.

SB227 4077.0075

646.9

Job No. Sheet

2 of 2

Surface Elevation Northing: 6212.0

	S	AM	PLE		VISUAL CLASSIFICATION	SOIL	ERTIES	
lo.		Mois-	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
7	14	W	9	- - 	Soil) Brown Fine SAND (SP), Some Thin (<1.0 inch) Black Stained Seams from 16.5 to 17.5 ft			
3	14	w	10		Brown to Gray Brown Fine SAND (SP), Little Medium to Coarse Sand and Fine Gravel, Dark Brown Stained Zone from 19.2 to 19.4 ft			
)	18	W	8	-	Brown to Gray Brown, Fine to Coarse SAND (SP)			
0	18	w	11	- - - - 25-	Gray Brown Fine SAND (SP), Little Medium to Coarse Sand and Fine Gravel, Grades to Gray in Color at 24.5 ft			
1	18	W/M	10	-	Gray Brown to Gray Stained, Fine SAND (SP) to 27.1 ft			
2	18	М	12	-	Very Stiff, Silty CLAY (CL-ML)	3.5-4.5 4.0- >4.5		
				- 30 - -	End of Boring at 29.5 ft Borehole Backfilled with Cave-in and Bentonite Chips			

B3

REMAINING SOIL BORING LOGS



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No.

SB101 4077.0075

Job No. Sheet

1 of 2

Northing:

Surface Elevation 637.9 6892.9

J\4077\Gint\40770_ID; CHICAGO

		-			100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5	Easting:	525	3. <i>1</i>
	S	AM	PLE		VISUAL CLASSIFICATION	SOIL	PROF	PERTIES
No.		Mois- ture	1	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
					Brown Sand and Gravel (Slag) (FILL)			
1	12	M/W	5	_	Dark Brown to Black Stained, Fine SAND (SP), Grades into Gray Brown, Fine to Coarse SAND, Little Fine to Coarse Gravel		5580.0	Field analysis for VOCs and PCBs
2	12	W	4	- - -	Gray Fine SAND, Little Medium to Coarse Sand (SP), Slight Organic Odor			Field analysis for VOCs and PCBs
3	18	W	8	- 5 - - -	Gray Fine SAND (SP), Trace Medium Sand, Slight Organic Odor		579.0	
4	18	w	7	- - -			215.0	
5	20	w	14	- - 10- - -			179.0	
	20	•	- '	- - -				
6	18	W	14	_	Slight Organic Odor Present		65.0	
	Ī	1	W	- 15- ATE	LEVEL OBSERVATIONS	SENERAL	. NOT	ES
i'ii De De	hile Dime After to	ter Dr Water Cave	∑ illing r in		Upon Completion of Drilling ft. Start 1/ Driller E Logger I	17/96 End 6 & F Chief DAP Editor od 2 1/4" [.	1/17/96 GH PMS	



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No.

SB101 4077.0075

637.9

Job No. Sheet

2 of 2

Surface Elevation Northing:

6892.9

5253.7 Easting:

_					21	00 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-500	0 -				
			PLE			VISUAL CLASSIFICATION	SOIL	SOIL PROPERTIES			
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)		and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks		
								238.0			
7	20	w	8	_		Gray Brown Fine SAND (SP), Trace Silt and Shell Fragments, Slight Organic Odor Present		238.0			
				-							
8	20	W	14					1348.0			
				20 		Very Stiff, Gray CLAY (CL)		1211.0			
						End of Boring at 20.5 ft					
						Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.					
				_							
				 - 25							
		·		_ 25_							
				_							
				-							
				_							
				- 30-							
							1				
! !	1	!						· · · · · · · · · · · · · · · · · · ·			



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No.

SB102

637.8

Job No. Sheet

4077.0075 1 of 2

Surface Elevation

Northing:

6873.7 5269.6

		W	ν		2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-500	Easting:	5269.6	
	S	ΑM	PLE		VISUAL CLASSIFICATION		. PROPER	TIES
No.	<u> </u>	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm) F	Remarks
1	12	М	9	-	Green and Brown CLAY (CL) Black Stained Fine SAND, Organic Odor and Roots Present		623.0	
2	18	M/W	4	 5	Black and Gray Stained Fine SAND (SP) to 4.5 ft, Grades to Brown Fine SAND (SP), Organic Odor Present		for V	d analysis VOCs and PCBs
3	20	w	8	-	Light Gray Brown Fine SAND (SP), Organic Odor Present		603.0	
4	20	w	5		Gray Fine SAND (SP), Trace Medium to Coarse Sand, Organic Odor		2735.0	
5	18	W	5	— 10	Trace Shell Fragments and Organic Odor Present		146.0	
6	20	W	10	- - - - - - 15-	Gray and Brown Fine SAND (SP), Little Medium to Coarse Sand, Trace Shells and Shell Fragments, Organic Odor Present		432.0	
i	1	i	W		LEVEL OBSERVATIONS GE	NERAL	NOTES	
fin De De	nile Dr ne Aft pth to pth to he strat	er Dri Water Cave	in n lines	represen		96 End F Chief P Editor 2 1/4" I.	1/17/96 GH Rig PMS	g CME 55



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon Location Griffith, Indiana

Sheet 2 of 2 Surface Elevation Northing:

Boring No.

Job No.

6873.7 5269.6

SB102

637.8

	Ü	U		Location Griffith, Indiana 100 Corporate Drive, Addison, Illinois 60101, TEL. (7)	, 908) 691-500	Easting:	526	9.6
	Mois- ture		Depth	VISUAL CLASSIFICATION and Remarks		1	PID (ppm)	PERTIES Remarks
7 16	w	10	- - -	Gray Brown Fine SAND (SP), Trace Shells Trace Medium to Coarse Sand, Organic Od Present			704.0	
3 16	W	15	 20	Gray Clay Zone at 19.5 to 19.8 ft Grades into Gray and Brown, Fine to Coars SAND and GRAVEL (GP), Organic Odor Present	e		3245.0	Field analys for VOCs ar PCBs
22	М	10	-	Very Stiff, Gray Brown, Silty CLAY (CL)		4.0	1325.0	
			- - - - - - -	End of Boring at 23.0 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.				
			30-					



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon Location

Griffith, Indiana

Boring No. SB103 Job No. 4077.0075

Sheet 1 of 2

637.8 Surface Elevation Northing: 6855.1

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 5287.1

	S	AM	PLE		VISUAL CLASSIFICATION	SOIL	PRO	PERTIES	
	Rec. (in.)		N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks	
1	20	M	6		Dark Brown Fine SAND (SP), Little Silt, Trace Organics, Roots, Organic Odor Present, Some Black Staining from 1 to 2 ft		1041.0	Field analysis for PCBs	
2	20	M/W		- - - 5	Black Sandy SILT (ML), Trace Organics (Roots), Organic Odor Present		0.0	Possible topsoil layer, organic roots	
				-	Olive Brown Fine SAND (SP), Little Silt,				
1	18	W			Organic Odor Present		0.0		
4	20	W		- - 10	- 10-	Gray Brown to Gray Fine SAND (SP), Organic Odor Present		0.0	
5	16	W					50.0		
					Dark Gray Fine SAND (SP), Little Medium to Coarse Sand from 12 to 12.5 ft, Organic Odor Present				
6	18	W	14	- - 15-	Dark Gray Fine SAND (SP), Trace Silt, Organic Odor Present		328.0		
	1.1	<u> </u>	W		LEVEL OBSERVATIONS GE	NERAL	NOT	ES	
Ti De De	hile Dome After the pth to The strangition	ter Dr Wate Cave	illing r in	represen	t. Upon Completion of Drilling Tt. Start 1/17/	96 End F Chief P Editor 2 1/4" I.	1/17/9 GH PMS D. HSA	Rig CME 55	



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon Griffith, Indiana Location

Boring No. **SB103** Job No. 4077.0075

Sheet 2 of 2

Surface Elevation 637.8

Northing: 6855.1 5287.1

		Ū	V		21	Location Griffith, Indiana OO Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-50	Northin Easting		55.1 57.1
			PLE	r——		VISUAL CLASSIFICATION	SOI		PERTIES
) .	Rec. (in.)	Mois- ture	N Value	Depth (ft.)	60	and Remarks	qu (qa) (tsf)	(ppm)	Remarks
,	20	W		-		Gray Fine SAND (SP), Little Silt, Clay Lens from 17.5 to 17.6 ft, Organic Odor Present		821.0	Clay zone 17.5-17.6 1
	18	W/M		- - - - - -		Gray Brown Fine SAND (SP), Little to Some, Medium to Coarse Sand, Strong Organic Odor Present, Brown Oily Substance Present Gray SILT (ML), Trace to Little Fine Sand and		592.0	Field analys for VOCs a PCBs Hydrophob
	20	М		- 20- - -		Clay at 19.5 ft Gray, Silty CLAY (CL)	4.0	1051.0	dye test posit
						T. I. C.D			
				- - - 25-		End of Boring at 23.0 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.			
				_					
				-					
				- 30 					
· · · · · · · · · · · · · · · · · · ·				-					



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No.

SB104 4077.0075

Job No. Sheet

1 of 2

Northing:

Surface Elevation 637.8 6838.3

Easting:

5304.1

#4077\Gint\40770_ID; CHICAGO

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION PID Rec. Mois-Depth and Remarks (qs) ture Value (in.) (ft.) (ppm) Remarks Gravel and Slag (FILL) Black Stained Fine SAND (SP), Some Gravel 52.0 1 10 W 4 Poor recovery, and Wood, Petroleum Odor Present petroleum odor 2 8 9 24.0 Poor recovery, sheen and Dark Gray, Fine SAND and GRAVEL (GP), Pieces of Wood from 5 to 5.5 ft, Sheen and petroleum odor Petroleum Odor Present 0.0 No recovery 1270.0 Poor recovery 4 2 6 Black Stained Fine SAND (SP), Little Fine Gravel, Roots, Small Pieces of Wood, Petroleum-Like Odor Present 10 Black and Gray Stained, Fine to Coarse SAND 10 5 18 48.0 (SP), Organic Odor Present Black Stained Fine SAND (SP), Trace Shell Fragments and Fine Gravel (Chert) to 14 ft, 12 103.0 6 16 Grades into Gray Brown Fine Sand, Organic Odor Present WATER LEVEL OBSERVATIONS **GENERAL NOTES** While Drilling ft. Upon Completion of Drilling ft. Start 1/18/96 End 1/18/96 Driller E&F Chief Time After Drilling Rig CME 55 GH Logger DAP Editor Depth to Water **PMS** Depth to Cave in Drill Method 2 1/4" I.D. HSA

The stratification lines represent the approximate boundary between soil types and the transition may be gradual.



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon Location

Griffith, Indiana

Boring No. Job No.

SB104 4077,0075

637.8

Sheet

2 of 2

Surface Elevation

Northing: 6838.3 5304.1

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SOIL PROPERTIES SAMPLE VISUAL CLASSIFICATION Rec. Mois-PID Depth and Remarks (qa) (tsf) (in.) ture (ft.) (ppm) Remarks Value Gray Brown, Fine SAND (SP), Little Silt, $\overline{\mathbf{w}}$ 193.0 16 Trace Fine Gravel, Organic Odor Present 772.0 8 18 W/M Field analysis for VOCs and Gray Brown Fine SAND (SP), Little Medium to **PCBs** Coarse Sand 4.0 20 Very Stiff, Gray, Silty CLAY (CL), Trace Fine >4.0 to Coarse Sand and Fine Gravel 1050.0 20 W 12 Gray Clayey SILT (ML), Trace to Little Fine Sand End of Boring at 22.5 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel. 25 30-



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No. Job No.

SB105 4077.0075

Sheet

1 of 2

Surface Elevation

637.8

Northing: 6817.9 5321.3

		W	ν		1 21	OO Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-500	Easting:	532	21.3
	S	ΑM	PLE			VISUAL CLASSIFICATION	1	PRO	PERTIES
No.	Rec.	Mois- ture	N Value	Depth (ft.)		and Remarks	qu (qa) (tsf)	PiD (ppm)	Remarks
				_		Gravel and Gray Slag (FILL)			
1	10	W	5	-		Black Stained GRAVEL (GP), Black Stained Fine Sand, Organic Odor Present		115.0	Poor recovery
2			4					0.0	No recovery
3	18	w	5	5- - 		Dark Olive Brown, Fine SAND (SP), Trace Silt		1249.0	
,	10	W	3	-		and Organics, Sheen Present at 6.5 ft, Organic Petroleum Odor Present		1249.0	
4	18	w	6	- - - 10-		Petroleum Staining Present Very Strong Pink, Purple, Green Sheen		2259.0	Field analysis for VOCs and PCBs
5	18	w	10					284.0	
				-					
6		W	9			Dark Gray Brown, Fine SAND (SP), Organic Petroleum Odor Present		404.0	
		i	W	ATE	RL	EVEL OBSERVATIONS GE	NERAL	. NOT	ES
Tin De De	nile Dr ne Aft pth to pth to	er Dri Watei Cave	in			Driller E & Logger DA Drill Method		PMS	6 Rig CME 55
1	ransition	may b	n tines oc gradi	represen ual	i ine	approximate houndary between soil types and the		/\407.7\Ginti407	770 ID. CHICAGO



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon Griffith, Indiana Location

Boring No. **SB105** Job No. 4077.0075 Sheet 2 of 2 Surface Elevation 637.8 6817.9

Northing: 5321.3

		W	V ——		Location Griffith, Indiana 100 Corporate Drive, Addison, Illinois 60101, TEL. (7)	Northing: Easting: 08) 691-5000	532	7.9 1.3
	SA	MI	PLE		VISUAL CLASSIFICATION	SOIL	PRO	PERTIES
UA LEI	ec. M		N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
7 2	0 1	w	13	-	Brown, Stained Fine SAND (SP), Trace Silt Clay, Petroleum Sheen and Odor Present	t and	659.0	Strong shee
3 2	0 W	//M	8	-	Brown, Fine to Coarse SAND (SP), Trace S and Clay, Organic Odor Present	4.0	1269.0	Field analys for VOCs ar PCBS
9 1	8 1	M	9	20- - 	Very Stiff, Silty Gray CLAY (CL) Gray Brown, Silty CLAY (CL), Trace Fine Coarse Sand	to <4.0	109.0	
					End of Boring at 22.5 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.			
				25-				
				-				
				- 30-				



transition may be gradual.

LOG OF TEST BORING

Project American Chemical Service, Inc.
Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No. SB106
Job No. 4077.0075

Sheet 1 of 2
Surface Elevation 637.8

Northing: **6802.1**Easting: **5339.3**

______J:4027:Gint:40270_IC. CHICAGU

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION Nc. Rec. Mois-Depth PID and Remarks (ap) ture Value (ft.) (ppm) Remarks (tsf) Gravel and Gray Slag (FILL) Black Stained, Brown Clay FILL, Some Gravel, 12 4.0 M 6 1 Over Black Stained Brown Fine Sand and Silt, Petroleum Odor Present 2 12 M/W 6 Black Stained Brown, Fine SAND (SP), Some 497.0 Petroleum Silt, Trace Clay, Petroleum Odor and Sheen sheen Present 5 Dark Gray Stained Fine SAND (SP), Little Silt, 298.0 10 $\overline{\mathbf{w}}$ 6 Petroleum Odor Present Black Stained Fine SAND (SP), Grades into Olive Brown Stained, Fine Sand, Little Silt, 1012.0 4 Field analysis 16 3 Organic Odor Present for VOCs and **PCBs** 10 Dark Brown, Fine SAND (SP), Grades into 275.0 5 18 Petroleum Fine to Coarse Sand at 11.5 to 12.5 ft, sheen at 12.0 ft Petroleum Sheen at 12.0 ft, Grades Back into Brown Fine Sand at 12.5 ft, Petroleum Odor Present Dark Brown to Black Stained, Fine SAND (SP), 120.0 6 12 W Thin Fine to Coarse Sand Seam at 15.0 ft 15-WATER LEVEL OBSERVATIONS **GENERAL NOTES** ft. | Start ft. Upon Completion of Drilling 1/18/96 End 1/18/96 While Drilling Driller E&F Chief Rig CME 55 Time After Drilling GH Logger DAP Editor PMS Depth to Water Drill Method 2 1/4" I.D. HSA Depth to Cave in The stratification lines represent the approximate boundary between soil types and the



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No.

SB106

Job No. Sheet

4077.0075 2 of 2

Surface Elevation

637.8 6802.1

Northing:

	Location Griffith, Indiana	Northing: Easting:	5339 5339	
SAMPLE	2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 VISUAL CLASSIFICATION	1	PERTIES	
No. Rec. Mois- N Depth ture Value (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
7 16 W	Clay Lens from 15.2 to 15.4 ft Brown Stained Fine SAND (SP) at 15.4 ft, Organic Odor Present Brown Fine SAND (SP), Little Silt, Organic Odor Present		154.0	
8 18 M/W	Gray Brown Fine SAND (SP), Little Silt to 20.2 ft, Organic Odor Present Very Stiff, Gray Silty CLAY (CL), Trace Fine	4.0	1833.0	Field analysis for VOCs and PCBs
9 12 M	to Coarse Sand Hard, Gray Brown, Silty CLAY (CL), Trace Fine to Coarse Sand	>4.5	199.0	
	End of Boring at 22.0 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.	.,		



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No.

SB107 4077.0075

Job No. Sheet

1 of 2

Surface Elevation 637.8

Northing:

6782.4 5356.8

	2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691	1.000		56.8
SAMPLE Rec. Mois- N	VISUAL CLASSIFICATION	L	OIL PRO	PERTIES
No. (in.) ture Value	epth and Remarks		sf) (ppm)	Remarks
	Gravel and Gray Slag (FILL)		517	
1 8 M/W 4	Gray Fine to Coarse SAND and GRAVEL (GP), Grades into Black Stained Fine Sand, Trace Silt at 1.8 ft, Organic Odor Present	-	- 13.0	
2 3	No Recovery	_	- 0.0	
3 20 W 4	Black Stained Fine SAND and GRAVEL (GP), Grades into Brown Fine Sand, Little Silt, Trace Organics (Roots), Organic Varnish Like Odor Present		- 2463.0	Field analysis for VOCs and PCBs
4	No Recovery, Piece of Slag in Spoon		0.0	
5 20 W 12	Gray Brown, Fine to Coarse SAND and Fine GRAVEL (GP), Grades Back into Gray Brown Fine SAND (SP), Organic Varnish Odor Present		1520.0	Field analysis for VOCs and PCBs
6 18 W 10	Gray Brown Fine to Coarse SAND (SP), Brown Oily Zone at 14 ft, Grades Back into Gray Brown Fine Sand at 14.3 ft, Slight Sheen Present		440.0	
W	TER LEVEL OBSERVATIONS	GENE	RAL NOT	ES
'Vhile Drilling 'ime After Drilling Depth to Water Depth to Cave in	Driller Logger	DAP E	End 1/18/9 Chief GH Editor PMS (4" I.D. HSA	Rig CME 55



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon Location

Griffith, Indiana

Boring No.

SB107 4077.0075

637.8

Job No. Sheet

2 of 2

Surface Elevation

Northing: 6782.4 5356.8

		Ū	D		21	Location Griffith, Indiana OO Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-500	Norming Easting:		56.8
			PLE			VISUAL CLASSIFICATION			PERTIES
No.	Rec.	Mois- ture	N Value	Depth (ft.)	1 × × ·	and Remarks	(qa) (tsf)	PID (ppm)	Remarks
						G D Ti to Go of GAND (OD) Street			
7	18	W	14	- - -		Gray Brown, Fine to Coarse SAND (SP), Small Brown Oily Zone at Interface of Fine to Coarse and Fine Sand, Grades into Gray Brown Fine Sand at 17 ft		1016.0	
8	20	W/M	12	-		Gray Brown, Fine to Coarse SAND (SP)	>4.5	210.0	Hydrophobic dye test positive
				_ 20		Gray Silty CLAY (CL)			
						End of Boring at 20.5 ft			
				 -		Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.			
				-					
				_ - - 25					
				-					
				-					
				- 30-					
				_					1
!					!		ſ	1	·



LOG OF TEST BORING

Project American Chemical Service, Inc.
Still Bottoms/Treatment Lagoon

Location Griffith, Indiana Northing
Easting:
2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000

Boring No. SB108
Job No. 4077.0075

Job No. 40/7.007 Sheet 1 of 2

Surface Elevation 637.6

J'A077:Gint:40770 IC. CHICAGO =

Northing: 6764.6 Easting: 5372.8

SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION PID Rec. Mois-N Depth and Remarks (qa) No. (in.) ture Value (ft.) (ppm) Remarks (tsf) Gravel and Gray Slag (FILL) Black Stained. Fine to Coarse SAND and 1 12 W 13 75.0 GRAVEL (GP), Grades into Black Stained Fine Sand, Organic Odor Present Black Stained, Fine to Coarse SAND and 2 12 $\widetilde{\mathbf{w}}$ 13 9922.0 Field analysis GRAVEL (GP) Over Brown Black Clay, Silt, for VOCs and Gravel and a Large Piece of Wood **PCBs** Black Stained Fine SAND (SP), Silt, Pieces of 9743.0 3 8 W 17 Wood, Grades into Brown Fine Sand, Pieces of Wood, Solvent Odor Present Gray Stained Fine SAND (SP), Some Pieces of 4 12 W 2159.0 15 Wood, Some Brown and Black Staining, Organic Solvent Odor Present Gray/Black Stained Fine SAND (SP) to 5 16 W 12 3868.0 Field analysis approximately 10.2 ft, Gray Stained Fine to ofr VOCs and Coarse Sand, Fine Gravel and Brown Oily **PCBs** 10-Sheen at 10.8 ft Gray Brown Stained, Fine SAND (SP), Grades Field analysis 18 W 18 5716.0 6 into Fine to Coarse Sand from 11.5 to 12.5 ft, for VOCs Black Stained Fine Sand at 12.8 ft, Solvent Odor and Sheen Present Gray Brown Fine SAND (SP), Little Silt, 7 159.0 22 W 12 Organic Odor Present WATER LEVEL OBSERVATIONS **GENERAL NOTES** ft. Upon Completion of Drilling Ψ ft. Start 1/19/96 End 'Vhile Drilling 1/19/96 Driller E&F Chief rime After Drilling GH Rig CME 55 Depth to Water Logger DAP Editor **PMS** Drill Method 4 1/4" I.D. HSA Depth to Cave in

The stratification lines represent the approximate boundary between soil types and the

transition may be gradual



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana Boring No.

SB108 4077.0075

Job No. Sheet

2 of 2

Surface Elevation

637.6

Northing:

6764.6 5372.8

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SAMPLE SOIL PROPERTIES **VISUAL CLASSIFICATION** Rec. Mois-Depth PID and Remarks No. (ap) (in.) ture Value (ft.) (ppm) Remarks (tsf) Brown Fine SAND (SP), Trace Silt, Musty 18 $\overline{\mathbf{w}}$ 10 189.0 Organic Odor SILT (ML) 20 W/M 11 Brown Fine to Coarse SAND (SP) from 17.5 to 9 2876.0 18.6 ft, Musty Odor Present >4.0 Very Stiff, Gray CLAY (CL), Pushed Shelby Tube 18 in. Then Encountered 10 6" sand blow-in M Refusal on Stiff Clay in shelby tube End of Boring at 20.5 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel. 25 30-



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No.

SB110 4077.0075

638.8

Job No. Sheet

1 of 2

Surface Elevation Northing: 6751.9

	S	ΑM	PLE		VISUAL CLASSIFICATION	so	OIL PRO	PERTIES
lo.	.	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa (tsf) /nnm)	Remarks
					Gravel and Gray Slag and Brown Fine Sand (FILL)			
1	18	М	16	 	Black Fine SAND and Fine to Coarse GRAVEL (GP), Grades into Brown Fine Sand from 2 to 2.5 ft, then into Brown, Fine to Coarse Sand, Solvent Odor Present		9592.0	PID over ran
2	22	М	14	 	Brown, Fine to Coarse SAND (SP), Little Fine to Coarse Gravel, Solvent Odor, Rust (Varnish-Like) Staining Present		3236.0	PID over ran
3	22	M/W	7	_ 5-	Brown, Fine to Coarse SAND (SP), Little Fine		3384.0	for PCBs PID over rang
				- -	Gravel, Solvent Odor and Gray Brown Staining at 6 ft			
	20	W	12		Gray Brown Fine SAND (SP), Trace Silt and Medium to Coarse Sand, Solvent Odor and Sheen Present		9592.0	Field analysis for VOCs
	20	W	10	 - 10-	Gray, Fine to Coarse SAND (SP), Trace Silt, Solvent Odor Present		8405.0	Over range PI
5	20	W	14	 	Gray Fine SAND (SP), Trace Silt and Coarse Sand, Musty Solvent Odor Present	<u></u>	6127.0	
7	18	w	7	- -	Gray, Fine to Coarse SAND (SP), Trace Silt and Shell Fragments, Grades Back into Gray Fine Sand at 14 ft, Musty Solvent Odor Present		5908.0	Over range PI
	1	<u> </u>	W	15- Δ TF I	LEVEL OBSERVATIONS G	SENER	AL NOT	FS
.'iı De	nile Dr ne Aft pth to pth to	er Dr Wate	☑ illing r		Upon Completion of Drillingft. Start 1/2 Driller E	22/96 En & F Ch DAP Ed		Rig CME



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon Location

Griffith, Indiana

Boring No.

SB110 4077.0075

638.8

Job No. Sheet

2 of 2

Surface Elevation

6751.9 Northing: 5660.5

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000

			PLE		VISUAL CLASSIFICATION	L		ERTIES
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
8	18	W	16	-	Gray, Fine to Coarse SAND (SP), Trace Silt, Musty Solvent Odor Present (SP)	-	2961.0	
9	18	W	11	-	Gray, Fine to Coarse SAND (SP), Trace Fine Gravel, Musty Solvent Odor Present		5424.0	
10	20	W	21	 - 20	Gray, Fine to Coarse SAND (SP), Trace Clay and Silt, Musty Solvent Odor Present		2019.0	Blow-in
11	20	w	12		Gray, Fine to Coarse SAND (SP), Trace Silt and Clay, Musty Odor			Blow-in
12	22	w			Gray, Clayey SILT/Silty CLAY (ML/CL) Gray Clayey SILT (ML)	2.5		
				25-	End of Boring at 24.0 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.			



Depth to Cave in

transition may be gradual

The stratification lines represent the approximate boundary between soil types and the

LOG OF TEST BORING

Project American Chemical Service, Inc.
Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No. SE Job No. 4077.

SB111 4077.0075

Sheet 1 of 2

Surface Elevation 638.4

Northing:

Drill Method 4 1/4" I.D. HSA

J\4077\Gmt\40770 ID: CHICAGO --

6688.6 5524.4

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-Depth and Remarks Nc. (ap) (in.) ture Value (ft.) (ppm) Remarks (tsf) Gravel and Grav Slag (FILL) Over Black Fine Sand, Silt 12 Brown Fine SAND (SP), Trace Fine Gravel, 1 20 M 9182.0 Field analysis Strong Solvent Odor Present for VOCs and **PCBs** Light Brown Fine SAND (SP), Solvent Odor 2 20 W 14 8618.0 Present Light Brown Fine SAND (SP), Trace to Little 5074.0 3 20 8 Fine to Coarse Sand from 6 to 7 ft. Strong Solvent Odor Present Grades into Olive Brown Stained, Fine to w 4 18 11 8107.0 Field analysis Coarse SAND (SP), Very Strong Solvent Odor for VOCs and from 8 to 9 ft **PCBs** 5 14 W 9 Olive Gray Brown, Fine to Coaix SAND and 6945.0 GRAVEL (GP), (Possible Fill) Strong Solvent Odor Present Black Stained, Fine to Coarse SAND and 6 16 W 12 1086.0 GRAVEL (GP) Gray Stained Fine SAND (SP), Trace Medium to Coarse Sand, Strong Solvent Odor 7 16 w 905.0 14 Gray, Fine to Coarse SAND (SP), Trace Fine Gravel, Solvent Odor Present, Grades into Gray, Fine Sand at 14 ft 15-WATER LEVEL OBSERVATIONS **GENERAL NOTES** ft. Upon Completion of Drilling \(\frac{1}{2}\) 1/22/96 End 1/22/96 While Drilling Start Time After Drilling Driller E & F Chief Rig CME 55 GH Depth to Water **PMS** Logger DAP Editor



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No. Job No.

SB111 4077.0075

Sheet

2 of 2 Surface Elevation 638.4

Northing:

6688.6 5524.4

-	S	ΑM	PLE		VISUAL CLASSIFICATION		SOIL	. PROP	ERTIES
о.	Rec.	Mois-	N Value	Depth (ft.)	and Remarks		qu (qa) (tsf)	PID (ppm)	Remarks
8	20	W	14	_	Gray Fine SAND (SP), Trace Medium to Coarse Sand, Solvent/Musty Odor Present		-	726.0	
•	16	W	10	-	Gray Brown Fine SAND (SP), Some Clay and Silt Lenses; Silt Lenses 17.5 to 18.5 ft			355.0	
0	20	w	20	 20	Gray, Silty CLAY to Clayey SILT (CL-ML)		>4.0		
				-	End of Boring at 21.0 ft				
				-	Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.				
				- 					
				— 25— -					
				30-					
			1	4 !		}			



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

SB112 Boring No. Job No. 4077.0075 1 of 2 Sheet

Surface Elevation 639.7 Northing: 6935.0

J/4077/Gint/40770 ID: CHICAGO

		W	D		1	Location Griffith, Indiana		-	Northing Easting:		35.U 75.9
	S	AM	PLE		21	OO Corporate Drive, Addison, Illinois 60101, TEL. (7		-5000		- PRO	PERTIES
No.	LU L	Mois-	N Value	Depth (ft.)		and Remarks	•		qu (qa) (tsf)	PID (ppm)	Remarks
				_		Gravel and Gray Slag, Some Sand (FILL)					
1	16	М	8	-		Gray Stained Fine SAND (SP), Grades into Dark Brown Stained, Fine Sand at 2 ft, Sligh Musty Solvent Odor Present				5748.0	
2				- - -		No Recovery - Drilling Feels Like Concrete Block/Large Gravel	:				Refusal at 1.0 fi
3	16	w		5- - -		Gray Stained, Fine to Coarse SAND (SP), Some to Coarse Gravel, Purple Staining from to 6.5 ft, Grades Back into Brown Fine Sand Strong Solvent Odor Present	5.5			5409.0	Field analysis for PCBs
4						No Recovery					No recovery, high PID readings in breathing zone
5	20	W	4	 - _ 10 _ -		Gray Stained Fine SAND (SP), Grades to Bla Stained, Fine to Coarse Sand and Fine Grave Brown-Stained, Oily, Petroleum Sheen, Fine Coarse Sand and Fine Gravel from 10 to 10.0 ft, Grades Back into Brown Fine Sand, Strong Salvant Odan	el; e to 6			8524.0	Sheen, field analysis for VOCs and PCBs
6	20	W	8	-		Solvent Odor Stained, Fine to Coarse SAND to 11.5 ft, Grades into Gray, Fine to Coarse Sand and F Gravel, Little Silt, Trace Clay, Strong Solver Odor				9564.0	Field analysis for VOCs
7	8	W	13	 15-		Brown, Fine to Coarse SAND (SP) to 13.5 ft Grades into Gray Fine Sand, Some Medium to Coarse Sand and Fine to Coarse Gravel, Trac Shells	to		_	5624.0	
	1	l	W	ATE	R L	EVEL OBSERVATIONS	. [GE	NERA	LNOT	ES
Γir De	nile Di ne Aft pth to pth to	er Dr Wate	<u>¥</u> illing r			Upon Completion of Drilling ft. St D Lo	riller ogger	1/22/9 E & DAI	96 End F Chief	1/22/9 GH r PMS	Rig CME 55

The stratification lines represent the approximate boundary between soil types and the transition may be gradual.



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No.

SB112 4077.0075

Job No. Sheet

2 of 2

Surface Elevation 639.7

Northing:

6935.0 5575.9

		<u>AM</u>	PLE			VISUAL CLASSIFICATION	L	- PROP	ERTIES
ło.	Rec.	ture	N Value	Depth (ft.)		and Remarks	qu (qa) (tsf)	PID (ppm)	Romarks
8	20	W	17			Gray-Brown Fine SAND (SP), Some Medium to Coarse Sand, Fine Gravel and Shell Fragments		4083.0	
9		W		-	Silt Lens at 18.2 to 18.5 ft, Some Clay	Silt Lens at 18.2 to 18.5 ft, Some Clay			
0	22	W/M		 20		Hard, Gray, Silty CLAY (CL/ML)	>4.5		
• 1		M		-					
				- - - -		End of Boring at 22.0 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.			
				25 - 					
				 -					
				30-					
,									



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No. Job No.

SB117 4077,0075

637.9

Sheet

1 of 2

J/4077/Gint/40770 ID, CHICAGO _____

Surface Elevation Northing:

6929.2

Easting: 5219.9

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION PID Rec. Mois-Ν Depth and Remarks (qa) ture Value (in.) (ft.) (ppm) Remarks (tsf) Gravel and Gray Slag (FILL) 1 10 M 8 Brown Fine SAND (SP), Black-Stained Wood 3.0 Refusal, wood Chips in Tip of Spoon; Split-Spoon Refusal railroad tie 2 Black Stained Fine SAND (SP), Trace Silt and 16 M/W 11.0 Field analysis Organics (Roots), Creosote Solvent Like Odor for PCBs 5 Olive Gray Brown, Fine SAND (SP), Trace 3 16 5 13.0 Medium to Coarse Sand, Musty Solvent Odor Present Olive Gray Brown, Fine to Coarse SAND (SP), 17.0 4 W 16 6 Trace Medium to Coarse Sand, Musty Odor Present 10 Dark Olive Gray Brown Fine SAND (SP), 9.0 5 16 Grades into Dark Gray, Fine to Coarse at 12 to 13 ft, Musty Odor Present Gray, Fine to Coarse SAND (SP), Little Fine Gravel, Musty Odor 18 W 11 14.0 6 WATER LEVEL OBSERVATIONS **GENERAL NOTES** ft. Upon Completion of Drilling While Drilling ft. Start 1/24/96 End 1/24/96 Time After Drilling Driller E&F Chief GH Rig CME 55 Logger DAP Editor PMS Depth to Water Drill Method 2 1/4" I.D. HSA Depth to Cave in The stratification lines represent the approximate boundary between soil types and the transition may be gradual.



LOG OF TEST BORING

Project American Chemical Service, Inc.

Still Bottoms/Treatment Lagoon Griffith, Indiana Location

Boring No.

SB117

Job No. Sheet

4077.0075 2 of 2

Surface Elevation

637.9

Northing: Easting:

6929.2 5219.9

\geq					21	00 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-500	Easung:	521						
<u> </u>			PLE	, <u>.</u>		VISUAL CLASSIFICATION	SOIL PROPERTIES							
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)		and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks					
7	18	w		-		Gray Brown, Fine SAND (SP), Little to Some, Medium to Coarse Sand, Musty Odor Present	-	238.0	Field analysis for VOCs					
8	22	W/M		- - - 20-		~ ~ 20~	- - - - 20-		- - - - 20-		Hard, Gray Silty CLAY (CL-ML) SILT Lens (ML) 19.2 to 19.6 ft	>4.5 1.0 >4.0		
				25-		End of Boring at 20.5 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.								



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana Boring No.

SB118 4077.0075

Job No. Sheet

1 of 2

Surface Elevation 639.1

Northing: Easting:

		W	<i></i>		2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5	Easting: -	562	20.5
	S	AM	PLE		VISUAL CLASSIFICATION	SOIL	PRO	PERTIES
No.	AI .	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
				_	Brown SAND and GRAVEL (FILL)			
1	14	М	6		Orange Brown Stained, Fine to Coarse SAND (SP), Grades into Brown Fine Sand at 2 ft, Some Black Staining to 2.5 ft, Strong Solvent Odor Present		4012.0	
2	14	M	6	- - - - 5-	Brown, Fine to Coarse SAND (SP), Some Gray Olive Gray Staining from 4 to 4.8 ft, Strong Solvent Odor Present		4965.0	Field analysis for VOCs
	14	M/W	4	- - -	Brown, Fine to Coarse SAND and Fine GRAVEL (GP), Trace Silt, Some Brown Oily Staining from 7.5 to 7.7 ft, Strong Solvent Odor Present		5629.0	Field analysis for VOCs and PCBs
4	4	W	2				5753.0	Poor recovery
				- - 10-	Loose, Brown, Fine to Coarse SAND and GRAVEL (GP), Strong Solvent Odor, Sheen Present			
				_	Grey Fine to Coopee SAND and Fine			
5	14	W	6	- 	Gray, Fine to Coarse SAND and Fine GRAVEL (GP), Black Stained from 12 to 12.2 ft, Strong Solvent Odor, Slight Sheen	-	2297.0	Field analysis for PCBs
				_				
6	16	W	12	-	Grades into Gray Brown, Fine SAND (SP) at	-	891.0	
	<u></u>		\A!	- 15-		CAICDAI	NOT	EC.
				ATEF		ENERAL		
Tin De _l De _l	ile Dr ne Aft oth to oth to	er Dri Watei Cave	r in		Driller E Logger D Drill Metho	24/96 End & F Chief DAP Editor od 2 1/4" I.	1/24/9 GH PMS D. HSA	6 Rig CME 55
T	he strat	ificatio	n lines oc gradi	represent	e approximate boundary between soil types and the		4077.Gint\40	770 ID: CHICAGO



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No.

SB118 4077.0075

Job No. Sheet

2 of 2

Surface Elevation 639.1

Northing:

6721.5 5620.5

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000

	S	ΑM	PLE		VISUAL CLASSIFICATION	SOII	L PROP	ERTIES
No.	Rec.	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
				_	14.5 ft, Musty Solvent Odor Present			
7	16	w	12	-	Grades into Gray Fine SAND (SP), Trace Medium to Coarse Sand at 16.5 ft, Musty Solvent Odor Present		382.0	
$\overline{}$					Gray, Fine to Coarse SAND (SP), Trace to			
8	16	W	11	 	Little Fine Gravel, Musty Solvent Odor Present		340.0	·
				20-				
				_				
1	20	W	12				230.0	
				-			604.0	
10	20	W	11		Gray, Fine to Coarse SAND and Fine GRAVEL (SP), Little Silt, Trace Clay		624.0	
				— 25 —	Gray, Clayey SILT to Silty CLAY (CL-ML)			
11	22	W	12			1.5 2.5 2.5 1.0		
					End of Boring at 27.5 ft			
					Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.			
				30-				
	i			-				
		ļ 1	:					



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No. Job No.

SB119

Sheet

4077.0075 1 of 2

Surface Elevation

638.8

Northing:

6708.8 5567.4

		W	<i>y</i>		100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-500	Easting:	556	7.4
	S	AM	PLE		VISUAL CLASSIFICATION	1	. PROI	PERTIES
No.	Rec.	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
				_	Brown and Gray Slag and Sand and Gravel (FILL)			
1	16	М	9	-	Light Brown, Fine SAND (SP), Little Medium to Coarse Sand, Solvent Odor Present		2682.0	
				;				
2	16	M	6				3294.0	Field analysis for VOCs
		-		- 5- -	Grades into Gray Brown Fine SAND (SP) at 5 ft			
	12	M/W	6	_	Grades into Brown, Fine to Coarse SAND (SP),		3219.0	Field analysis for VOCs and PCBs
-				-	Solvent Odor at 7 ft, Oil Stained			
4	8	W	9	· ·			705.0	Sheen on spoon
				- 10-	Grades into Gray Stained, Fine to Coarse Sand and Gravel, Solvent Odor Present (FILL)	,		
5	10	W	7	_	Brown Stained, Fine to Coarse SAND and		570.0	Sheen on
					GRAVEL (GP), Black Staining from 12 to 13 ft, Solvent Odor Present			spoon, field analysis for PCBs
6	18	W		-				
U	10	W			Brown, Fine to Coarse SAND (SP), Little Fine Gravel, Grades into Brown, Fine Sand at 14.5			
	Π	<u> </u>	W	ATE	LEVEL OBSERVATIONS G	ENERAL	NOT	ES
Γi De De	hile Dime Afepth to	ter Dr Wate Cave	rilling r in		Driller E & Logger D. Drill Method	5/96 End & F Chief AP Editor 1 2 1/4" I.	r PMS	Rig CME 55
	The stra transitio	tification n_may_	on tines	s represer lual	ne approximate boundary between soil types and the		J:4027\ <u>Gint\40</u>	770 ID: CHICAGO



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No. Job No.

SB119 4077.0075

Sheet

2 of 2

Surface Elevation Northing:

638.8

6708.8 5567.4

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000

	S	ΑM	PLE		VISUAL CLASSIFICATION		L PROP	ERTIES
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
7	16	w	10		ft, Solvent Odor Present Gray Brown, Fine to Coarse SAND (SP), Trace Fine Gravel, Musty Solvent Odor, Trace Shells		610.0	
8	16	W	10	- - - - 20-			678.0	
	22	w	22		Gray Brown, Fine to Coarse SAND, Little Fine Gravel, Musty Solvent Odor, Trace Shells (SP) Stiff, Gray Silty CLAY (CL-ML)	1.75 2.5	315.0	
10	10	М	13		Gray Clayey SILT to Silty CLAY (CL-ML) End of Boring at 24.5 ft Borehole Backfilled with Bentonite Cement			
				30-	Grout. Topped with 6 inches of Gravel.			



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana Boring No.

SB120

Job No.

4077.0075

Sheet 1 of 2 Surface Elevation

637.7

Northing: Easting:

6742.0 5280.7

\geq					2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-500	Casung:		80.7	
	SAMPLE				VISUAL CLASSIFICATION		SOIL PROPERTIES		
No.		Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks	
					Gravel and Gray Slag (FILL)	,,,,,,			
1	14	М	10		Dark Brown to Black Stained, Fine SAND (SP), Trace Organics, Roots, Fine Gravel, Pieces of Wood, Sweet Musty Odor Present		105.0		
2	16	М	6	 - - - 5	Black, Fine SAND (SP), Trace Silt and Organics, Roots, Grades into Brown to Olive Brown Fine Sand, Shell Pieces Present, Sweet Musty Odor Present		332.0	Field analysis for PCBs	
7	16	W	7		Olive Gray Brown Fine SAND (SP), Trace Medium to Coarse Sand, Little Black Staining, Musty Odor Present		98.0		
4	14	w	3	 - - - - 10-	Olive Gray to Gray Fine SAND (SP), Trace Medium to Coarse Sand, Silt and Clay Lenses from 9.5 to 10.5 ft (<1" Thick), Musty Odor Present		291.0		
5	16	w	9	-	Gray Stained, Fine to Coarse SAND (SP), Some Sheen and Brown Staining from 12 to 12.5 ft, Grades into Gray Brown Fine Sand, Musty Solvent Odor Present		1243.0	Field analysis for VOCs and PCBs	
6	14	w	10		Gray, Fine to Coarse SAND (SP), Grades into Brown, Fine Sand, Silt Lens from 15 to 15.5 ft, Musty Odor Present		188.0		
	1	<u> </u>	W	ATE	LEVEL OBSERVATIONS GE	NERAL	. NOT	ΓES	
Tim Der Der	ne Aftoth to the to		<u>∑</u> illing r in	represen	. Upon Completion of Drilling ft. Start 1/25	6/96 End 2 F Chief 3 P Editor 2 1/4" I.	1/25/9 GH PMS D. HSA	Rig CME 55	



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No.

SB120

Job No. Sheet

4077.0075 2 of 2

Surface Elevation 637.7

Northing:

6742.0

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 5280.7 **SAMPLE** SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-PID Depth and Remarks No. (qa) (in.) ture Value (ft.) (ppm) Remarks Brown Fine SAND (SP), Trace Fine to Coarse 7 W 9 18 241.0 Sand, Slight Musty Odor Present Brown, Fine to Coarse SAND (SP), Trace Fine 404.0 20 W/M 15 Gravel, Musty Odor Present 16.0 20-Hard, Gray Brown, Silty CLAY (CL-ML), >4.5 Trace Fine to Coarse Sand 4.25 9 M Very Stiff, Gray, Silty CLAY (CL-ML), Trace 16.0 to Little, Fine to Coarse Sand 4.0 End of Boring at 22.5 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel. 25-30-



Depth to Cave in

transition may be gradual.

The stratification lines represent the approximate boundary between soil types and the

LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No.

SB121

Job No. Sheet 4077.0075 1 of 2

Surface Elevation

638.1

Northing: Easting:

Drill Method 2 1/4" I.D. HSA

J:4077/Gint/40770 ID. CHICAGO

6673.0 5476.0

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 **SAMPLE** SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-Ν PID Depth and Remarks (qa) No. (in.) ture Value (ft.) (mgg) Remarks (tsf) Black Stained Fine SAND (SP), Some Silt, 1 14 6 419.0 M Trace Organics, Roots, Grades into Brown Fine Sand (SP) Brown Fine SAND (SP), Trace Medium to 2 18 M/W 1467.0 Coarse Sand, Solvent Odor Present 5 Olive Brown/Gray Color Noted from 5 to 5.5 ft Brown Fine SAND (SP), Trace Medium to w 3 12 8 1684.0 Field analysis Coarse Sand, Solvent Odor Present for VOCs and **PCBs** Gray Brown Stained Fine SAND (SP), Grades 804.0 Field analysis w 8 4 14 into Brown Fine to Coarse Sand and Gravel for PCBs from 9.5 to 10 ft, then into Dark Gray Stained. Fine to Coarse Sand and Gravel, Solvent Odor 10-Present Olive Gray/Brown, Fine to Coarse SAND (SP), 2367.0 Field analysis W 5 18 6 Trace to Little Fine Gravel, Solvent Odor for VOCs Present Gray Brown Fine SAND (SP), Little Medium to 1413.0 20 8 6 Coarse Sand, Trace Fine Gravel, Musty Solvent Odor Present (SP) Silt Lens from 13 to 13.2 ft 15-**GENERAL NOTES** WATER LEVEL OBSERVATIONS ft. Upon Completion of Drilling ft. Start 1/25/96 End 1/25/96 **Vhile Drilling** Driller E&F Chief GH Rig CME 55 rime After Drilling Logger DAP Editor **PMS** Depth to Water



LOG OF TEST BORING

Project American Chemical Service, Inc.

Still Bottoms/Treatment Lagoon

Location Griffith, Indiana Boring No.

SB121

Job No. Sheet

4077.0075 2 of 2

Surface Elevation

638.1

Northing:

6673.0 5476.0

>					21	00 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-500	T	5476		
		AM Mois-	PLE	Depth		VISUAL CLASSIFICATION	SOIL PROPERTIES			
0.	(in.)		N Value	(ft.)		and Remarks	(qa) (tsf)	(ppm)	Remarks	
7	16	W	8	-		Brown Fine SAND (SP), Musty Solvent Odor Present Silt Lens from 17 to 17.1 ft		1319.0		
	16	w	12	 20		Brown Fine SAND (SP), Musty Solvent Odor Present Silty CLAY (CL/ML) Lens from 19.5 to 19.8 ft		1201.0		
0	18	W/M		-		Stiff, Gray, Clayey SILT to Silty CLAY (CL-ML), Little Fine to Coarse Sand and Fine Gravel	2.5 2.75	2352.0		
				- 25- -		End of Boring at 24.0 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.				
				30-						



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No.

SB122 4077.0075

Job No. Sheet

1 of 2

Surface Elevation

638.1

Northing: Easting:

6971.7 5248.3

J'4077:Gint/40770 ID; CHICAGO

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000

	S	AM	PLE		VISUAL CLASSIFICATION	SOIL	SOIL PROPERTIES			
No.	A.I	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks		
1	14	М	8	_	Light Brown Fine SAND (SP), Some Gravel Light Brown Fine SAND (SP), Grades to Dark Gray to Black Fine Sand, Trace Fine Gravel, Slight Solvent Odor Present		1600.0	Field analysis for VOCs		
2	20	w	4	- 5-	Dark Gray Stained Fine SAND (SP), Some Silt, Trace Medium to Coarse Sand, Trace Organics, Roots, Trace Fine to Coarse Gravel, Slight Musty Odor, Small Pieces of Wood		99.0			
?	16	W	3		Dark Brown to Black Stained Fine SAND (SP), Trace Organics (Roots), Trace Fine Gravel, Little Silt, Musty Oily Odor Present		75.0	Field analysis for PCBs		
4	18	W	6		Gray Brown Fine SAND (SP), Musty Organic Odor Present		39.0			
5	22	W	7	— 10- - - -	Gray Fine SAND (SP), Little Silt, Musty Organic Odor Present					
6	6	W	7	_	Grades into Gray, Fine to Coarse SAND and GRAVEL (GP), Musty Odor Present			Poor recovery		
	1	L	W	ATE	LEVEL OBSERVATIONS G	ENERAL	NOT	ES		
Tir De	nile Dr ne Aft pth to pth to	er Dr Wate	illing r		Driller E Logger D	25/96 End & F Chief OAP Editor od 2 1/4" I.	PMS	Rig CME 55		

The stratification lines represent the approximate boundary between soil types and the

transition may be gradual.



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No.

SB122

Job No.

4077.0075

Sheet

2 of 2 Surface Elevation 638.1

Northing:

6971.7

Easting:

5248.3

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000

	S	ΑM	PLE		VISUAL CLASSIFICATION	£	PROP	ERTIES
lo.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
7	20	W	11	- - - -	Gray, Fine to Coarse SAND (SP), Some Fine Gravel, Little Silt, Musty Odor Present			
8	18	M	12	 20	Hard, Silty CLAY (CL-ML), Trace Fine to Coarse Sand and Gravel	>4.5		
)				25-	End of Boring at 20.5 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.			
				30-				



LOG OF TEST BORING

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No.

SB125

Job No. Sheet 4077.0075 1 of 2

Surface Elevation

638.4

Northing: Easting:

6855.0 5622.8

J/4022/Gint/40770 ID. CHICAGO

SOIL PROPERTIES SAMPLE VISUAL CLASSIFICATION -PID Rec. Mois-Depth and Remarks No. (qa) (ppm) (in.) ture Value (ft.) Remarks (tsf) Gravel and Gray Slag, Black Fine Sand (FILL) (Corugated Rubber Hose: Old Water Line) 1 10 M 6 Dark Gray to Black Stained Fine SAND (SP), 1207.0 Trace Fine to Coarse Gravel, Solvent Odor Olive Gray Brown to Brown, Fine to Coarse 2 2884.0 Field analysis 16 $\overline{\mathbf{w}}$ SAND (SP), Small Black Stained zone of Fine for VOCs Gravel from 5.0 to 5.2 ft, Solvent Odor Present 5-Gray Brown Stained Fine SAND (SP), Thin Field analysis 16 -W 3 2863.0 Black Stained Fine to Coarse Sand and Gravel, for VOCs and Oily Zone from 6.7 to 7.0 ft, Grades into Gray **PCBs** Stained, Fine to Coarse Sand and Gravel, Solvent Odor Present Black Stained, Fine to Coarse SAND and Fine 4 8 789.0 Poor recovery GRAVEL (SP), Musty Solvent Odor Present Field analysis for PCBs 10 Black Stained. Fine to Coarse SAND and Fine 527.0 5 12 $\overline{\mathbf{w}}$ GRAVEL (SP) to 12.2 ft, Grades into Brown Fine Sand, Musty Solvent Odor Present Gray-Brown, Fine to Coarse SAND (SP), 22 6 Grades into Gray Brown Fine Sand at 14.5 ft, Musty Propane Like Odor Present WATER LEVEL OBSERVATIONS **GENERAL NOTES** ft. Upon Completion of Drilling ft. Start -1/26/96 End 1/26/96 While Drilling Driller E&F Chief GH Rig CME 55 Time After Drilling Logger DAP Editor **PMS** Depth to Water Drill Method 2 1/4" I.D. HSA Depth to Cave in

The stratification lines represent the approximate boundary between soil types and the

transition may be gradual.



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana Boring No. Job No.

SB125 4077.0075

Sheet

2 of 2

Surface Elevation Northing:

638.4 6855.0

5622.8

	S	ΑM	PLE		VISUAL CLASSIFICATION		SOIL	PROP	ERTIES
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)	and Remarks		qu (qa) (tsf)	PID (ppm)	Remarks
7	20	w	7	-	Gray Brown Fine SAND (SP), Sweet Musty Odor Present		_		
8	18	W/M	10	- - - - 20-	Grades into Gray Clayey SILT (CL-ML) at 19.0 ft, Small Sand Lense (<1 in.) at 19.8 to 19.9 ft, then into Hard Gray Silty Clay, Trace Fine to Coarse Sand and Gravel		2.5 >4.5		
n	12	W/M	12	-	Stiff, Gray, Clayey SILT to Silty CLAY (CL-ML)		1.5 2.5		
				- 25- 	End of Boring at 23 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.				
				30-					



Depth to Cave in

transition may be gradual

The stratification lines represent the approximate boundary between soil types and the

LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No.
Job No.

SB128

Sheet

4077.0075

SHEEL

1 of 2

Northing: **6803.1**

Surface Elevation 638.9

Easting: 0.00 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000

Drill Method 2 1/4" I.D. HSA

J.4077\Gint\40770_ID_CHICAGO

5653.1

SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-N PID Depth and Remarks (qa) No. (in.) ture Value (ft.) (ppm) Remarks (tsf) Gravel and Gray Slag, Brown Fine Sand (FILL) 1 18 M 6 Dark Brown to Yellow Brown, Fine to Coarse 2267.0 SAND (SP), Fine Gravel, Solvent Odor Present Brown, Fine to Coarse SAND (SP), Little Fine 2 14 M 2914.0 to Coarse Gravel, Solvent Odor Present 5-Brown, Fine to Coarse SAND and Fine 16 3 2334.0 Sheen GRAVEL (SP), Brown Oil Stained Zone from Field analysis 7.0 to 7.5 ft, Solvent Varnish-Like Odor for VOCs and Present **PCBs** Black and Brown, Oily Stained, Fine to Coarse W 2213.0 Sheen 4 4 SAND and Fine GRAVEL (SP), Solvent Oily Odor Present Field analysis for VOCs and 10-PCBs. Black Stained. Fine to Coarse SAND and 1364.0 Poor Recovery 5 5 6 W GRAVEL (SP), Solvent Odor Present w 7 Grades into Brown Fine SAND (SP) at 14.0 ft, 187.0 16 6 Sweet, Musty, Propane-Like Odor Present 15-WATER LEVEL OBSERVATIONS **GENERAL NOTES** ft. Upon Completion of Drilling 某 ft. Start 1/30/96 End **Vhile Drilling** 1/30/96 Time After Drilling Driller E&F Chief GH Rig CME 55 **PMS** Depth to Water Logger DAP Editor



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No.

SB128

Job No. Sheet 4077.0075 2 of 2

Surface Elevation

638.9

Northing:

6803.1

Easting: 5653.1

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SOIL PROPERTIES **SAMPLE** VISUAL CLASSIFICATION PID Rec. Mois-Depth and Remarks (ap) (in.) ture Value (ft.) (ppm) Remarks (tsf) Trace Fine to Coarse Gravel, Thin Silt Seam 144.0 $\overline{\mathbf{w}}$ 11 16 from 17.5 to 17.7 ft Gray Brown Fine SAND (SP), Little Medium to 108.0 20 W/M 11 8 Coarse Sand 4.0 Hard, Gray Silty CLAY (CL-ML) 20 Gray Brown, Fine to Coarse SAND (SP), 101.0 20 W 12 Musty Odor Present 18 W/M 6 10 Stiff to Very Stiff, Gray, Silty CLAY (CL-ML) 2.5 25 > 4.5 12 11 M 11 Stiff to Hard, Gray Brown, Silty CLAY (CL-ML), Trace Fine to Coarse Sand and Gravel End of Boring at 27.0 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel. 30-



LOG OF TEST BORING

Project American Chemical Service, Inc.
Still Bottoms/Treatment Lagoon
Location Griffith, Indiana

Boring No. SB129
Job No. 4077.0075
Sheet 1 of 2
Surface Elevation 636.9

Northing: **6712.4** Easting: **5268.4**

	S	AM	PLE		VISUAL CLASSIFICATION	SOIL	- PRO	PERTIES
No.	A.I	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
					Gravel and Gray Slag (FILL)			
1	20	М	5	-	Black, Silty, Fine to Coarse SAND (SP), Trace Organics, Roots, Slight Musty Odor Present		13.0	
2	20	M/W	6	- - - - 5-	Dark Brown, Silty Fine SAND (SP), Trace Roots, Grades into Gray Fine Sand, Musty Odor Present		9.0	
,	20	w	8	-	Gray Fine SAND (SP), Some Black Staining, Scattered Musty Odor		13.0	Field analysis for PCBs
4	12	w	7	- - - - - 10-	Dark Gray, Fine to Coarse SAND (SP), Some Silt, Silt and Clay Zone from 9.5 to 10.0 ft, Musty Odor		24.0	
5	20	w	10	- -	Gray, Fine to Coarse SAND and GRAVEL (SP), Thin Brown Stained Zone (Sheen Also) from 12.0 to 12.2 ft, Grades into Gray Fine Sand at 12.2 ft, Solvent Odor Present		926.0	Field analysis for VOCs and PCBs
6	18	W	10	 15-	Gray Brown Fine SAND (SP), Little Medium to Coarse Sand, Gray Staining from 14 to 14.5 ft, then into Brown Fine Sand, Solvent Odor Present		155.0	
	1	<u> </u>	W		LEVEL OBSERVATIONS GE	NERA	L NOT	res
Tir De De	nile Dene Aforth to The stransition	ter Dr Wate Cave	illing r in on lines	represen	t. Upon Completion of Drilling ft. Start 1/30 Driller E & Logger DA Drill Method	P Edito	r PMS .D. HSA	Rig CME 55



LOG OF TEST BORING

Project American Chemical Service, Inc.
Still Bottoms/Treatment Lagoon
Location Griffith, Indiana

Surface E

Boring No.

SB129 4077.0075

Job No. 4077.00 Sheet 2 of 2

Surface Elevation 636.9

Northing: 6712.4 Easting: 5268.4

	S	AM	PLE			VISUAL CLASSIFICATION				ERTIES
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)	85.75	and Remarks	} {q	u a) ef)	PID (ppm)	Remarks
7	18	w	10	-		Brown Fine SAND (SP), Trace Medium to Coarse Sand and Fine to Coarse Gravel, Musty Odor Present		-	217.0	
8	22	W	12	- - - - 20-		Hard, Silty CLAY (CL-ML), Trace Fine to Coarse Sand and Fine Gravel	>4	4.5	110.0	
				25-	3333	End of Boring at 20.5 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.				
				30-	-					



LOG OF TEST BORING

Project American Chemical Service, Inc.
Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No.

SB128

Job No.

4077.0075

Sheet

1 of 2

Surface Elevation Northing: 6803

638.9

Easting:

6803.1 5653.1

_					21	00 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691	1-5000			
	S	ΑM	PLE	·		VISUAL CLASSIFICATION			PRO	PERTIES
No.	Rec.	Mois- ture	N Value	Depth (ft.)		and Remarks		qu (qa)	PID (ppm)	Remarks
				1		Gravel and Gray Slag, Brown Fine Sand (FILL)		(tsf)	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	Trong No.
				_						
1	18	M	6	_		Dark Brown to Yellow Brown, Fine to Coarse SAND (SP), Fine Gravel, Solvent Odor Present			2267.0	
						or in the drawer, bower oder resem				
				- -						
										
2	14	M	7	-		Brown, Fine to Coarse SAND (SP), Little Fine to Coarse Gravel, Solvent Odor Present			2914.0	
				_		w Coarse Graver, Solvent Odor Fresent				
				— 5-{						
				-						
2	16	w	3	-		Brown, Fine to Coarse SAND and Fine			2334.0	Sheen
				-		GRAVEL (SP), Brown Oil Stained Zone from 7.0 to 7.5 ft, Solvent Varnish-Like Odor				Field analysis
				_		Present				for VOCs and PCBs
				_						
4	14	w	4	-		Black and Brown, Oily Stained, Fine to Coarse	-		2213.0	Sheen
·		.,		_		SAND and Fine GRAVEL (SP), Solvent Oily Odor Present			2213.0	Shech
				-		Odol Heschi	·			Field analysis
				10 -						for VOCs and PCBs
		137		_		Black Stained, Fine to Coarse SAND and			1064.0	
5	6	W	5	-		GRAVEL (SP), Solvent Odor Present			1364.0	Poor Recovery
				_						
				-						
									-	
6	16	W	7			Grades into Brown Fine SAND (SP) at 14.0 ft, Sweet, Musty, Propane-Like Odor Present			187.0	
				-		sweet, Musty, Propance-Like Odor Present				
				— 15 <u>—</u>						
				ATE	7 L	EVEL OBSERVATIONS	GEN	IERAI	L NOT	ES
	nile Dr				ft.		1/30/96		1/30/9	1
De	me Aft pth to	Water	r			Driller Logger	DAP	Chief Edito	r PMS	3
De	pth to	Cave	in n lines	represen	t the	approximate boundary between soil types and the	ethod 2	2 1/4" I	.D. HSA	.]
1	ransitio	n may t	e gradi	uaf.					1/4077/Gint/40	1770 ID GUISTON



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No.
Job No.

SB128 4077,0075

638.9

Sheet

2 of 2

Surface Elevation

Northing: **6803.1**

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 5653.1 **SOIL PROPERTIES SAMPLE** VISUAL CLASSIFICATION Rec. Mois-PID Depth and Remarks (qa) (tsf) (in.) ture Value (ft.) (mag) Remarks Trace Fine to Coarse Gravel, Thin Silt Seam 144.0 7 16 W 11 from 17.5 to 17.7 ft Gray Brown Fine SAND (SP), Little Medium to 20 W/M 11 108.0 Coarse Sand 4.0 Hard, Gray Silty CLAY (CL-ML) Gray Brown, Fine to Coarse SAND (SP), 9 Ŵ 101.0 12 20 Musty Odor Present 10 18 W/M Stiff to Very Stiff, Gray, Silty CLAY (CL-ML) 2.5 25 >4.5 12 11 M 11 Stiff to Hard, Gray Brown, Silty CLAY (CL-ML), Trace Fine to Coarse Sand and Gravel End of Boring at 27.0 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel. 30-



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No. Job No.

SB129 4077.0075

636.9

Job No.
Sheet

1 of 2

Surface Elevation

Northing: 6

6712.4 5268.4

	S	ΑM	PLE		VISUAL CLASSIFICATION	SOIL	- PRO	PERTIES
No.	N.	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
					Gravel and Gray Slag (FILL)	((0))		
1	20	М	5		Black, Silty, Fine to Coarse SAND (SP), Trace Organics, Roots, Slight Musty Odor Present		13.0	
2	20	M/W	6	 5	Dark Brown, Silty Fine SAND (SP), Trace Roots, Grades into Gray Fine Sand, Musty Odor Present		9.0	
3	20	W	8	-	Gray Fine SAND (SP), Some Black Staining, Scattered Musty Odor		13.0	Field analysis for PCBs
4	12	w	7	- - - - 10-	Dark Gray, Fine to Coarse SAND (SP), Some Silt, Silt and Clay Zone from 9.5 to 10.0 ft, Musty Odor		24.0	
5	20	w	10		Gray, Fine to Coarse SAND and GRAVEL (SP), Thin Brown Stained Zone (Sheen Also) from 12.0 to 12.2 ft, Grades into Gray Fine Sand at 12.2 ft, Solvent Odor Present		926.0	Field analysis for VOCs and PCBs
6	18	w	10	- - - - 15-	Gray Brown Fine SAND (SP), Little Medium to Coarse Sand, Gray Staining from 14 to 14.5 ft, then into Brown Fine Sand, Solvent Odor Present		155.0	
			W	I	LEVEL OBSERVATIONS GE	NERAI	ר חח	res
Tin Del Del	ne Aft oth to oth to he stra	rilling er Dri Water Cave tification may b	illing in n lines	represent	t. Upon Completion of Drilling ft. Start 1/30/ Driller E & Logger DAI Drill Method	P Edito	r PMS D. HSA	Rig CME 55



LOG OF TEST BORING

Project American Chemical Service, Inc.

Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No.

SB129 4077.0075

Job No.
Sheet

2 of 2

Surface Elevation

636.9

Northing:

6712.4 5268 A

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 5268.4 SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION PID Rec. Mois-Depth and Remarks No. (qa) (ppm) Remarks (in.) ture Value (ft.) (tsf) Brown Fine SAND (SP), Trace Medium to 10 217.0 7 18 W Coarse Sand and Fine to Coarse Gravel, Musty **Odor Present** Hard, Silty CLAY (CL-ML), Trace Fine to >4.5 110.0 22 $\overline{\mathbf{w}}$ 12 Coarse Sand and Fine Gravel End of Boring at 20.5 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel. 25-30



Depth to Water

Depth to Cave in

transition may be gradual.

The stratification lines represent the approximate boundary between soil types and the

LOG OF TEST BORING

Project American Chemical Service, Inc.
Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No.

SB130

Job No. Sheet 4077.0075

Sheet 1 of 2 Surface Elevation

637.9

Northing: Easting:

6652.2 5448.6

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-Depth PID and Remarks (ap) ture Value No. (in.) (ft.) (ppm) Remarks (tsf) Gravel and Gray Slag (FILL) 1 18 5 Black Fine SAND (SP), Grades into Very Dark M 392.0 Brown Sandy Silt, Trace Organics, Epoxy-Like **Odor Present** 2 Light Brown Fine SAND (SP), Epoxy-Like 18 $\overline{\mathbf{M}}$ 4 335.0 Odor 5 Light Brown Fine SAND (SP), Sovlent-Like 18 $\overline{\mathbf{w}}$ 5 620.0 Field analysis Odor Present, Very Slight Sheen from 6.5 to for VOCs and 7.0 ft **PCBs** Gray, Fine to Coarse SAND and Fine 4 W 5 388.0 Field analysis 4 GRAVEL (SP), Musty Odor Present for PCBs 10-Olive Gray to Gray, Fine to Coarse SAND 22 $\overline{\mathbf{w}}$ 340.0 $\overline{11}$ 5 (SP), Trace Shell Fragments, Musty Odor Present Olive Gray Fine SAND (SP), Little Medium to 870.0 20 W 8 6 Coarse Sand and Fine to Coarse Gravel, Fine Sand at 15.0 to 15.5 ft, Musty Odor Present 15-WATER LEVEL OBSERVATIONS GENERAL NOTES ft. Upon Completion of Drilling While Drilling ft. Start 1/30/96 End 1/30/96 Time After Drilling Rig CME 55 Driller E&F Chief GH

Logger DAP

Editor

Drill Method 2 1/4" I.D. HSA

PMS

J\4077\Gint\40770_ID; CHICAGO



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No.

SB130 4077.0075

Job No. Sheet

2 of 2

Surface Elevation 637.9

Northing:

6652.2

5448.6

	S	AM	PLE		VISUAL CLASSIFICATION	L	. PRO	PERTIES
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
7	20	w	15	- - -	Gray Brown Fine SAND (SP), Trace Medium to Coarse Sand and Fine to Coarse Gravel, Musty Solvent Odor Present		1018.0	Field analysis for VOCs
8	20	W	12	- - - - 20-	Gray, Fine to Coarse SAND (SP), Musty Solvent Odor Present Stiff, Gray Clayey SILT to Silty CLAY			
9				-	(CL-ML)	-		
				25-	End of Boring at 22.0 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.			



LOG OF TEST BORING

Project American Chemical Service, Inc.
Still Bottoms/Treatment Lagoon
Location Griffith, Indiana

Boring No. SB132
Job No. 4077.0075
Sheet 1 of 2
Surface Elevation 637.0
Northing: 6756.4

5174.5

	S	ΑM	PLE		VISUAL CLASSIFICATION	SOIL	PRO	PERTIES
No.	4.1	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PiD (ppm)	Remarks
				_				
1	16	М	7	-	Brown Fine SAND (SP) Grades into Dark Brown to Black Fine Sand, Silt, Trace Organics, Sweet Musty Odor Present		28.0	
2	18	М	7		Dark Gray Brown to Gray Fine SAND (SP), Sweet Musty Odor		59.0	
2	16	w	6	5 —	Dark Gray Fine SAND (SP), Sweet Solvent-Like Odor Present		23.0	
4	14	w	6	- 10-	Dark Gray Fine SAND (SP), Grades into a Black Stained Zone from 9.5 to 10.0 ft, Grades into Gray, Fine to Coarse Sand and Fine Gravel at 10.2 ft		27.0	Field analysis for PCBs
5	16	W	10	-	Dark Gray, Fine to Coarse SAND and Fine GRAVEL (SP), Sweet Propane-Like Odor Present		103.0	Field analysis for VOCs
6	14	W	10	-	Gray, Fine to Coarse SAND and Fine GRAVEL (SP) to 14.5 ft, Grades into Gray Fine Sand, Silt Seam from 14.8 to 14.9 ft,		32.0	
			W		Musty Odor Present R LEVEL OBSERVATIONS GE	NERAL	. NOT	ES
rin De De	nile Dr ne Aft pth to pth to The stra ransitio	ter Dr Wate Cave	illing r in on lines	represent	t. Upon Completion of Drillingft. Start 1/31 Driller E & Logger DA Drill Method	P Editor	PMS	Rig CME 55



LOG OF TEST BORING

Project American Chemical Service, Inc.
Still Bottoms/Treatment Lagoon

Location Griffith, Indiana

Boring No. Job No.

SB132 4077.0075

Sheet

2 of 2

Surface Elevation

on 637.0

Northing:

6756.4

Easting: 5174.5

_					21	00 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5	000			
		SAM			VISUAL CLASSIFICATION			SOIL		PERTIES
No.	Red (in.	. Mois	N Value	Depth (ft.)		and Remarks		qu (qa) (tsf)	PID (ppm)	Remarks
7	18	W	10			Gray Brown Fine SAND (SP), Musty Odor Present, Little Medium to Caorse Sand from 16.5 to 17.5 ft			37.0	
8		W	15	 20		Hard, Gray Silty CLAY (CL-ML), Trace Fine to Coarse Sand and Gravel		4.5		
9				-						
				- - - - 25-		End of Boring at 21.5 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.				
				30-						



.ime After Drilling

transition may be gradual.

The stratification lines represent the approximate boundary between soil types and the

Depth to Water

Depth to Cave in

LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No. SB133 Job No. 4077.0075

Sheet 1 of 2

Surface Elevation 637.3 Northing: 6670.7

5352.5

Driller E&F Chief

Logger DAP Editor

Drill Method 2 1/4" I.D. HSA

Rig CME 55

GH

PMS

J/4077/Gint/40770 ID: CHICAGO

2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION qu Rec. Mois-N PID Depth and Remarks (qa) No. (in.) ture Value (ft.) (ppm) Remarks (tsf) Gravel and Gray Slag (FILL) Brown Fine SAND (SP), Grades into Dark 1 16 М 5 221.0 Brown to Black Stained Fine Sand from 1.5 to 2.5 ft, Then into Gray Brown Fine Sand, Solvent Odor Present, Trace Organics, Roots Gray Brown Fine SAND (SP), Solvent 12 424.0 Epoxy-Like Odor Present 5-Gray Brown Fine SAND (SP), Epoxy 181.0 Field analysis 16 6 Resin-Like Odor, Some Black Staining Present for PCBs Throughout, Thin Silt Seam from 7.0 to 7.2 ft Very Dark Brown to Black Stained Fine SAND 182.0 14 (SP), Grades into Dark Gray Stained Fine Sand, **Epoxy Odor Present** 10-Gray Brown Fine SAND (SP), Slight Sheen Field analysis W 306.0 18 11 Present from 11.0 to 11.5 ft, Epoxy-Like Odor for VOCs and Present **PCBs** Gray Brown Fine to Coarse SAND (SP), 13 742.0 W 6 16 Grades into Fine Sand at 14.5 ft, Sweet Musty **Odor Present** WATER LEVEL OBSERVATIONS **GENERAL NOTES** ft. Upon Completion of Drilling ft. Start 1/31/96 End 1/31/96 hile Drilling



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon Griffith, Indiana Location

SB133 Boring No. Job No. 4077.0075 2 of 2 Sheet

Surface Elevation 637.3

6670.7 Northing: 5352.5

					31	Location Griffith, Indiana OO Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-500	Northing Easting:	: 667 535	
	S	AM	PLE		21	VISUAL CLASSIFICATION		. PROI	PERTIES
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)		and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
7	14	W	12			Gray Brown Fine SAND (SP), Little Silt at 17.0 ft, Sweet Musty Odor Present		1146.0	Field analysis for VOCs
8	18	W/M	12	-		Gray Brown, Fine to Coarse SAND (SP), Sweet Musty Propane-Like Odor Present		604.0	
				20- -		Very Stiff, Gray Silty CLAY (CL-ML), Trace Fine to Coarse Sand and Fine Gravel	4.0		
9	16	M	16	~		Z III W COMADO CAMA MINA A INC CHATCA	4.0		
				25-	22322	End of Boring at 22.0 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.			
į								<u> </u>	



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No. Job No.

SB134

4077.0075 1 of 2

Sheet Surface Elevation

637.7

Northing:

6667.5 5402.1

		W	<i>y</i>		2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000	Easting: _	540	2.1
	S	AM	PLE		VISUAL CLASSIFICATION		PROF	PERTIES
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
				_	Gravel and Gray Slag (FILL)			
1	20	M	12	_	Light Brown Fine SAND (SP) to 2.0 ft, Grades into Black Silt and Fine Sand, Organic Matter, Roots, Leaves, Solvent Odor Present4		105.0	
2	20	М	8	_	Dark Olive Brown Fine SAND (SP), Some Pieces of Wood, Organic Matter, Roots, Leaves, Solvent Odor Present		123.0	
3	20	W	8	5- - 	Gray Stained, Fine SAND (SP), Grades into Black Stained Fine Sand, Then into Gray Brown Fine Sand, Solvent Odor Present		96.0	Field analysis for PCBs
4	20	W	7		Brown to Olive Gray Fine SAND (SP), Little Silt at 8.0 ft, Solvent Odor, Some Black Staining		92.0	
5	20	W	7	 - 10 -	Gray Fine SAND (SP), Little Black Staining, Sweet Musty Odor Present		237.0	
6	22	W	9		Grades into Fine to Coarse SAND and Fine GRAVEL (SP), Sweet Musty Odor Present		654.0	
7	20	W	10	- - - 15	Gray Brown Fine SAND (SP), Some Silt, Trace Clay, Sweet Musty Odor Present	-	985.0	
1 	1		W		LEVEL OBSERVATIONS GE	NERAL	NOT	ES
Fir De De	nile Dr ne Aft pth to pth to The strai	er Dr Wate: Cave	illing r in on lines	represen	Upon Completion of Drilling ft. Start 2/1/9 Driller E & Logger DAI Drill Method the approximate boundary between soil types and the	P Editor 4 1/4" I.	D. HSA	Rig CME 55



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon Griffith, Indiana Location

SB134 Boring No. Job No. 4077.0075 Sheet 2 of 2

Surface Elevation 637.7 6667.5

Northing: 5402.1

		Ū	D		ı	Location Griffith, Indiana	-	Northing: Easting:	540	7.5 2.1
	S	AM	PLE		21	00 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5 VISUAL CLASSIFICATION	3000		PRO	PERTIES
No.	Rec.	Mois-	N Value	Depth (ft.)		and Remarks		qu (qa) (tsf)	PID (ppm)	Remarks
8	20	W	12	-		Gray to Gray Brown, Fine to Medium SAND (SP), Trace Fine to Coarse Gravel, Musty Odor Present			1480.0	
9	20	W	7	 		Gray Brown, Fine to Coarse SAND (SP), Musty Solvent Odor Present			1819.0	
10	22	W/M	15	 20		Gray Brown, Fine to Coarse SAND (SP), Slight Sheen with Brown Oily Staining, Grades into Gray Silt to 20.0 ft, Fine to Coarse Sand, Clay and Silt to 20.5 (Positive Hydrophobic Dye Test)		4.5	1609.0	Solvent Odor Field Analysis for VOCs and PCBs
'1		М		-		Hard, Silty CLAY (CL-ML), Trace Fine to Coarse Sand and Gravel				
				- 25- - 25-		End of Boring at 23.0 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.				
				30 - 	-					



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No.

SB135

Job No. Sheet

4077.0075 1 of 2

Surface Elevation

637.1

Northing: 6737.0 5230.1

		W	V		21	00 Corporate Drive, Addison, Illinois 60101, TEL.	(708) 691	-5000	asting:	523	30.1
	S	AM	PLE			VISUAL CLASSIFICATIO			SOIL	PRO	PERTIES
No.	<u>u.</u> 1	Mois- ture	N Value	Depth (ft.)		and Remarks			qu (qa) (tsf)	PID (ppm)	Remarks
						Gravel and Gray Slag (FILL)					
1	20	М	6	_		Light Gray Brown Fine SAND (SP), Sweet Musty Odor Present	et			49.0	
2	20	M	6	-		Black Stained Fine SAND (SP), Trace Organics, Sweet Musty Odor Present				66.0	
3	22	w		- - 5- -		Black Stained Fine SAND (SP) from 6.0 to ft, Musty Solvent Odor Present	o 7.0	-		70.0	Field analysis for VOCs and PCBs
4	20	W	6	-		Black Stained to Gray Fine SAND (SP), M Solvent Odor Present	lusty			75.0	Field analysis for PCBs
5	18	W	12	- 10		Dark Gray, Fine to Coarse SAND and Fine GRAVEL (SP), Trace Shells, Musty Odor Present				288.0	Field analysis for VOCs
6	16	W	14			Gray Brown, Fine to Coarse SAND and Fi GRAVEL (SP), Sweet Musty Odor Presen Grades into Gray Brown Fine Sand at 12.2	ıt,		-	118.0	
7	16	W	8	- - - - -		Gray Brown, Fine to Coarse SAND and GRAVEL (SP), Grades into Gray Brown F Sand, Little Clay at 14.2 to 14.5 ft	Fine			170.0	
			\	15-	1	EVEL OBSERVATIONS		CEN	ICDAL	NOT	
ļ						EVEL OBSERVATIONS			IERAL		
rii De De	hile Dr me Aft pth to pth to	er Dr Wate Cave	illing r in					E & F DAP	Editor	PMS	Rig CME 55
1	transitio	n may	he grad	ual.		, , , , , , , , , , , , , , , , , , , ,				J:4077\Gint\40	1770 ID. CHICAGO



LOG OF TEST BORING

Project American Chemical Service, Inc.
Still Bottoms/Treatment Lagoon
Location Griffith, Indiana

Boring No.

Job No.

4

SB135 4077.0075

Sheet

2 of 2

Surface Elevation
Northing: 673

637.1

Northing:

6737.0 5230.1

	S	AM	PLE		VISUAL CLASSIFICATION	SOIL	PRO	PERTIES
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qø) (tsf)	PID (ppm)	Remarks
8	20	W	10	-	Gray Brown, Fine to Coarse SAND (SP) to 15.5 ft, Grades into Gray Brown Fine Sand, Musty Propane Odor Present		159.0	
9	20	W/M	10	-	Gray Brown Fine SAND (SP), Grades into Dark Brown Sand at 18.0 ft, with Clay and Silt Lenses into Gray silty Clay at 18.5 ft Hard, Gray, Silty CLAY (CL-ML), Trace Fine	>4.5	168.0	
10	16	M	14	- - - 20-	to Coarse Sand and Gravel	>4.5		
				25-	End of Boring at 20.5 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.			
		1					}	



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No. Job No.

SB137 4077.0075

Sheet

1 of 2

Surface Elevation Northing:

637.6

6985.7 5225.5

	S	ΑM	PLE		VISUAL CLASSIFICATION	SC	IL PRO	PERTIES
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa)		Remarks
				_	Light Brown, Silty Fine SAND (SM)	(tsf)		
1	12	M	4				54.0	
1	12	141	7	-			34.0	
					Dark Gray/Brown Fine Silty SAND (SP)			
				-				
2	18	M/W	8	- -	Dark Gray Stained Silty, Fine to Medium SAND (SP)	-	10.0	
				-				
	ļ			— 5— -		_		
-	20	w	8		Dark Brown/Black Stained, Silty Fine to Coarse		12.0	Field analysis
				- : -	SAND (SP) 1 in. Oily Clay Layer at 6.5 ft			for PCBs
				-				
				-				
4	12	W	9	- -			64.0	Field analysis for PCBs
				-				ioi i CD3
				- 10-				
5	12	w	10	-			32.0	
				- :			32.0	
				_	Gray, Fine to Coarse SAND and Fine GRAVEL (GP)			
				_				
6	20	W	28	-			5.0	
				-	Gray Silty Fine To Medium SAND (SM)			
			\\/	- 15-		CENIED	AL NOT	EC
1/I	ule Dr	illing				/1/96 En		
Tir	ne Aft pth to	er Dr	illing		Driller E	E&F Ch		Rig CME 55
De	pth to	Cave	in		Drill Metho			
	The stra	tification may b	n lines oe grad	representual.	e approximate boundary between soil types and the		J\4077\Gent\40	2770 ID: CHICAGO



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No.

SB137

Job No.

4077.0075

Sheet

2 of 2

Surface Elevation Northing:

637.6

6985.7 5225.5

		Ü	V		1	Location Griffith, Indiana	Northing Easting:				
SAMPLE					21	00 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-500 VISUAL CLASSIFICATION	1	_ PROP	ERTIES		
	Rec. (in.)	Mois- ture	N Value	Depth (ft.)	1	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks		
	18	W/M	21	-		Gray Silty CLAY (CL-ML)		237.0			
	18	M	25	 20					-	2.0	
				-		End of Boring at 20.5 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.					
				25-							
				30-							
		: }	i								



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana Boring No.

SB138

Job No. Sheet

4077.0075 1 of 2

Surface Elevation 637.6

Northing:

6636.5 5397.5

		W	V		Location Griffith, Indiana 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5	Northing:		36 <u>.5</u> 97.5
	S	AM	PLE		VISUAL CLASSIFICATION		L PRO	PERTIES
No.	Rec. (in.)	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
1	18	M	7		Black/Dark Brown, Silty, Fine SAND (SM), Some Trace Organics, Solvent Odor Present		227.0	
2	20	M/W	8				519.0	Field analysis for VOCs
?	18	W	4	- - -	Black Stained, Silty, Fine to Coarse SAND (SM) Dark Gray, Silty, Fine to Medium SAND (SM)		388.0	
4	14	W	25	- - - - - 10-			216.0	
5	18	w	18	-			705.0	
6	18	w	24	- In the second			748.0	
		<u> </u>	W	- 15-	LEVEL OBSERVATIONS G	ENERA	L NOT	ES
Fime Dept Dept	e Afi th to th to	rilling ter Dr Water Cave	illing r	f		1/96 End & F Chie DAP Edito	2/1/90 f GH or PMS	Rig CME 55



30

LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Location Griffith, Indiana Boring No.

SB138 4077.0075

Job No. Sheet

2 of 2

Surface Elevation 637.6

Northing:

6636.5

5397.5

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 **SOIL PROPERTIES SAMPLE** VISUAL CLASSIFICATION PID Depth Rec. Moisand Remarks (ap) No. (ppm) Remarks (in.) ture Value (ft.) (tsf) Gray, Silty, Fine to Coarse SAND (SM) 818.0 $\overline{\mathbf{w}}$ 24 7 12 24 W/M 20 1538.0 Field analysis for PCBs **Brown Staining Present** Hydrophobic Dye Test Postive Gray, Silty CLAY (CL-ML) 1496.0 12 17 M End of Boring at 22.5 ft Grading to Gray Silty Fine to Coarse SAND at 9.5 ft (SP) 25-Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel.



Depth to Cave in

transition may be gradual.

The stratification lines represent the approximate boundary between soil types and the

LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No. Job No.

SB143 4077.0075

Sheet

1 of 2

Surface Elevation

637.6

Northing:

7078.6

Drill Method 2 1/4" I.D. HSA

J\4077\Gmt\40770_ID_CHICAGO_

5430.1

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 SAMPLE **SOIL PROPERTIES** VISUAL CLASSIFICATION Rec. Mois-Depth PID and Remarks (qa) No. E (in.) ture Value (ft.) (ppm) Remarks (tsf) Gray Slag and Gravel (FILL) Orange Brown to Brown Fine SAND (SP) 1 14 3 5.0 M Orange Brown Fine SAND (SP), Grades into 20 M 2 19.0 Black Stained Fine Sand, Trace Piece of Wood, Organics, Roots, Very Slight Sulfur Odor Present 5 Black Stained Fine SAND (SP) to 7.2 ft Grades 20 1052.0 Field analysis into Gray and Brown Fine Sand, Little Silt, for VOCs and Solvent Odor Present at 7.2 ft **PCBs** Dark Gray, Fine to Coarse SAND (SP), Silt 4 14 W 6 994.0 Field analysis Lense from 9.5 to 9.7 ft, Then into Black for VOCs and Stained, Fine to Coarse Sand and Gravel at 9 ft, **PCBs** Sheen and Solvent Odor Present 10-Dark Gray, Fine to Coarse SAND and Fine 5 20 $\overline{\mathbf{w}}$ 21.0 GRAVEL (SP), Becomes Light Gray at 12.2 ft, Slight Solvent Odor Present Dark Gray, Fine to Coarse SAND and Fine 6 16 $\overline{\mathbf{w}}$ 7.0 GRAVEL (SP), Becomes More Fine Sand at 14.8 to 15.5 ft, Musty Odor Present WATER LEVEL OBSERVATIONS **GENERAL NOTES** ft. Upon Completion of Drilling \(\frac{1}{2} \) ft. Start 2/6/96 End 2/6/96 Vhile Drilling Time After Drilling Driller E&F Chief GH Rig CME 55 Logger Depth to Water DAP Editor **PMS**



LOG OF TEST BORING

Project American Chemical Service, Inc. Still Bottoms/Treatment Lagoon

Griffith, Indiana Location

Boring No. Job No.

SB143 4077.0075

Sheet

2 of 2

Surface Elevation

637.6

Northing:

7078.6

5430.1

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 **SAMPLE** SOIL PROPERTIES VISUAL CLASSIFICATION Rec. Mois-PID Depth and Remarks No. (qa) (in.) ture Value (ppm) (ft.) Remarks (tsf) Dark Gray, Fine to Coarse SAND (SP), Grades 7 16.0 16 4 into Gray, Silty Fine Sand at 17.0 ft, Slight Musty Odor, Silt Seam at 17.5 ft to 17.7 ft Gray, Fine to Coarse SAND (SP), Trace Silt 22 W/M and Clay, Slight Musty Odor Present Very Stiff to Hard, Gray Silty CLAY (CL-ML), 4.0-4.5 Trace Fine to Coarse Sand 12 9 \overline{M} Hard, Gray Brown Silty CLAY (CL-ML) >4.5 End of Boring at 22.0 ft Borehole Backfilled with Bentonite Cement Grout. Topped with 6 inches of Gravel. 25-



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area Griffith, Indiana Location

SB217 Boring No. Job No. 4077.0075 Sheet 1 of 2 Surface Elevation

639.5

Northing: 6444.1 5602.8

No. (in.) ture Value (ft.)		S	ΑM	PLE		VISUAL CLASSIFICATION	L	_ PRC	PERTIES
Gravel/Soil FILL	No.	LLI.	1	1		and Remarks			Remarks
SAND (SM) 2 18 M 17 3 18 M/W 18 5 -					_	Gravel/Soil FILL	((0))		
SAND (SM) 2 18 M 17 3 18 M/W 18 5 -	1	18	M	14	_	Light Brown/Rust, Silty, Fine to Medium		0.0	
Trace Coarse Sand Dark Gray, Silty, Fine to Medium SAND, Brown Staining from 7.0 to 7.5 ft Trace to Little, Fine to Coarse GRAVEL and SAND at 8.5 to 8.7 ft Gray, Silty, Fine to Medium SAND, Trace Fine to Coarse Gravel (SM) 6 18 W 39					-				
Trace Coarse Sand Dark Gray, Silty, Fine to Medium SAND, Brown Staining from 7.0 to 7.5 ft Trace to Little, Fine to Coarse GRAVEL and SAND at 8.5 to 8.7 ft Gray, Silty, Fine to Medium SAND, Trace Fine to Coarse Gravel (SM) 6 18 W 39					-				
Trace Coarse Sand Dark Gray, Silty, Fine to Medium SAND, Brown Staining from 7.0 to 7.5 ft Trace to Little, Fine to Coarse GRAVEL and SAND at 8.5 to 8.7 ft Gray, Silty, Fine to Medium SAND, Trace Fine to Coarse Gravel (SM) 6 18 W 39	2	18	M	17			· · · · · · · · · · · · · · · · · · ·	49.0	
Trace Coarse Sand Dark Gray, Silty, Fine to Medium SAND, Brown Staining from 7.0 to 7.5 ft Trace to Little, Fine to Coarse GRAVEL and SAND at 8.5 to 8.7 ft Gray, Silty, Fine to Medium SAND, Trace Fine to Coarse Gravel (SM) 6 18 W 39					_				
Trace Coarse Sand Dark Gray, Silty, Fine to Medium SAND, Brown Staining from 7.0 to 7.5 ft Trace to Little, Fine to Coarse GRAVEL and SAND at 8.5 to 8.7 ft Gray, Silty, Fine to Medium SAND, Trace Fine to Coarse Gravel (SM) 6 18 W 39					-				
Dark Gray, Silty, Fine to Medium SAND, Brown Staining from 7.0 to 7.5 ft Trace to Little, Fine to Coarse GRAVEL and SAND at 8.5 to 8.7 ft Gray, Silty, Fine to Medium SAND, Trace Fine to Coarse Gravel (SM) 6 18 W 39	3	18	M/W	18	- 5-			50.0	
Dark Gray, Silty, Fine to Medium SAND, Brown Staining from 7.0 to 7.5 ft Trace to Little, Fine to Coarse GRAVEL and SAND at 8.5 to 8.7 ft Gray, Silty, Fine to Medium SAND, Trace Fine to Coarse Gravel (SM) 6 18 W 39					- 	Trace Coarse Sand			
Brown Staining from 7.0 to 7.5 ft Trace to Little, Fine to Coarse GRAVEL and SAND at 8.5 to 8.7 ft Gray, Silty, Fine to Medium SAND, Trace Fine to Coarse Gravel (SM) 6 18 W 39					- ¥	Trace Coarse Sand			
Trace to Little, Fine to Coarse GRAVEL and SAND at 8.5 to 8.7 ft Gray, Silty, Fine to Medium SAND, Trace Fine to Coarse Gravel (SM) 6 18 W 39	4 -	18	W	30				800.0	Field analysis
5 18 W 24 Gray, Silty, Fine to Medium SAND, Trace Fine to Coarse Gravel (SM) 6 18 W 39					- j				
6 18 W 39 1034.0					-				
6 18 W 39 - 1034.0	5	18	W	24	— _			650.0	
					— 10 –				
					- }				
Trace Elongated Cobbles	6	18	W	39	_			1034.0	
					[]	Trace Elongated Cobbles			
					-	\$ 1 }			:
7 20 W 21 Field analysis for VOCs and	7	20	W	21	— [] - []			2680.0	Field analysis for VOCs and
PCBs					[
15-14!					- - 15-				
WATER LEVEL OBSERVATIONS GENERAL NOTES	l	J	1	W	(LEVEL OBSERVATIONS G	ENERAI	NO1	ΓES
'/hile Drilling					6.5 t				
Depth to Water Logger PMS Editor DAP 850	De	pth to	Water	r		Logger P!	MS Edito	r DAF	850
Depth to Cave in The stratification lines represent the approximate boundary between soil types and the transition may be gradual. Drill Method 3 1/4" 1.D. HSA 23 1/4" 1.D. HSA	7	The stra	tificatio	n lines	represent				



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area Location

Griffith, Indiana

Boring No. Joh No.

SB217 4077.0075

Sheet

2 of 2

Surface Elevation

639.5

Northing:

6444.1 5602.8

					2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-50	- 00		
			PLE		VISUAL CLASSIFICATION	SOIL	. PROP	ERTIES
No.	Rec.	ture	Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
8	18	W	40	_	Trace Coarse SAND and Fine to Coarse GRAVEL (SM)		684.0	
9	18	W	37	-	1 in. Thin Silt Seam at 18.0 ft		118.0	
10	20	W/M	38	 - 20 -	2" Clay Lense at 20.5 ft		5.0	
11	18	W/M	35	-	Gray, Silty CLAY (CL-ML)		2.0	
12	18	M	30	 - 			0.0	
				- 25-1 - - -	End of Boring at 25.0 ft Abandoned Borehole with Bentonite Cement Grout. Topped at the Surface with Bentonite Chips.			
				- 30-				
	<u> </u>	; } !				[!		



hile Drilling

Depth to Water

Depth to Cave in

me After Drilling

transition may be gradual.

LOG OF TEST BORING

American Chemical Service, Inc. Off-Site Containment Area Location

Griffith, Indiana

Northing:

Boring No. SB218 Job No. 4077.0075 Sheet 1 of 2

Surface Elevation 634.7 6517.4

Easting: 5411.0 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-**5000**

SAMPLE SOIL PROPERTIES VISUAL CLASSIFICATION qu Rec. Mois-Depth PID and Remarks (qa) No. E (in.) ture Value (ft.) (ppm) Remarks (tsf) Light Brown, Silty, Fine to Medium SAND (SM) 18 M/W 291.0 Field analysis for PCBs Dark Gray, Silty, Fine to Medium SAND (SM), Trace Coarse Sand and Fine Gravel 18 $\overline{\mathbf{w}}$ 9 2358.0 Field analysis 2 for VOCs Trace Shell Fragments Present 3 12 $\overline{\mathrm{w}}$ 10 415.0 W 13 4 18 3662.0 Field analysis for VOCs 12 200.0 5 18 6 18 Ŵ 15 118.0 1 in. Thin SILT Seam at 14.5 ft WATER LEVEL OBSERVATIONS **GENERAL NOTES**

ft. Start

1/29/96 End

Drill Method 3 1/4" I.D. HSA

Driller E&F Chief

Logger PMS Editor

1/29/96

JE

DAP

∡A277.0am 40770 ⊔0, CHICAGO...

Rig CME

850

ft. Upon Completion of Drilling

The stratification lines represent the approximate boundary between soil types and the



LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area Location

Griffith, Indiana

Boring No. Job No.

SB218 4077.0075

634.7

Sheet

2 of 2

Surface Elevation Northing:

6517.4 5411.0

		Ū	Ū			Location Griffith, Indiana	Northing Easting:	5411	
			PLE			VISUAL CLASSIFICATION	SOIL		ERTIES
No.	Rec.	Mois- ture	N Value	Depth (ft.)	377	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
7	18	W	12			Gray Clayey SILT (ML)	3.0	5.0	
•	10			_		Gray Clayey GIET (ME)	2.5	3.0	
<u> </u>						End of Boring at 18.0 ft			
				- 20-		Abandoned Borehole with Bentonite Cement Grout. Topped at the Surface with Bentonite Chips.			
				-					
			 	 - 		·			
				-					
				- 25- -					
				-					
				_					
:								1 :	
				- 30- -] ; ;	
							i !	· ·	
ļ									



Depth to Cave in

The stratification lines represent the approximate boundary between soil types and the transition may be gradual

LOG OF TEST BORING

Project American Chemical Service, Inc. Off-Site Containment Area

Location Griffith, Indiana Boring No. Job No.

SB219 4077.0075

Sheet

1 of 2

Surface Elevation Northing:

633.0

Drill Method 3 1/4" I.D. HSA

6606.9 5299.9

Easting: 2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-5000 **SAMPLE** SOIL PROPERTIES VISUAL CLASSIFICATION qu PID Rec. Mois-Depth and Remarks (qa) No. (in.) ture Value (ft.) (ppm) Remarks (tsf) Dark Brown, Silty, Fine to Medium SAND (SM) 225.0 18 Field analysis 10 for PCBs Gray to Dark Gray, Silty, Fine to Medium SAND (SM), Trace Black Discoloration at 2.5 2 18 W 503.0 Field analysis 11 for VOCs Trace Clay Present W 291.0 13 12 4 18 $\overline{\mathbf{w}}$ 16 388.0 Field analysis for VOCs 210.0 5 18 $\overline{\mathbf{w}}$ 16 1 in, SILT Seam at 12.0 ft Some Fine to Coarse SAND from 12.5 to 12.6 20 W/M 18 4.0 55.0 6 Gray Silty CLAY (CL-ML) WATER LEVEL OBSERVATIONS **GENERAL NOTES** ile Drilling 1.5 ft. Upon Completion of Drilling ft. Start 1/30/96 End 1/30/96 Driller time After Drilling E&F Chief JE Rig CME Logger PMS Editor DAP 850 Depth to Water



LOG OF TEST BORING

Project American Chemical Service, Inc.
Off-Site Containment Area

Location Grif

Griffith, Indiana

Boring No.

SB219 4077.0075

Job No. Sheet

2 of 2

Surface Elevation

633.0

Northing:

6606.9

Easting:

5299.9

<u> </u>	_					2100 Corporate Drive, Addison, Illinois 60101, TEL. (708) 691-500	0		
	SAMPLE No. P (in.) (ture Value (ft.)					VISUAL CLASSIFICATION	ſ		PERTIES
No.	Y	Rec. (in.)	Mois- ture	N Value	Depth (ft.)	and Remarks	qu (qa) (tsf)	PID (ppm)	Remarks
					_				
<i></i>	1				-	End of Boring at 16.0 ft Abandoned Borehole with Bentonite Cement Grout. Topped at the Surface with Bentonite Chips.			
					- 20 				
					25- - 			!	
					- - -			:	
					- 30- - - -			,	

)

C

FIELD PCB RESULTS (OHMICRON ENVIRONMENTAL DIAGNOSTICS RAPID ASSAY SOIL TEST)

Run 1

Date: 19-Jan-96

Run ID	Sample Number	Sample #	<u>Depth</u>	<u>PCBs</u>	<u>≥10</u>
20:52	SB103	1	1 - 3	15.1	Y
20:52	SB104	2	18.5 - 20.5	ND	
20:52	SB106	3	8.5 - 10.5	39	Y
20:52	SB202A	4	13.5 - 15.5	ND	
20:52	SB202A	5	16 - 18	ND	
20:52	SB103	6	18.5 - 20.5	ND	
20:52	SB105	7	18.5 - 20.5	ND	
20:52	SB102	8	18.5 - 20.5	ND	
20:52	SB101	9	3.5 - 5.5	30.4	Y
20:52	SB102	10	3.5 - 5.5	ND	
20:52	SB101	11	1 - 3	22.1	Y
20:52	SB204	12	16 - 18	ND	
20:52	SB107	13	11 - 13	ND	
20:52	SB107	14	6 - 8	21.1	Y
20:52	SB204	15	13.5 - 15.5	ND	
20:52	SB105	16	8.5 - 10.5	3.5	
20:52	SB203	17	16 - 18	ND	
20:52	SB203	18	13.5 - 15.5	1.1	
20:52	SB106	19	18.5 - 20.5	1.8	
20:52	Proficiency A	20	NA	1.55 (ppb)	
20:52	Proficiency B	21	NA	2.29 (ppb)	
20:52	Proficiency C	22	NA	4.22 (ppb)	

Run 2

Date:

23-Jan-96

Run ID	Sample Number	Sample #	<u>Depth</u>	<u>PCBs</u>	≥10
17:21	SB206	1	5 - 7	ND	
17:21	SB206	2	7 - 9	ND	
17:21	SB207	3	13.5 - 15.5	ND	
17:21	SB207	4	16 - 18	ND	
17:21	SB207	5	21 - 23	ND	
17:21	SB108	6	3 - 5	>50	Y
17:21	SB108	7	9 - 11	3.5	
17:21	SB109	8	13 - 15	ND	
17:21	Proficiency A	9	NA	0.86 (ppb)	
17:21	Proficiency B	10	NA	2.31 (ppb)	
17:21	Proficiency C	11	NA	4.55 (ppb)	

Run ID	Sample Number	Sample #	<u>Depth</u>	PCBs	≥10
14:00	SB110	1	3 - 5	ND	
14:00	SB111	2	1 - 3	1.5	
14:00	SB111	3	7 - 9	5	
14:00	SB112	4	5 - 7	>50	Y
14:00	SB112	5	9 - 11	38.2	Y
14:00	SB113	6	7 - 9	17.3	Y
14:00	SB113	7	9 - 11	ND	
14:00	SB114	8	3.5 - 5.5	1.9	
14:00	SB114	9	8.5 - 10.5	1.4	
14:00	Proficiency A	10	NA	0.76 (ppb)	
14:00	Proficiency B	11	NA	1.80 (ppb)	
14:00	Proficiency C	12	NA	3.84 (ppb)	

Run 4 Date: 24-Jan-96

Run ID	Sample Number	Sample #	<u>Depth</u>	<u>PCBs</u>	>10
18:07	SB208	1	11-13	1.2	
18:07	SB208	2	23.5 - 25.5	ND	
18:07	SB209	3	16-18	ND	
18:07	SB209	4	18.5-20.5	ND	
18:07	SB210	5	16-18	ND	
18:07	SB210	6	18.5-20.5	ND	
18:07	SB115	7	3.5-5.5	ND	
18:07	SB115	8	6-8	ND	
18:07	Proficiency A	9	NA	0.68 (ppb)	
18:07	Proficiency B	10	NA	1.81 (ppb)	
18:07	Proficiency C	11	NA	4.49 (ppb)	!

Run 5 Date: 25-Jan-96

Run ID	Sample Number	Sample #	<u>Depth</u>	<u>PCBs</u>	<u>≥10</u>
12:26	SB116	1	3.5 - 5.5	ND	
12:26	SB116	2	6 - 8	1.5	
12:26	SB117	-3	3.5 - 5.5	ND	
12:26	Proficiency A	4	NA	0.65 (ppb)	,
12:26	Proficiency B	5	NA	1.89 (ppb)	
12:26	Proficiency C	6	NA	4.11 (ppb)	

Run 6 Date: 25-Jan-96

Run ID	Sample Number	Sample #	<u>Depth</u>	<u>PCBs</u>	<u>>10</u>
17:45	SB118	1	6 - 8	4.2	
17:45	SB118	2	11 - 13	ND	
17:45	SB119	3	6 - 8	17.9	Y
17:45	SB119	4	11 - 13	ND	
17:45	SB205A	5	8.5 - 10.5	ND	
17:45	SB205A	6	23.5 - 25.5	ND	
17:45	SB211	7	8.5 - 10.5	ND	
17:45	SB211	8	18.5 - 20.5	ND	
17:45	SB120	9	3.5 - 5.5	>50	Y
17:45	SB120	10	11 - 13	1.5	
17:45	Proficiency A	11	NA	NR	
17:45	Proficiency B	12	NA	NR	
17:45	Proficiency C	13	NA	NR	;

Run 7 Date: 26-Jan-96

Run ID	Sample Number	Sample #	<u>Depth</u>	<u>PCBs</u>	≥10
12:26	SB121	1	6 - 8	6.5	
12:26	SB121	2	8.5 - 10.5	ND	
12:26	SB122	3	6 - 8	15.6	Y
12:26	SB212	4	19 - 21	ND	
12:26	SB213	5	23.5 - 25.5	ND	
12:26	Proficiency A	6	NA	0.53 (ppb)	
12:26	Proficiency B	7	NA	1.79 (ppb)	
12:26	Proficiency C	8	NA	4.58 (ppb)	

Run 8 Date: 29-Jan-96

Run ID	Sample Number	Sample #	<u>Depth</u>	<u>PCBs</u>	<u>≥10</u>
16:55	SB123	1	3.5 - 5.5	ND	
16:55	SB123	2	6 - 8	ND	
16:55	SB124	3	6 - 8	ND	
16:55	SB124	4	8.5 - 10.5	5.2	
16:55	SB125	5	6 - 8	36.5	Y
16:55	SB125	6	8.5 - 10.5	ND	
16:55	SB214	7	13.5 - 15.5	10.6	Y
16:55	SB214	8	18.5 - 20.5	ND	
16:55	SB215	9	17 - 19	ND	
16:55	SB215	10	19 - 21	ND	
16:55	Proficiency A	11	NA	0.57 (ppb)	
16:55	Proficiency B	12	NA	1.73 (ppb)	
16:55	Proficiency C	13	NA	4.60 (ppb)	

Run 9

Date: 30-Jan-96

Run ID	Sample Number	Sample #	<u>Depth</u>	<u>PCBs</u>	>10
13:30	SB126	1	11 - 13	7.6	
13:30	SB216	2	13.5 - 15.5	ND	
13:30	SB217	3	7 - 9	ND	
13:30	SB217	4	13 -15	ND	1
13:30	SB127	5	6 - 8	8.5	
13:30	SB127	6	8.5 - 10.5	ND	
13:30	Proficiency A	7	NA	0.31 (ppb)	
13:30	Proficiency B	8	NA	1.82 (ppb)	
13:30	Proficiency C	9	NA	4.08 (ppb)	

Run 10

Date: 30-Jan-96

Run ID	Sample Number	Sample #	<u>Depth</u>	<u>PCBs</u>	>10
18:43	SB128	1	6 - 8	4.3	
18:43	SB128	2	8.5 - 10.5	ND	
18:43	SB218	3	1 - 3	ND	
18:43	SB219	4	1 - 3	ND	
18:43	SB129	5	6 - 8	ND	
18:43	SB129	6	11 - 13	4	
18:43	Proficiency A	7	NA	0.50 (ppb)	
18:43	Proficiency B	8	NA	1.71 (ppb)	
18:43	Proficiency C	9	NA	3.63 (ppb)	

Run 11 Date: 31-Jan-96

Run ID	Sample Number	Sample #	<u>Depth</u>	<u>PCBs</u>	<u>≥10</u>
18:13	SB130	1	6 - 8	ND	
18:13	SB130	2	8.5 - 10.5	ND	
18:13	SB131	3.	6 - 8	ND	
18:13	SB132	4	8.5 - 10.5	ND	
18:13	SB220	5	8.5 - 10.5	ND	
18:13	SB220	6	11 - 13	ND	t
18:13	Proficiency A	7	NA	0.37 (ppb)	
18:13	Proficiency B	8	NA	1.38 (ppb)	
18:13	Proficiency C	9	NA	3.52 (ppb)	

Run 12 Date: 1-Feb-96

Run ID	Sample Number	Sample #	<u>Depth</u>	<u>PCBs</u>	≥10
15:23	SB133	I	6 - 8	ND	
15:23	SB133	2	11 - 13	1.2	
15:23	SB221	3	9 - 11	ND	
15:23	SB221	4	11 - 13	ND	
15:23	SB222	5	13.5 - 15.5	ND	
15:23	SB134	6	5 - 7	ND	
15:23	SB134	7	19-21	19.3	Y
15:23	Proficiency A	8	NA	0.67 (ppb)	
15:23	Proficiency B	9	NA	2.10 (ppb)	
15:23	Proficiency C	10	NA	4.37 (ppb)	

Run ID	Sample Number	Sample #	<u>Depth</u>	<u>PCBs</u>	>10
19:04	SB135	1	5 - 7	23.8	Y
19:04	SB135	2	7 - 9	ND	
19:04	SB137	.3	6 - 8	20	Y
19:04	SB137	4	8.5 - 10.5	ND	
19:04	SB136	5	5 - 7	ND	
19:04	Proficiency A	6	NA	0.58 (ppb)	
19:04	Proficiency B	7	NA	1.82 (ppb)	
19:04	Proficiency C	8	NA	3.82 (ppb)	

Run 14

Date:

8-Feb-96

Run ID	Sample Number	Sample #	<u>Depth</u>	<u>PCBs</u>	>10
19:32	SB138	1	18.5 - 20.5	26.8	Y
19:32	SB139	2	6 - 8	2.8	
19:32	SB140	3	8.5 - 10.5	ND	
19:32	SB141	4	6 - 8	ND	
19:32	SB141	5	8.5 - 10.5	1.5	
19:32	SB142	6	6 - 8	ND	
19:32	SB142	7	8.5 - 10.5	ND	
19:32	SB143	8	6 - 8	13.9	Y
19:32	SB143	9	8.5 - 10.5	16.4	Y
19:32	SB144	10	8.5 - 10.5	8.3	i
19:32	SB144	11	11 - 13	7.4	
19:32	Proficiency A	12	NA	1.13 (ppb)	
19:32	Proficiency B	13	NA	2.17 (ppb)	•
19:32	Proficiency C	14	NA	3.57 (ppb)	

Run ID	Sample Number	Sample #	<u>Depth</u>	<u>PCBs</u>	<u>>10</u>
19:56	SB149	1	8.5 - 10.5	10.1	Y
19:56	SB149	2	16 - 18	14.4	Y
19:56	SB223	3	18.5 - 20.5	7.3	
19:56	SB150	4	6 - 8	>50	Y
19:56	SB151	5	5 - 7	14.4	Y
19:56	SB151	6	9 - 11	13.9	Y
19:56	SB152	7	7 - 9	15	Y
19:56	SB152	8	9 - 11	33	Y
19:56	Proficiency A	9	NA	0.67 (ppb)	
19:56	Proficiency B	10	NA	2.25 (ppb)	
19:56	Proficiency C	11	NA	4.70 (ppb)	

Notes:

The notes provided below refer to the tables for PCB test kit Runs 1 through 15 PCB Sample results are reported in parts per million (ppm)

Proficiency sample results are reported in parts per billion (ppb)

Run ID - Identifies the time of day sample analysis run was complete

Sample Number - Soil boring number or Proficiency samples A, B or C

Sample # - The location (or order) in the run in which the sample was analyzed

Depth - Depth below ground surface sample was collected

Results > 10 - Refers to PCB results greater than or equal to waste criteria (10 ppm) as defined in the ROD, Y (Yes)

NA - Not Applicable to Proficiency Samples

Proficiency samples were overlooked on Run 6, therefore no results (NR) were recorded

Proficiency Samples

<u>Sample</u>	Range (ppb)	<u>Mean</u>
Α	0.33-0.68	0.50
В	1.28 - 2.13	1.70
C	3.20 - 4.80	4.00

******* OHMICRON ******

'ease Wait 30 Minutes -19-96 20:51:31

01-19-96 20:52:38

****** OHMICRON ******

PROTOCOL :

PCB

TECH ID : M. PAULI LOT # : EXP DATE:

Data Reduct:Lin.Regression
Xformation: Ln/L9t8
Read Mode : Absorbance
Wavelength : 450 nm
Units : PPB

EQUATION OF LINE:

Intercept = -0.659 Corr (r) = 0.9968

Transformed Data:

Conc	Abs
-1.39	1.190
0.00	0.136
1.61	-0.790

"Calibrator Data:

Conc	Abs Diff	4CV	Predic %Diff
9.00	1.402 1.300		
Mean	1.351	5.3	
0.25 Mean	1.036 -0.018 1.036 -0.018 1.036	0.0	0.23 -7.7 0.23 -7.7
nean	-0.018	0.0	0.23 -7.7
1.00	0.753 -0.005 0.690 0.325		1.00 -0.5 1.33 24.5
Mean	9.721 9.149	6.2	1.15
5.00	0.415 -0.146 0.428 -0.469		4.85 -3.0 4.53
Hean	0.422	2.2	-10.4 4.69 -6.6

Ctrl#	Abs	Conc
1	9.493	3.27
ID:		

Samples Data :

Sp1#	Abs	Conc
1	9.660	1.51
10: S	B 103	1-3
2	1.256	0.03nd
10:21.5	B104	18.5-20.5
7.7		
ა 	0.458 6.01	8.5-10.5
10: _3	5100	1.5 (0.5
	1.303	. 0.01nd ,
ID: _5	B202A	13.5-15.5
5	1.272	8.02nd
		16-18
		0.04nd
		18.5-20.5°
ID:S	ر از	
	1.171	0.08nd
ID: _5£	3105	18.5-20.5
8	1.212	9.95nd
10: 50	3102	18.5-20.5
	 0.509	
		3.5-5.5°
10	1.185	0.87nd
ID: 36	3102	3.5-5.5'
	9.577	2.21
ID: _5	6101	1-3'
12	1.217	0.95nd
		16-18

13 1.322

ID: 53107

14 0.587

ID: 5B107 6-81

9.89nd 11-13

2.11

15 10: 56204 13.5-15.5 16 9.967 0.35 ID: 58105 8.5-10.5" 17 1.273 0.02nd 10: 56 203 16-18' 18 1.142 0.11 10: 5B 203 13.5-15.5 1.074 0.13 18.5-20.5 10: 58 lob 0.654 28 1.55 ID: PROFICIENCY A 2.29 0.569 ID: PRIFICIENCY B 22 0.442 4.22 10: PROFICIENCY

END OF RUN 01-19-2 ****

Please Wait 30 Minutes 01-23-96 16:31:12

01-23-96 17:21:21

****** OHMICRON ******

PROTOCOL:

PCB

TECH ID : 75 Burke LOT : 75 ST

Data Reduct:Lin.Regression
Xformation: Ln/LgtB
Read Mode: Absorbance
Wavelength: 450 nm
Units: PPB

EQUATION OF LINE:

Slore = -1.004 Intercept = 0.762 Corr (r) = 0.9996

Transformed Data:

Conc	Abs
-1.39	2.179
0.00	0.715
1.61	-0.832

Calibrator Data:

Conc	Abs Diff	%CV	Predic
0.00	0.756 1.023		
Mean	0.889	21.2*	
0.25	0.806 -0.028 0.792 0.016		0.22 -12.7 0.27 6.1
Mean	0.799 -0.006	1.3	0.24 -2.5
1.00	0.607 -0.006 0.587		0.99 -0.6 1.10
Mean	0.104 0.597 0.048	2.4	9.4 1.05 4.6
5.89	0.279 -0.359 0.269	4 3	4.65 -7.6 5.16
Mear	8.15 8.27	ē 5. <u>.</u>	4.38

Con ---Ctrl# Abs Conc 1 0.355 3.21 ID:_____ Samples Data : Spl# Abs Conc 1 0.911 10: SB206 0.978 2 10: 5B206 3 1.032 nd 0.987 nd 10: 5B207 1.012 ·nd 7 0.765 8.35 10:5B 108 9-11 8 0.920 nd 10:5B 109 9 0.634 0.86 2.31 0.427 10 11 END OF 5 .01-23

Please Wait 30 Minutes 01-24-96 11:34:37

01-24-96 14:00:19

****** OHMICRON ******

PROTOCOL:

PCB

TECH ID :_ LOT # :___

Data Reduct:Lin.Regression Xformation: Read Mode : Ln/L9tB Absorbance 450 nm PPB Wavelength: Units

EQUATION OF LINE :

-0.783 Slope 0.335 0.9997 Intercept = Corr(r) =

Transformed Data:

Conc Abs 1.401 0.370 -0.940 -1.39 0.00 1.61

Calibrator Data:

Conc	Abs Diff	%CV	Predic %Diff
9.00	0.974 0.931		
Mean	0.953	3.2	
0.25	0.773 -0.011 0.756 0.024		0.24 -4.8 0.27 8.8
Hean	0.764 0.006	1.5	0.26 2.4
1.90	0.579 -0.121 0.548 0.040		0.88 -13.8 1.04 3.9
Mean	0.563 -0.043	3.8	0.96 -4.5
5.00	0.282 -0.354 0.253		4.65 -7.6 5.62
Mε			

Contro.

Ctrl# Abs Conc 1 0.326 3.55 ID:_____

Samples Data:

Spl# Abs Conc 0.861 0.09nd 0.822 0.15 10: 5B 111 0.674 ID: 5B111 0.238 6.24Hi 0.313 3.82 10:5B112 8.455 1.73 0.861 0.09nd 0.19 0.800 ID: _< 0.828 9.603 10 0.76 0.447 1.80 11

END : 01-2-

0.312

3.84

12

***** PROTOCOL: PCB

TECH ID : 451891 LOT # 451891 EXP DATE: 9796

Data Reduct:Lin.Regression Xformation: Ln/L9tB
Read Mode: Absorbance
Wavelength: 450 nm
Units: PPB

EQUATION OF LINE :

Slope = -0.783 Intercept = 0.434 Corr (r) = 0.9964

Transformed Data:

Conc	Abs
-1.39	1.582
0.00	0.318
1.61	-0.772

Calibrator Data:

Conc	Abs Diff	%CV	Predic %Diff
0.00	0.918 0.889 0.984	2.3	
Hean	0.704	2.5	
	0.739 0.006 0.760 -0.043 0.750	2.0	9.26 2.4 9.21 -20.9 0.23
nean	-0.019		-8.3
1.00	0.511 0.242 0.535 0.082		1.24 19.5 1.08 7.6
Hean	9.523 0.160	3.2	1.16
5.00	0.283 -0.242 0.289 -0.418		4.76 -5.1 4.58 -9.1
Mean	0.286 -0.331	1.4	4.67

Con

Ctr. 1 0.336 3.40 ID:____

Samples Data: -----

Sel#	Abs	Conc	
	0.805	0.12	
ID:_=	2B 20	08	11-13
2	0.941	nd	3.5-992
ID: S	B 20	8 J	3.2-997
3	0.838	0.07nd	1
	s <u>B</u> 20		
4	0.881	0.02nd	1
			8.5-20.5
	0.847		
کــ:۱۵	B21	<u> </u>	6-18
	0.875		
کے۔:۱۵	13 21	0 18	<u>.5-20.5</u>
7	0.825	0.09nd	1
ک۔:۵۱	13 II	53	5-55
	9.877		
يك_:10	B 115	5	-8.
	3.612		
10:_Y	coficien	<u> </u>	
19	3.446	1.81	2
10:	roficin	incy l	5
11 (3.292	4.49	_
ID: - Y_1	coficil	rcx (<u></u>
		/	

END OF F 01 01-25-96 12:26:18

****** OHMICRON ******

PROTOCOL:

PC8

TECH ID : T. Burk LOT # : 951368 EXP DATE: 5-96

Data Reduct:Lin.Regression
Xformation: Ln/L9t8
Read Mode: Absorbance
Wavelength: 450 nm
Units: PPB

EQUATION OF LINE:

Slope = -0.635 Intercept = 0.322 Corr (r) = 1.0000

Transformed Data :

Conc	Abs
-1.39	1.202
0.00	0.323
1.61	-0.701

Calibrator Data:

Conc	Abs Diff	%CV	Predic %Diff
0.00	0.708 0.708		
Mean	0.708	0.0	
0. 25	0.553 -0.027 0.535 0.030		9.22 -12.1 9.28 19.6
Mean	0.544 0.000	2.3	0.25 0.1
1.00	0.393 0.171 0.428 -0.152		1.17 14.6 0.85 -17.9
Mean	9.411 -0.002	6.1	1.00 -0.2
5.00	0.235 -0.016		4.98

Mean

Control Data : Ctrl# Abs Conc 1 0.274 3.43 ID:_____ Samples Data: Abs Spl# Conc 0.683 0.01nd 0.583 0.15 0.696 0.00nd 0.65 END TO THE 81-

*****	กับสองกักษ	****
PROTOCOL	:	PCB
	7. B.	

Data Reduct:Lin.Regression Xformation: Ln/L9tB Read Mode: Absorbance Wavelength: 450 nm Units: PPB

EQUATION OF LINE :

Slope = -0.643 Intercept = 0.332 Corr (r) = 0.9999

Transformed Data:

Conc	Abs
-1.39	1.231
0.00	0.320
1.61	-0.698

Calibrator Data:

Conc	Abs Diff	%CV	Predic %Diff
0.00	0.827 0.820		
Mean	0.824	9.6	
0.25	0.639 -0.006 0.636		0.24 -2.4 0.25 0.3
Mean	0.001 0.637 -0.003	0.3	0.25 -1.0
1.00	0.478 0.016 0.477 0.022		1.02 1.6 1.02 2.2
Mean	9.477 9.019	0.1	1.02
5.00	0.277 -0.180 9.279		4.82 -3.7 5.18
Mean	جدمل ہے۔		

1

Cont:
Ctrl# Abs Conc
1 0.316 3.51
ID:
Samples Data :
Spl# Abs Conc
1 0.583 0.42 10: 5B18 6-8
·
2 0.807 0.00nd ID: SB 18 11-13
3 0.403 1.79
ID: 5B119 6-8
4 0.814 0.80nd
10: SB 119 11-13
5 8.764 8.83nd 10: 5B205 A 8.5-10.5
6 0.820 0.00nd
10: 5B205A 23,5-255
7 0.832 nd
10:5B211 8.5-10.5
8 0.810 0.00nd
10:5B21/ 18.5-20.5
9 0.179 12.25Hi
10:5 <u>B120</u> 3.5-5.5
18 0.678 8.15 10: 5B120 11-13
10: 313120 11-13

Please ward 30 Minutes 19 01-26-96 11:34:33

81-26-96 12:26:14

****** OHMICRON ******

PROTOCOL:

PCB

TECH ID : 1. Burks LOT : 951368 EXP DATE: 5296

Data Reduct:Lin.Regression Xformation: Ln/L9tB Read Mode: Absorbance Wavelen9th: 450 nm Units: PPB

EQUATION OF LINE :

5lore = -0.644 Intercept = 0.322 Corr (r) = 0.9995

Transformed Data:

Conc	Abs
-1.39	1.234
0.00	6.288
1.61	-0.698

Calibrator Data:

Conc	Abs Diff	አርሀ	Predic %Diff
0.00	0.789 0.782		
Mean	9.785	0.7	
0.25	0.612 -0.018 0.604 0.004		0.23 -7.9 0.25 1.7
Mean	9.698 -0.007	1.0	0.24 -2.9
1.00	0.455 0.001 0.442 0.113		1.00 0.1 1.11 10.1
ifean	0.449 0.055	2.1	1.06
5.00	9.266 -0.349		4.65 -7.5

Mean

Contro

Etrl#	Abs	Conc
1	0.295	3.63
ID:		

Samples Data:

		•
Spl#	Abs	Conc
	0.507	
10:	B12)	6-8
2	0.720	0.04nd
1D: <u>S</u>	B12	8.5-10.5
3	0.399	1.56
10:5	B139	× 6-8
4	0.773	0.00nd
الم: ١٥:	5B212	2 19-21
5	0.779	0.00nd
<u>ک</u> :10	B213	3 23,5-255
6	9.531	0.53
10:_\$	rofici	rency 17
7	0.382	1.79 R
₩.	- Co- 00	o a y B

4.58

Please Wait 30 Minutes 01-29-96 15:58:56

01-29-96 16:55:11

****** OHMICRON ******

PROTOCOL:

PCB

TECH ID : T. Burke LOT # 951368 EXP DATE: 5/96

Data Reduct:Lin.Regression
Xformation: Ln/L9tB
Read Mode : Absorbance
Wavelength : 450 nm
Units : PPB

EQUATION OF LINE :

Slope = -0.694 Intercept = 0.261 Corr (r) = 0.9984

Transformed Data:

Conc	Abs
-1.39 0.00	1.261 0.192 -0.824

Calibrator Data:

Conc	Abs Diff	አርሀ	Predic %Diff
0.00	0.866 0.865		
Mean	0.866	0.1	
0.25	0.681 -0.029 0.667 0.003		0.22 -12.9 0.25 1.3
Mean	0.674 -0.013	1.5	0.24 -5.5
1.00	0.504 -0.096 0.445 0.346		0.90 -10.6 1.35 25.7
Mean	8.474 6.164	8.8	1.10
5.00	0.268 9.375		4.62 -8.1 4.93

Мe

Content baca :

Ctrl#	Abs	Conc
1	0.311	3.36
ID:		

Samples Data:

Sp1#	Abs	Conc
1	0.759	0.09nd
ID:	<u>513 12</u>	<u>3 3,5-5,5</u>

Please Wait 30 Minutes 01-30-96 12:33:43

01-30-96 13:30:52

****** OHMICRON ******

PROTOCOL:

PCB

TECH ID : T. Burke LOT : 951368 EXP DATE: 5/96

Data Reduct:Lin.Regression
Xformation: Ln/Lgt8
Read Mode: Absorbance
Wavelength: 450 nm
Units: PPB

EQUATION OF LINE :

Slope = -0.778 Intercept = 0.559 Corr (r) = 0.9973

Transformed Data:

Conc	Abs
-1.39	1.690
0.00	0.461
1.61	-0.647

Calibrator Data:

Conc	Abs Diff	%CV	Predic %Diff
0.00	0.780 0.760		
Mean	0.770	1.8	
0.25	0.645 -0.002 0.655 -0.031		0.25 -0.6 0.22 -14.1
Mean	0.650 -0.016	1.1	0.23 -7.0
1.00	0.467 0.178 0.478 0.093		1.18 15.1 1.09 8.5
Mean	9.472 0.135	1.6	1.13
5.00	0.256 0.014		5.01 .0.3
Mean	-		

Cor
Ctrl# Abs Conc
1 0.318 3.22
ID:
Samples Data:
Spl# Abs Conc
1 0.527 0.76
10:5B 126 11-13
2 0.839 nd
10:5B 216 13.5-15.5
3 0.820 nd
10:5B217 7-9
4 0.839 nd
10:5B217 13-15
5 0.512 0.85
10: 5B 127 6-8
6 0.735 0.04nd
10:5B127 85-105
7 0.627 0.31
10: Proficiency A 8 0.403 1.82
8 0.403 1.82
10: Proficiency B
9 0.284 4.08 ID: Proficiency
10: I toticimcy
END 01-3

PROTOCOL : PCB TECH ID : _____ | Sur LOT # : _____ | 1361 EXP DATE: ____ 5/96

Data Reduct:Lin.Regression Xformation: Read Mode : Wavelength : Ln/L9tB Absorbance

Units

450 nm PPB

EQUATION OF LINE :

-0.702 0.115 = Slope Intercept = Corr(r) =0.9981

Transformed Data:

Conc Abs -1.39 1.128 0.00 0.040 1.61 -0.980

Calibrator Data:

Conc	Abs Diff	%EV	Predic %Diff
0.00	0.840 0.834		
Mean	0.837	0.5	
0.25	0.630 -0.008 0.635		0.24 -3.1 0.23 -8.8
Mean	-0.020 8.633 -0.014	0.6	0.24 -5.9
1.00	0.431 0.085 0.423 0.141		1.08 7.8 1.14 12.4
Mean	0.427 0.113	1.2	1.11
5.00	0.238 -0.592 0.213 0.148		4.41 -13.4 5.15
Hean	9 -8		

Contro

Ctrl# Abs Conc 1 0.273 3.32 ID:_____

Samples Data:

Conc 5p1# Abs 1 9.569 0.43

0.773 0.03nd

1.546

0.803 0.01nd

0.781 0.03nd

0.569 0.40

0.50

0.364 8 1.71

0.261 3.63

END " 0101-31-96 18:13:14

PROTUCOL:

PCB

TECH ID : T. Buyke

Data Reduct:Lin.Regression
Xformation: Ln/L9tB
Read Mode : Absorbance
Wavelength : 450 nm
Units : PPB

EQUATION OF LINE :

5lope = -0.667 Intercept = 0.092 Corr (r) = 0.9998

Transformed Data:

Conc	Abs
-1.39 0.00	1.028 0.072 -0.972

Calibrator Data:

Conc	Abs Diff	አር ሀ	Predic %Diff
0.00	1.099		
Mean	1.090	1.1	
0.25	0.781 0.037 0.825 -0.041		0.29 12.8 0.21 -19.5
Mean	9.803 -0.004	3.9	0.25 -1.7
1.00	9.563 0.040 9.566 0.022		1.04 3.9 1.02 2.1
Mean	9.565 9.931	0.4	1.03
5.00	0.295 0.072		5.07 1.4 4.79

Ħe:

Cont

Ctrl# Abs Conc 1 0.388 2.79 ID:_____

Samples Data:

SP1# Abs Conc 1 0.970 0.05nd ID: 5B 130 6-8

2 1.014 0.02nd 10:5B130 8.5-10.5

3 1.076 0.00nd 10:5B131 6-8

4 1.862 8.81nd

5 1.029 0.02nd 0:5B220.8.5-10,5

6 1.131 nd b: SB20 11-13

7 0.740 0.37 10: Proficiency A

8 0.511 1.38 10: Proficiency B 9 0.350 3.52

10: Proficiency C

END (01-31 ****

02-01-96 15:23:25

****** OHMICRON ******

PROTOCOL:

PCB

TECH ID: 9518921 LOT # 9518921 EXP DATE: 7/96

Data Reduct:Lin.Regression Ln/L9tB Xformation: Read Mode : Absorbance Wavelen9th : Units 450 nm PPB

EQUATION OF LINE :

Slope = -0.757 Intercept = 0.205 Corr (r) = 0.9983

Transformed Data:

Conc	Abs
-1.39	1.294
0.00	0.129
1.61	-0.978

Calibrator Data:

Conc	Abs Diff	%CV	Predic %Diff
0.00	1.508		
Hean	1.494	1.3	
0.25	1.166 -0.005 1.179 -0.021		9.25 -2.9 9.23 -9.2
Mean	1.172	0.8	0.24 -5.5
1.00 Mean	0.778 0.171 0.811 0.042 0.795	2.9	1.17 14.6 1.04 4.0 1.10
	0.105		9.5
5.00	0.407 -0.199		4.80 -4.2

Mean

Contro.

Ctrl# Abs Conc 1 0.488 3.40 ID:_____

Samples Data:

Sp1# Abs Conc 1 1.418 0.03nd 2 1.280 3 1.411 0.03nd 4 1.389 0.04nd 0.03nd 1.406 1.425 0.02nd 9.428 10 END 0: 02-81

****** OHMICRON *******

PROTOCOL:

PCB

TECH ID : TECH ID : 457893 EXP DATE: -7/96

Data Reduct:Lin.Regression
Xformation: Ln/L9t8
Read Mode: Absorbance
Wavelength: 450 nm 450 nm •

Units

EQUATION OF LINE:

-0.784 0.262 Slope = Intercept = 0.9959 Corr (r) =

Transformed Data:

Conc	Abs
-1.39 9.00	1.414 0.139 -0.943

Calibrator Data:

Mean

Conc	Abs Diff	иси	Predic %Diff
0.00	1.018		
Mean	1.000	2.5	
0.25	0.806 -0.022 0.803 -0.018	0.2	0.23 -9.9 0.23 -7.7 0.23
Mean	0.804 -0.020	0.2	-8.8
1.99	0.530 0.197 0.539 0.142		1.20 16.4 1.14 12.5
Mean	9.535 9.169	1.2	1.17 14.5
5.90	0.283 -0.421		4.58 -9.2

Control Ctrl# Abs Conc 1 9.341 3.23 ID:_____ Samples Data: Sel# Abs Conc 0.397 2.38 2.00 1.014 6 0.665 0.58 1.82 0.312 3.82 Ð.

02-08-96 19:32:44

****** OHMICRON ******

PROTOCOL: PCB

TECH ID : PHIL SOUTH
LOT # :----EXP DATE:

Data Reduct:Lin.Regression Xformation: Ln/L9tB Read Mode: Absorbance Wavelength: 450 nm Units: PPB

EQUATION OF LINE :

Slope = -0.751 Intercept = 0.446 Corr (r) = 0.9983

Transformed Data:

Conc	Abs
-1.39	1.528
0.00	0.371
1.61	-0.728

Calibrator Data:

Conc	Abs Diff	2CV	Predic %Diff
0.00	0.894 0.981		
Mean	0.938	6.6	
9.25	0.774 -0.022 0.767 -0.005		0.23 -9.4 0.25 -1.8
Mean	9.771 -0.013	0.7	0.24 -5.5
1.00	0.576 -0.026 0.533 0.252		0.97 -2.7 1.25 20.1
Mean	0.555 0.105	5.4	1.11
5.00	0.333 -0.990 0.272		4.01 -24.7 5.73

Μe

Ctrl#	Abs	Conc	
1	0.390	2.85	
:D:			

Samples Data:

		_
Sr:1#	Abs	Conc
1	0.400	2.68
<u>ک</u> : ID	B138 18	5-205
2	0.751	0.28
ID:	5B139	6-8"
2	0.872	0.06nd
ID::	58140 8	75-105
4	0.868	0.06nd
10:	58141	6.8"
5	0.813	0.15
ID:	8141	815-10.5'
6	0.390	0.04nd
ID:	SB142	6-81
7	0.891	0.04nd
ID:_5	B142	8.5-10.5'
8	0.515	1.39
ID:	53143	C-D'
9	0.487	1.64
ID:	8143	8.5-10.5
10	0.602	0.83
10:5	53144	8.5-10.5'
11	0.621	0.74
ID:	58144	//-/3 '
12	0.551	1.13
1D: Z	PURLIEN	× J A
13	0.437	2.17
ID:_Z	PAURUE	cry B
		•

14 0.352 3.57

10: Properting

02-13-96 19:56:43

******* OHMICRON ******

PROTOCOL :

PCB

TECH ID : MARK PAUL | LOT # : 951391 EXP DATE: 9176

Data Reduct:Lin.Regression Xformation: Ln/L9tB Read Mode : Absorbance Wavelength : 450 nm Units : PP8

EQUATION OF LINE :

Slope = -0.663 Intercept = 0.480 Corr (r) = 0.9998

Transformed Data:

Conc Abs -1.39 1.413 0.00 0.456 1.61 -0.576

Calibrator Data:

Conc	Abs Diff	%CV	Predic %Diff
0.00	1.039		
Mean	1.025	2.0	
0.25	9.839 -0.019 9.818 9.010		0.23 -8.1 0.26 3.7
Mean	0.824 -0.005	1.1	0.25 -2.0
1.00	0.626 0.048 0.629 0.027		1.05 4.6 1.03 2.6
Mean	0.627 0.037	0.4	1.04
5.00	0.367 -0.045 0.370		4.96 -0.9 4.88
Mean	-0.122 0.369 -0.084	0.5	-2.5 4.92 -1.7

Ctrl# Abs Conc 1 0.419 3.59 1D: 3.01 0.6 4: \$951879

Samples Data :

		_
SpI#	Abs	
	0.632 C4:119	2.5-10.5'
2	0.573	16-(8
10:_=	5.57.7.1.	
-	0.767	0.77
10:	3/3/2/2	18.5-20.5
4	й. 295	8.07Hi, 6-8
5 ID:	0.573 5 B (5 (1.44 5-7
ID::	0.580 SB15 (9-11
7	0.566	1.50 ,
10:_5	13152	7-9
3	0.433	3.30
ID:	SB152	9-11
^	0.695	A
10: <u>P</u>	46711141	vey A
10	0.497	2.25
10: <u>12</u>) WF1C181	ucy D
11	0.376 WAC14N	4.70
10: 1	WACIEN	cy C

END OF RUN 02-13-96 19:59:51

D

FIELD GC RESULTS - VOCS

FIELD GC SUMMARY SHEET - Still Bottoms/Treatment Lagoon

ACS NPL SITE Griffith, Indiana

Boring	Depth	PID Reading	DF	Acetone	1,1 Dichloroethene	trans 1,2 Dichloroethene	1,1 Dichloroethane	2-Butunore (MEK)cis 1,2-DCE	as 1,2 Dichloroethene	1,2 Dichloroethane	1,1,1 Trichloroethane	Вепгете	Carbon tetrachloride	nichloroethene	-Methyl-2-pentanone (MIBK)	1,1,2 Trichloroethane	obene	etrachloroethene	Chlorobenzene	Ethylbenzene	m+p Xylene	Styrene	Xylene	otal VOCs (ppm)
				ng/kg	ug/kg	ng/kg	ng/kg	ug/kg	ug/kg	ug/kg	ug/kg	Dg/kg	ng/kg	ug/kg	ug/kg	ug/kg								
SB101	1-3	5580	100												UE/AR	- UN-EX	ug/kg 3470	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	mg/kg
SB101	3.5-5.5	1380				\vdash		1140		I							3650	+		730	2540 2900		1950 2800	8.7 ppm
SB102	3.5-5.5	3801	250					9950							3980		1620			1040	4060		1250	11.5 ppm 20.9 ppm
SB102	18.5-20.5	3245	2500					42900			16400			14600			13800	26400			4000		1250	20.9 ppm
SB103	1-3	1041	50					4:000									1.4.4							114.1 ppm 0.0 ppm
SB103	18.5-20.5	592	50	5400	610		2080	24200			8030			7920	1440		14100	49600		3990	17200		5200	139.8 ppm
SB104 SB105	18.5-20.5 8.5-10.5	772 2259	1000 1000			-	2660	51200 4600			17000			7050			20400	13600		2773	13000		5840	130.8 ppm
	18.5-20.5	1269	2500					4600	12500	6400				2500			45000	45000	3600	50600	190000		36000	383.7 2000
SB105 SB106	8.5-10.5°	1012	1000					248000	1200								11100	17200		•				383.7 ppm 40.8 ppm
SB106	18.5-20.5	1833	1000					24000			14300			7610			56300	18200		32900	101000		39900	518.2 ppm
SB107	6-8	2463	250		3600			390000	170000		3900			1300			3700	10000			3200			22.1 ppm
SB107	11-13	1520	250					1870	1300		5000	7900	<u> </u>	580000	9600		620000	600000	8900	250000	710000		200000	22.1 ppm 3555.0 ppm
SBION	3-5'	9922	2500					1870	25000								4700	1300		4000	15000	$\overline{}$	3100	31.3 ppm
SB108 Dup	3.5	9922	2500			+			28000					17000			69000	26000		57000	166000		37000	397.0 ppm
SB108	9-11,	3868	1000						2000					18000			82000	42000		62000	177000		42000	451.0 ppm
SB108	11-13'	5716	1000	14500	4400			27300	11000		28000						5800			3300	20800			29 9 ppm
SB109	13-15	49	50									8100		49000			460000	130000		200000	700000		120000	1752.3 ppm
SB110	7-9	9592	250000	2200	32000		740	17000			1000000	14000								1300				1.3 ppm
SB111	1-3'	9182	5000					1			100000	14000		1200000	4400		870000	3800000	7200	27000	140000		900000	8014 5 ppm
SB111	7-9'	8107	2500		13000					+	38000			35000			190000	69000		52000	160000		35000	541 0 ppm
SB112	9-11'	8524	2500		29000		1	136000			58000	22000		64000		L	120000	84600		17000	56000		_	392.6 ppm
SB112	11-13	9564	2500					45000				. 2200		6900			110000	92000		68000	200000		38000	759.9 ppm
SB113	7-9	3875	1000														13000							58 ∪ ppm
SB113	9-11'	6529	250																	11000	31000			42.0 ppm
SB114	3.5-5.5	904	50									570									2300			2.3 ppm
SB114	8.5-10.5	111	50	T								490				├					550			7.1 ppm
SB115	3.5-5.5	156	50			250		I				- 72									480			1.0 ppm
SB116	6-8"	38	50												260			1200			320			2.0 ppm
SB116	1.3'	459	250	4140					2500															0.0 ppm
SB117	16-18"	238	50		2200	250		I	3900								22000			14000	42000		22000	106.6 ppm
SB118	3.5-5.5	4965	500	10400	2900				I		7500			11000	13000		3100 570000							9.5 ppm
SB118	6-8"	5625	10000			 }	\rightarrow		I					71000			3400000	42000	28000	220000	670000		280000	1854.8 ppm
SB119	3.5-5.5	3294	50000					68500				25000					1300000	290000	46000	680000	2700000		550000	7737.0 ppm
SB119	6-8"	3219	100000		∤			↓		I							4500000		93000	530000	2200000		960000	5176.5 ppm
SB120	11-13'	1243	1000				- +		8000			1					37000			19000	3700000		1500000	10700.0 ppm
SB121	6-8"	1684	1000								I			9400			17000	5100			57000		25000	146 0 ppm
SB121Dup	6-8"	1684	1000											11000			36000	5200		4100	28000		17000	80.6 ppm
SB121 SB122	11-13'	2367	2000				+	21000			18000			54000		+	48000	37000		9800	33000		20000	115.0 ppm
	3-5	1600	1000	16200	7700				33000		34000	1		25000		+	97000	66000	}	23000	15000	\longrightarrow	40000	193.0 ppm
SB123	11-13'	366 512	250	9760	+				16000		2400	3200					260000	9700	3500	110000	83000		48000	4167 ppm
SB124	11-13	214	720	9/00								1800					11000		- 300	5300	250000 17000		120000 6700	791.1 ppm 51.6 ppm

FIELD GC SUMMARY SHEET - Still Bottoms/Treatment Lagoon

ACS NPL SITE Griffith, Indiana

Bonng	Depth	PID Reading	DF	Acetone	1,1 Dichloroethene	trans 1,2 Dichloroethene	1,1 Dichloroethane	2-Butanone (MEK)/cis 1,2-DCE	cis 1,2 Dichloroethene	1,2 Dichloroethane	1,1,1 Trichloroethane	Ветасте	Carbon tetrachloride	Trichloroethene	4-Methyl-2-pentanone (MIBK)	1,1,2 Trichloroethane	Toluene	Tetrachloroethere	Chloroberzene	Ethylbenzene	n+p Xylene	Styrene	o Xylene	Fotal VOCs (ppm)
				ug/kg	ug/kg	Dg/kg	ug/kg	pg/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ng/kg	ug/kg	UR/KR	mg/kg
SB125	3.5-5.5'	2284	2500					170000			21400	20900			24700		853000		46000	457000	1512000		805000	3910.0 ppm
SB125	6-8	2863	5000					210000			22600	24400					1053000			701000	1553000		684000	4248.0 ppm
SB126	3.5-5.5	604	1000														46400			24500	82000		53900	206,8 ppm
SB126	11-13	662	250	31800	28900		7700	66000			76500						12600	3980		5190	30300		6280	269.3 ppm
SB127	8.5-10.5	1086	10000	122000							89500							141200						352.7 ppm
SB128	6-8	2334	10000					367000			54800						11000000			384000	1529000		691700	4126.5 ppm
SB129	11-13	926	1000								I									22700	66000		7100	95.8 ppm
SB130	6-8'	620	1000														13700			13300	00000	97400	207000	331.4 ppm
SB130	16-18	1000	1000					98300			5540				15700		41100				16100	71400	5190	181.9 ppm
SB131	13.5-15.5	140	50														11040				10100			11.0 ppm
SB132	11-13	103	50									402					2380			4780	15900		5730	29.2 ppm
SB133	11-13	306	250				2120	29800								1	8390			1430	6300		5620	53.7 ppm
SB133	16-18	1146	1000					143300							16000		22800			100	13600		4920	200.6 ppm
SB134	19-21	1609	2500				33100	232500			124600			273700	18300		117000	677600		38500	122500		46800	1684.6 ppm
SB135	5-7	70	50														227500	011000			122,00			0.0 ppm
SB135	9-11'	288	250					I									11600			6230	15500		7850	41.2 ppm
SB136	17-19	1012	2500				12600	193000			47900						53900	35500			21600			364.5 ppm
SB138	3.5-5.5	519	500	I				l									2960			3790	20600		13700	41.1 ppm
SB139	16-18	434	50				664	3230									19100			429	1420		788	25.6 ppm
SB140	6-8	10	50																		1-420		/00	0.0 ppm
SB141	3.5-5.5	2348	50														888				347			1.2 ppm
SB142	6-8"	1534	25000		150000			796000		Ŀ	395000					 	987000	99300	 	436000	1710000		595000	5168 3 ppm
SB143	6-8"	1052	10000		297000			591000			4600000		 	450000			846000	2700000		316000	1349000		434000	11583.0 ppm
SB143	8.5-10.5	994	250		1500						7610						1280	2/0000	 	31000			434000	11.9 ppm
SB144	8.5-10.5	1867	500					42900			5800	2590			 	 	22100			10000	1480		16300	141.0 ppm
SB149	8.5-10.5	465	50													 	412		 -	10800	40500		1720	6.1 ppm
SB150	6-8"	1648	50										 			 				812	3140		1720	0.0 ppm
SB151	19-21'	3251	1000	45000	25000								 			 		 	 -		 _			70 0 ppm

This table presents the results of field GC analysis of soil samples collected during the Barrier Wall Pre-design activities at the ACS Site in Griffith, Indiana during January and February 1996.

All samples were considered to be medium level solts due to the high contaminant concentrations and matrix interferences encountered. All results are considered to be estimated concentration.

PID = field PID results were determined using the jar headspace method.

F = Diution factor. Many samples were analyzed at multiple dilutions only the lowest allution factor is presented here. The reporting limit for non-detected compounds is equal to the allution factor times the method detection limit (5 ppb for all compounds except 10 ppb for acetone and MEK).

FIELD GC SUMMARY SHEET - Off-Site Containment Area

ACS NPL SITE Griffith, Indiana

		Reading.		Loetone	Dichloroethene	a 1,2 Dichloroethene	Dichloroethane	uttanone (MEKYcis 1,2-DCE	1,2 Dichloroethene	Dichloroethane	1,1,1 Trichloroethane	ZEJC	Carbon tetrachloride	ichloroethene	Methyl-2-pentanone (MIBK)	1,1,2 Trichloroethane	Ž.	etrachloroethene	Chlorobenzene	benzene	n+p Xylane	9	בווכ	otal VOCs (ppm)
Bonng	Depth	E.	DF			<u> </u>	↓ ː	7.	-8	2	1:	Į.	3	The l	+ W	7	Poluene	₽.	異	Ethylben	Į į	Styrene	o Xylene	ब्रु
CD 2024	127.15.6	├ -	60	ug/kg	ug/kg	og/kg	ug/kg	ng/kg	ug/kg	ng/kg	ng/kg	og/kg	ug/kg	ug/kg	0 2/kg	Dg/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	mg/kg
SB202A SB202A	13.5-15.5° 16-18°	6	50 50				 					330	ļ								2000			2.3 ppm
SB202A SB203	13.5-15.5	42	50			 	 					920												0.9 ppm
SB203	16-18"	37	50			 -	 					1290				ļ				548	2160			2.7 ppm
SB204	13.5-15.5	8	50									120	 	 -						454	1460			3.2 ppm
SB204	16-18"	17	50										├	 		-	<u> </u>				1090			1.1 ppm
SB205	3.5-5.5	592	100	16000	5600			3200	1500	11000		1500		66000	9900000	2400				585	2070			2.7 ppm
SB205	6-8"	1062	500	32200	7360	T		83000		2510				16400	88000000	3400	2600000	128000	2600	6000000	13000000		1800000	111639 ppm
SB205A	8.5-10.5	50	50													 	162000	24200		65600	348000	 	196000	937 ppm
SB205A	23.5-25.5	160	50											 		 	 		 -					0.0 ppm
SB206	5-7	330	50	L		↓	 									 	390				910	├		0.9 ppm
SB206	7-9	192	50			<u> </u>	<u> </u>									1	400			520	2800	— —	290	4.0 ppm
SB207	13.5-15.5	38	50			L	ļ									-				500	2400		300	3.6 ppm
SB207	16-18	84	50	ļ		<u> </u>	ļ									 	<u> </u>			340	760	1		angq 0.0
SB207	21-23	69	50	<u> </u>		├														340	760 1100			1.1 ppm
SB208	11-13	3810	250			├ -											† — — —				1100			1.1 ppm 0 0 ppm
SB208	21 5-25 5	830	50	<u> </u>		 	 									1								0.0 ppm
SB209 SB209	16-18' 18 5-20 5'	149	50			 										1					390			0.4 ppm
SB209 SB210	16-18	150 283	50	 		 							L								2600	 		2.6 ppm
SB210	18.5-20.5	480	50			 	 		 				<u> </u>							1100	4000			5.1 ppm
SB210	18 5-20.5 DUP	480	50			 	 													630	2400			3.0 ppm
SB211	8 5-10 S	60	50	-		 	 						ļ							690	2700			3.4 ppm
SB211	18 5-20 5	233	50			t											320							0.3 ppm
SB212	19-21'	726	200														230				610	1		0.8 ppm
SB212	23-25	1788	50	2600								800		 			810			500	3600		840	6 ppm
SB213	23.5-25.5	106	50	720								200			2100		2600			1400	4700		2100	16 ppm
SB213	26-28	199	50									560												0.9 ppm
SB214	16-18	480	250																	810	3000			4.4 ppm
SB214	21-23'	552	500	I							_					 					2200			2.2 ppm
SB215	17-19	780	2500											 	56500	 					9480			9.5 ppm
SB215	19-21'	897	50	L			-									╆╌╌┤	60200			53500	157300	L	69600	397 ppm
SB216	13.5-15.5	4200	50	<u> </u>		 -	ļ.,	780		I		330		<u> </u>		 	2280				1310	<u> </u>	380	1.7 ppm
SB217	7-9	800	500				 				2710					 	35900	8130		1840	6250		1790	13 ppm
SB217 SB218	13-15	2680	500			 -		21700]					 	14000	8130		16800	78800	 	23000	165 ppm
SB218 SB218	3.5-5.5° 8.5-10.5°	2358 3662	50 50]				 	340		-	4470	18000		6850	65 ppm
SB218 SB219	3 5-5-5	3662 503	250			-	 	6320 7290				368			1380		2340				512	 		0.9 ppm
SB219	8.5-10.5°	388	1000				4290	37200									6980			812	3970		4060	19 ppm
SB220	8.5-10.5°	263	50				7250	31200	 					I	13700		15600							14 ppm
SB220	11-13	1862	250									2950					12284							71 ppm 3.0 ppm
SB221	9-11	3105	1000		25300			32500				7430										 		7.4 ppm
SB221	11-13	1338	250	11800	16800			17100			850	6880					37300			8790	30400	 	11200	7.4 ppm 152 ppm
SB222	13 5-15.5	3015	250					3.1.50		+	- 630	3300					12900			5880	14200	 	6320	89 ppm
SB223	18.5-20.5	51	50								 -	6810 437					26600			6120	19300	1	6460	65 ppm
												43/				<u></u>				555				1.0 ppm

FIELD GC SUMMARY SHEET - Off-Site Containment Area

ACS NPL SITE Griffith, Indiana

This table presents the results of field GC analysis of soil samples collected during the Barrier Wall Pre-design activities at the ACS Site in Griffith, Indiana during January and February 1996.

All samples were considered to be medium level soils due to the high contaminant concentrations and matrix interferences encountered. All results are considered to be estimated concentration.

PID = field PID results were determined using the jar headspace method.

DF = Dilution tactor. Many samples were analyzed at multiple dilutions; only the lowest dilution factor is presented here. The reporting limit for non-detected compounds is equal to the dilution factor times the method detection limit (5 ppb for all compounds except 10 ppb for acetone and MEK).

E

IEA ANALYTICAL LABORATORY RESULTS

IEA, Inc

IEA Project NO.: 1589_126D

SDG: 01511

Client Project ID: 4077.0075

Data Summary Package

IEA

SDG NARRATIVE VOLATILE FRACTION

PROJECT: 1589-126 BATCH: 01511 METHOD: 1/91 SOW

SAMPLES: Three (3) Soil Samples

These samples were received at Industrial and Environmental Analysts, Inc. (IEA) on January 25 and February 01, 1996. Each sample was assigned a 9-character "IEA" lab identification number (lab ID) and an abbreviated client ID for simplicity in forms generation. This package makes reference to these ID's as listed on the IEA Assigned Number Index. In addition the pH for the water samples are listed on this index. All analyses were performed according to the EPA 1/91 SOW and meet the requirements of the IEA Quality Assurance Program. Please see the enclosed data package for your results and Chain of Custody (COC) documentation.

There is an air peak that is common to all of the volatile analyses and a solvent peak that is common to some volatile analyses. These peaks are present at the beginning of the Reconstructed Ion Chromatograms (RIC) and are labeled. These peaks are not searched as Tentatively Identified Compounds (TIC's).

The chromatographic separation of the analytes is performed using a J & W Scientific 75 m X 0.53 mm DB-624 fused silica capillary column with a 3.0 μ m film thickness.

The trap used in the purge-and-trap apparatus is a Supelco trap K (VOCARB 3000) consisting of 10 cm of Carbopack B, 6 cm of Carboxen 1000, and 1 cm of Carboxen 1001. This trap meets the criteria in the SOW for contract OLM03.1 for an equivalent trap. Documentation is maintained within the QA department for on-site review.

The "J" flag used on the Form I VOA indicates an estimated concentration between the Contract Required Quantitation Limit (CRQL) and the Method Detection Limit (MDL), not accounting for dilution of the sample prior to analysis. This flag is also used on the Form I VOA-TIC to indicate an estimated amount for all non-target concentrations.

The "M" flag used on the data system report form designates that a manual integration was required to provide an accurate quantification of that analyte. Manual integrations have been initialled and dated by the analyst.

The "Y" flag is used as a qualifier on the Form I VOA-TIC to indicate a siloxane contaminant attributed to trap breakdown.

The "N" flag used on the Form I VOA-TIC indicates that there is the presumptive evidence of a compound based on the mass spectral library search and the interpretation of the mass spectral interpretation specialist.

The "D" flag is used on the surrogate and spike recoveries to designate they were diluted out.

SDG NARRATIVE VOLATILE FRACTION

The following nonconformances associated with the analysis of the samples in this case are as follows:

Sample number 04 (client ID ACS-SB118SS3-6'-8') was used for the medium level soil matrix spike/matrix spike duplicate (MS/MSD). Due to the high dilution factor most of the spike compounds did not recover. This is designated with the "D" flag on the percent recoveries.

I certify that this data package is in compliance with the terms and conditions of the contract, both technically and for completeness, for other than the conditions detailed above. Release of the data contained in this hardcopy data package and in the computer-readable data submitted on diskette has been authorized by the laboratory manager or his designee, as verified by the following signature.

Brian D. Neptune

Lead Analyst, GC/MS Final Review

Brian 1). leptur 03/05/96

IEA, Inc.

IEA

IEA

SDG NARRATIVE PESTICIDE FRACTION

CASE: 1589-126

SDG NO.:01511

CONTRACT: SOW 1/91

Samples: (8) Soil Samples

This case was closed on February 1, 1996. Each sample has been assigned a 9-character IEA lab identification number.

The chromatographic separation of the analytes was performed using a J & W 30 m X 0.53 mm DB-1701 fused silica capillary column with a 1.0 µm bonded phase film thickness and a Restek 30 m X 0.53 mm Rt_x-35 fused silica capillary column with a 1.0 μ m bonded phase film thickness. The Rt_x-35 column used as one of the analytical columns is equivalent to the DB-608 column specified in the SOW.

The filenames have an extension of ".D" to denote the use of the ASCII file generated by the data system to produce the forms. Two significant figures were reported for the "calculated amount" on Form VII PEST-1 and -2. All of the initial pesticide chromatograms were missing the scaling factor; however, the scaling factor (in mV scale) appeared for the re-plotted chromatograms.

Gel Permeation Cleanup (GPC) was performed using a column series: a 19 X 300 mm Waters UltraStyragel column paired with a 19 X 150 mm Waters UltraStyragel column. The additional column provides the additional resolution needed to achieve the criteria for pesticide analysis. This column combination meets the equivalency criteria in paragraph 10.1.8.1.2, page D-43/PEST. A 2 mL injection loop is utilized by the GPC system.

All soil sample extracts underwent GPC as required by the SOW. Florisil column cleanup was performed on all sample extracts as required by the SOW.

The "P" flag is used to designate that there is a greater than 25% difference in the detected concentration of an analyte between the two analytical columns.

The "J" flag is used to designate target compounds reported below the quantitation limits.

The "*" used on the Form III PEST designates percent recoveries and/or RPD's are outside the OC limits.

The "D" flag indicates a target compound that is reported in the more dilute analysis.

Any nonconformances associated with the analysis of the samples in this case are note as follows:

The Matrix Spike/Matrix Spike Duplicate had zero (0) percent recovery due to sample dilution.

The aroclor 1254 present in the samples had high percent differences on the RTX-35 column due to overlapping of the arochlor 1248 pattern.

All samples were analyzed at dilutions due to target compounds that exceeded the calibration range. The surrogate recoveries were below the advisory limits due to dilutions and sample matrix interference.

I certify that this data package is in compliance with the terms and conditions of the contract, both technically and for completeness, for other than the conditions detailed above. Release of the data contained in this hardcopy data package and in the computer-readable data submitted on diskette has been authorized by the laboratory manager or his designee, as verified by the following signature.

Dwight A. Dingess 03/07/96

GC SV Lead Analyst

IEA, Inc.

	,						,			SPECIAL INSTRUCTIO	- ONS:	TUR;	IAROUND
_	((PECFA		_	KS (standard)
MONTGOMERY WATSON	CHAIN OF CI	ica			n=/	\				WI LUST		☐1 WEEK	
	CHAIN OF C	J 2	ıOl	JY	KE	JOH	(D			REPORT DRY	wt	1 DAY	
		1								☐OTHER:			
SAMPLER(S) A. P. S. C. STATE: INDIANA SAMPLER(S) A. P. S. C.	77.0075 -	OF CONTAIN	9 Sugar				//	//				LAB USE	ONLY
COLLECTION COLLECTION CARABI SAM	MPLE ID	2			/ /			/ /	/ /	/ REMARKS	MAT	RIX	LAB NO.
1-22-96 1300 X ACS-SB11055	4-7-9')		X					N.	# 9-29814			
1-2396 0845 × 19CS SB112 55	5-9-11		X						7	14×9-29813			
1-23.46 1345 XACS-SB113S	54-79		X						77	2 9-24815			
		 											
		 	1										
		 											
		⊩_	-	\vdash									
		 	\vdash				\vdash						
			-				1-1		-				
		 	+	-	\dashv	+			_		_		
SPECIAL INSTRUCTIONS:		<u></u>	<u>ا</u>			<u> </u>			472	PROLMGR	ــــــــــــــــــــــــــــــــــــ		
of Dao Level 3 paralysis	RECEIVED:					TEMP	<u>-</u>	9	ا ^ا ح	PROJUGA:	e VAST	-	
- P Da c ceour > //www.	TEDEN# 36	09:	25 5	620 4	70					708-	-691-	5020	
	Cocsos	" 3 (72 c	000 7	9								
SIGNATURE	PRINT NAM	NE			<u> </u>			CC	MPAN	IY / TITLE		DATE	TIME
RELINQUISHED BY: Jedl. Pag	DAVIDA. Pia	1240	494		mor	1410	214	WAT	22	/ Hy proged	25 is 24	1-24-96	
RECEIVED BY: 71 MAIN	1 .1 /	_	12 5 1	1						Dr.	//-/-		0940
RELINQUISHED BY:		,										1-11/1	1
RECEIVED BY									•				
C-O-C No.	1589-12	GD							 	NAME OF COURIER:			

	MONTGOMERY	WATSON
--	------------	--------

SPECIAL INSTRUCTIONS:	TURNAROUND
PECFA	EKS (standard
WILUST	☐1 WEEK
ACT 307	☐3 DAYS
REPORT DRY WT	1 DAY
Toruce	

	CHAIN OF CUSTODY F	RECORD		∐3 DAYS ☐1 DAY
SAMPLER(S) COLLECTION COLLECTION GRAB/ DATE STATE: STATE: SAMPLER(S) COLLECTION GRAB/ COMP SAMI	NO. OF CONTAINERS		TAG TES	LAB USE ONLY IX LAB NO
1-24-96 1600 Grab ACS-SB18 SS 1-25-96 0915 ACS-SB19SS 1-26-96 1035 ACS-SB124S 1-30-96 0900 ACS-SB127S 1-30-96 1100 ACS-SB128S 1-30-96 1430 ACS-SB129S 1-30-96 1100 Gud- ACS-SB128SS3-6 1-30-96 1430 Grd- ACS-SB129SSS	53-6'-8' SS4-85'-105 X SS3-6'-8' SS3-6'-8' SS5-11'-13' 6 135-15.5' 28' DUP	9-30 9-30 9-30 9-30 9-30 9-3	014/	
SPECIAL INSTRUCTIONS: COC Seal #3: 92-0008 CLP TCL POBS SIGNATURE RELINQUISHED BY RECEIVED BY: DUTC CONTROL SPECIAL INSTRUCTIONS: COC Seal #3: 92-0008	PRINT NAME	DAVE PIECZYNSKI CALL COMPANY/THE MAGORING LYMSON/ TEA Sample Mine	Hydrogralogisx 1	DATE TIME 131/96 1730
RELINQUISHED BY: RECEIVED BY: C-O-C No. : / {				

1589-126)

NAME OF COURIER: FEXC X
AIRBILL NUMBER: 3609254994

Will be come

VOLATILE ORGANICS ANALYSIS DATA SHEET

CLIENT SAMPLE NO.

ACS-SB110SS4-7'-9'

Lab Name: IEA-NC

Method: SOW 1/91

کد Code: IEA

Case No.: 1589-126

SDG No.: 01511

fatrix: (soil/water) SOIL

Lab Sample ID: 960151101

Sample wt/vol: 4 (g/mL) g

Lab File ID: 0130E07.D

Level: (low/med) MED

Date Received: 01/25/96

k Moisture: not dec. 15

Date Analyzed: 01/30/96

C Column: DB-624 ID: .53(mm) Dilution Factor: 400.0

Soil Extract Volume: 10000(uL)

Soil Aliquot Volume: 100(uL)

CONCENTRATION UNITS:

COMPOUND (ug/L or ug/Kg)	ug/kg	Q
Chloromethane	560000	U
<u> </u>		Ű
		
		Ū
		U
Acetone	560000	U
Carbon Disulfide	560000	U
1,1-Dichloroethene	560000	Ū
1,1-Dichloroethane	560000	U
1,2-Dichloroethene (total)	240000	J
Chloroform	560000	U
1,2-Dichloroethane	560000	U
2-Butanone	560000	Ū
1,1,1-Trichloroethane	2200000	
Carbon Tetrachloride	560000	Ü
Bromodichloromethane	560000	U
1,2-Dichloropropane	560000	U
cis-1,3-Dichloropropene	560000	U
Trichloroethene	2800000	
	560000	Ū
1,1,2-Trichloroethane	560000	Ü
Benzene	150000	J
Trans-1,3-Dichloropropene	560000	U
Bromoform	560000	U
	560000	U
	560000	U
Tetrachloroethene	8300000	
Toluene	2600000	
1,1,2,2-Tetrachloroethane	560000	Ü
Chlorobenzene	560000	Ü
Ethylbenzene	930000	
Styrene	560000	Ū
Xylene (total)	4600000	
	Chloromethane Bromomethane Vinyl Chloride Chlorcethane Methylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethene 1,1-Dichloroethane 1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene Trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene Toluene 1,1,2-Tetrachloroethane Chlorobenzene Ethylbenzene Styrene	Chloromethane 560000 Bromomethane 560000 Vinyl Chloride 560000 Chlorcethane 560000 Methylene Chloride 560000 Acetone 560000 Carbon Disulfide 560000 1,1-Dichloroethene 560000 1,2-Dichloroethane 560000 1,2-Dichloroethane 560000 1,2-Dichloroethane 560000 2-Butanone 560000 1,1,1-Trichloroethane 2200000 Carbon Tetrachloride 560000 Bromodichloromethane 560000 1,2-Dichloropropane 560000 Cis-1,3-Dichloropropene 560000 Trichloroethane 2800000 Dibromochloromethane 560000 1,1,2-Trichloroethane 560000 Benzene 150000 Bromoform 560000 4-Methyl-2-Pentanone 560000 2-Hexanone 560000 Tetrachloroethene 8300000 Toluene 2600000 1,1,2,2-Tetrachloroethane

1E

CLIENT SAMPLE NO.

VOLATILE ORGANICS ANALYSIS DATA SHEET TENTATIVELY IDENTIFIED COMPOUNDS

ACS-SB110SS4-7'-9'

Lab Name: IEA-NC

Method: SOW 1/91

L Code: IEA Case No.: 1589-126 SDG No.: 01511

Matrix: (soil/water) SOIL Lab Sample ID: 960151101

Sample wt/vol: 4 (g/mL) g Lab File ID: 0130E07.D

Level: (low/med) MED Date Received: 01/25/96

% Moisture: not dec. 15
Date Analyzed: 01/30/96

GC Column: DB-624 ID: .53(mm) Dilution Factor: 400.0

Soil Extract Volume: 10000(uL) Soil Aliquot Volume: 100(uL)

CONCENTRATION UNITS: (ug/L or ug/Kg) ug/kg

Number TICs Found: 10

		7=== ===	r	
CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
000111-65-9	OCTANE	16.01	570000	JN
	Unknown Alkane	18.27	360000	J
	Substituted Benzene	22.25	530000	J
	Unknown Alkane	22.52	780000	J
	Substituted Benzene	23.32	1200000	J
-	Substituted Benzene	27.06	310000	J
J <mark>0091-20-3</mark>	NAPHTHALENE	28.07	340000	JN
	Substituted Naphthalene	30.15	570000	J
	Substituted Naphthalene	30.55	440000	J
	Dimethyl Naphthalene Isomer	33.07	310000	J
				
				
		 		
				
		 		
		 		
		 		
				
		 		
		 		
				
		ļ		
	<u> </u>	1	ll	

1A VOLATILE ORGANICS ANALYSIS DATA SHEET

ACS-SB118SS3-6'-8'

Lab Name: IEA-NC

Method: SOW 1/91

La Jode: IEA

Case No.: 1589-126

SDG No.: 01511

Matrix: (soil/water) SOIL

Lab Sample ID: 960212404

Sample wt/vol: 4 (q/mL) q

Lab File ID: 0210E07.D

Level: (low/med) MED

Date Received: 02/01/96

t Moisture: not dec. 13

CAS NO. COMPOUND

Date Analyzed: 02/10/96

GC Column: DB-624

ID: .53(mm)

Dilution Factor: 200.0

30il Extract Volume: 10000(uL)

Soil Aliquot Volume: 100(uL)

ug/kg

CONCENTRATION UNITS:

(ug/L or ug/Kg)

74-87-3	Chloromethane	280000	บ
74-83-9	Bromomethane	280000	Ü
75-01-4	Vinyl Chloride	280000	Ü
75-00-3	Chloroethane	280000	Ü
75-09-2	Methylene Chloride	280000	Ū
-64-1	Acetone	230000	J
15-0	Carbon Disulfide	280000	Ū
75-35-4	1,1-Dichloroethene	280000	-0
75-34-3	1,1-Dichloroethane	280000	U
540-59-0	1,2-Dichloroethene (total)	280000	Ū
67-66-3	Chloroform	280000	Ū
107-06-2	1,2-Dichloroethane	280000	Ū
78-93-3	2-Butanone	280000	U
71 55-6	1,1,1-Trichloroethane	280000	Ū
5 23-5	Carbon Tetrachloride	280000	U
75-27-4	Bromodichloromethane	280000	U
78-87-5	1,2-Dichloropropane	280000	Ū
10061-01-5	cis-1,3-Dichloropropene	280000	U
79-01-6	Trichloroethene	80000	J
124-48-1	Dibromochloromethane	280000	Ū
79-00-5	1,1,2-Trichloroethane	280000	U
71-43-2	Benzene	280000	U
10061-02-6	Trans-1,3-Dichloropropene	280000	Ü
75-25-2	Bromoform	280000	U
108-10-1	4-Methyl-2-Pentanone	280000	Ū
591-78-6	2-Hexanone	280000	U
127-18-4	Tetrachloroethene	360000	
108-88-3	Toluene	3800000	
79-34-5	1,1,2,2-Tetrachloroethane	280000	U
108-90-7	Chlorobenzene	280000	Ü
100-41-4	Ethylbenzene	1000000	
100-42-5	Styrene	280000	Ū
1330-20-7	Xylene (total)	4500000	

1A

VOLATILE ORGANICS ANALYSIS DATA SHEET

CLIENT SAMPLE NO.

ACS-SB118SS3-6'-8'

Lab Name: IEA-NC Method: SOW 1/91

Land Code: IEA Case No.: 1589-126 SDG No.: 01511

Matrix: (soil/water) SOIL Lab Sample ID: 960212404

Sample wt/vol: 4 (g/mL) g Lab File ID: 0210E07.D

Level: (low/med) MED Date Received: 02/01/96

% Moisture: not dec. 13
Date Analyzed: 02/10/96

GC Column: DB-624 ID: .53(mm) Dilution Factor: 200.0

Soil Extract Volume: 10000(uL) Soil Aliquot Volume: 100(uL)

CONCENTRATION UNITS:

74-87-3 Chloromethane 280000 U 74-83-9 Bromomethane 280000 U 75-01-4 Vinyl Chloride 280000 U 75-00-3 Chloroethane 280000 U 75-09-2 Methylene Chloride 280000 U ~64-1 Acetone 130000 J -15-0 Carbon Disulfide 280000 U 75-35-4 1,1-Dichloroethene 280000 U 75-35-3 1,1-Dichloroethane 280000 U 540-59-0 1,2-Dichloroethane 280000 U 67-66-3 Chloroform 280000 U 107-06-2 1,2-Dichloroethane 280000 U 78-93-3 2-Butanone 53000 J 71-55-6 1,1,1-Trichloroethane 38000 J 75-27-4 Bromodichloromethane 280000 U 78-87-5 1,2-Dichloropropane 280000 U 79-01-6 Trichloroethane 280000 U	CAS NO.	COMPOUND (ug/L or ug/Kg	ı) ug/kg	Q
74-83-9 Bromomethane 280000 U 75-01-4 Vinyl Chloride 280000 U 75-01-4 Vinyl Chloride 280000 U 75-09-2 Chloroethane 280000 U 75-09-2 Methylene Chloride 280000 U 76-41 Acetone 130000 U 75-35-4 1,1-Dichloroethene 280000 U 75-35-4 1,1-Dichloroethene 280000 U 75-34-3 1,1-Dichloroethane 280000 U 76-66-3 Chloroform 280000 U 76-66-3 Chloroform 280000 U 77-55-6 1,1-Trichloroethane 280000 U 77-55-6 1,1-Trichloroethane 38000 U 75-27-4 Bromodichloromethane 38000 U 75-27-4 Bromodichloromethane 280000 U 78-87-5 1,2-Dichloropropane 280000 U 79-01-6 Trichloroethane 280000 U 77-527-4 Bromodichloromethane 280000 U 77-527-4 Trichloroethane 280000 U 77-527-4 Trichloroethane 280000 U 77-527-4 Trichloroethane 280000 U 77-527-4 Trichloroethane 280000 U 77-527-5 Bromoform 280000 U 77-527-6 Bromoform 280000 U 77-527-7 Bromoform 280000 U 77-78-6 2-Hexanone 380000 U 77-78-78-6 2-Hexanone 380000 U 77-78-78-78-78-78-78-78-78-78-78-78-78-7				
75-01-4				
75-00-3			1	•
75-09-2 Methylene Chloride 280000 U 7-64-1 Acetone 130000 J 5-15-0 Carbon Disulfide 280000 U 75-35-4 1,1-Dichloroethene 280000 U 75-34-3 1,1-Dichloroethane 280000 U 540-59-0 1,2-Dichloroethene (total) 280000 U 107-66-3 Chloroform 280000 U 107-66-2 1,2-Dichloroethane 280000 U 78-93-3 2-Butanone 38000 J 71-55-6 1,1,1-Trichloroethane 38000 J 75-27-4 Bromodichloromethane 280000 U 78-87-5 1,2-Dichloropropane 280000 U 10061-01-5 cis-1,3-Dichloropropene 280000 U 79-01-6 Trichloroethene 280000 U 124-48-1 Dibromochloromethane 280000 U 79-00-5 1,1,2-Trichloroethane 280000 U 70-25-2 Bromoform 280000 </td <td></td> <td></td> <td></td> <td></td>				
Televiside				
5-15-0 Carbon Disulfide 280000 U 75-35-4 1,1-Dichloroethene 280000 U 75-34-3 1,1-Dichloroethane 280000 U 540-59-0 1,2-Dichloroethene (total) 280000 U 67-66-3 Chloroform 280000 U 107-06-2 1,2-Dichloroethane 38000 U 78-93-3 2-Butanone 53000 J 71-55-6 1,1,1-Trichloroethane 38000 J 56-23-5 Carbon Tetrachloride 280000 U 75-27-4 Bromodichloromethane 280000 U 78-87-5 1,2-Dichloropropane 280000 U 79-01-6 Trichloroethene 80000 U 79-01-6 Trichloroethene 80000 U 79-00-5 1,1,2-Trichloroethane 43000 U 70-05-5 1,1,2-Trichloroethane 280000 U 1061-02-6 Trans-1,3-Dichloropropene 280000 U 75-25-2 Bromoform 2				
75-35-4 1,1-Dichloroethane 280000 U 75-34-3 1,1-Dichloroethane 280000 U 540-59-0 1,2-Dichloroethene (total) 280000 U 107-66-3 Chloroform 280000 U 107-06-2 1,2-Dichloroethane 280000 U 78-93-3 2-Butanone 53000 J 71-55-6 1,1,1-Trichloroethane 38000 J 56-23-5 Carbon Tetrachloride 280000 U 75-27-4 Bromodichloromethane 280000 U 78-87-5 1,2-Dichloropropane 280000 U 1061-01-5 cis-1,3-Dichloropropene 280000 U 79-01-6 Trichloroethane 80000 J 124-48-1 Dibromochloromethane 280000 U 79-02-5 1,1,2-Trichloroethane 280000 U 75-25-2 Bromoform 280000 U 108-10-1 4-Methyl-2-Pentanone 280000 U 108-80-3 Toluene				
75-34-3 1,1-Dichloroethane 280000 U 540-59-0 1,2-Dichloroethene (total) 280000 U 67-66-3 Chloroform 280000 U 107-06-2 1,2-Dichloroethane 280000 U 78-93-3 2-Butanone 53000 J 71-55-6 1,1,1-Trichloroethane 38000 J 56-23-5 Carbon Tetrachloride 280000 U 75-27-4 Bromodichloromethane 280000 U 78-87-5 1,2-Dichloropropane 280000 U 1061-01-5 cis-1,3-Dichloropropane 280000 U 79-01-6 Trichloroethene 80000 U 124-48-1 Dibromochloromethane 280000 U 79-00-5 1,1,2-Trichloroethane 43000 J 71-43-2 Benzene 280000 U 1061-02-6 Trans-1,3-Dichloropropene 280000 U 75-25-2 Bromoform 280000 U 108-10-1 4-Methyl-2-Pentanone				
540-59-0 1,2-Dichloroethene (total) 280000 U 67-66-3 Chloroform 280000 U 107-06-2 1,2-Dichloroethane 280000 U 78-93-3 2-Butanone 53000 J 71-55-6 1,1-Trichloroethane 38000 J 56-23-5 Carbon Tetrachloride 280000 U 75-27-4 Bromodichloromethane 280000 U 78-87-5 1,2-Dichloropropane 280000 U 10061-01-5 cis-1,3-Dichloropropene 280000 U 79-01-6 Trichloroethene 80000 J 124-48-1 Dibromochloromethane 280000 U 79-00-5 1,1,2-Trichloroethane 43000 J 71-43-2 Benzene 280000 U 1061-02-6 Trans-1,3-Dichloropropene 280000 U 75-25-2 Bromoform 280000 U 108-10-1 4-Methyl-2-Pentanone 280000 U 591-78-6 2-Hexanone 90				
67-66-3 Chloroform 280000 U 107-06-2 1,2-Dichloroethane 280000 U 78-93-3 2-Butanone 53000 J 71-55-6 1,1,1-Trichloroethane 38000 J 56-23-5 Carbon Tetrachloride 280000 U 75-27-4 Bromodichloromethane 280000 U 78-87-5 1,2-Dichloropropane 280000 U 1061-01-5 cis-1,3-Dichloropropene 280000 U 79-01-6 Trichloroethane 80000 J 124-48-1 Dibromochloromethane 280000 U 79-00-5 1,1,2-Trichloroethane 43000 J 71-43-2 Benzene 280000 U 1061-02-6 Trans-1,3-Dichloropropene 280000 U 75-25-2 Bromoform 280000 U 108-10-1 4-Methyl-2-Pentanone 280000 U 591-78-6 2-Hexanone 380000 U 108-88-3 Toluene 380000				
107-06-2 1,2-Dichloroethane 280000 U 78-93-3 2-Butanone 53000 J 71-55-6 1,1,1-Trichloroethane 38000 J 56-23-5 Carbon Tetrachloride 280000 U 75-27-4 Bromodichloromethane 280000 U 78-87-5 1,2-Dichloropropane 280000 U 10061-01-5 cis-1,3-Dichloropropene 280000 U 79-01-6 Trichloroethene 80000 J 124-48-1 Dibromochloromethane 280000 U 79-00-5 1,1,2-Trichloroethane 43000 J 71-43-2 Benzene 280000 U 10061-02-6 Trans-1,3-Dichloropropene 280000 U 75-25-2 Bromoform 280000 U 108-10-1 4-Methyl-2-Pentanone 360000 U 127-18-4 Tetrachloroethene 360000 U 108-88-3 Toluene 3800000 U 79-34-5 1,1,2,2-Tetrachloroethane		1,2-Dichloroethene (total)		
78-93-3 2-Butanone 53000 J 71-55-6 1,1,1-Trichloroethane 38000 J 56-23-5 Carbon Tetrachloride 280000 U 75-27-4 Bromodichloromethane 280000 U 78-87-5 1,2-Dichloropropane 280000 U 10061-01-5 Cis-1,3-Dichloropropene 280000 U 79-01-6 Trichloroethene 80000 J 124-48-1 Dibromochloromethane 280000 U 79-00-5 1,1,2-Trichloroethane 43000 J 71-43-2 Benzene 280000 U 10061-02-6 Trans-1,3-Dichloropropene 280000 U 75-25-2 Bromoform 280000 U 108-10-1 4-Methyl-2-Pentanone 280000 U 591-78-6 2-Hexanone 90000 J 127-18-4 Tetrachloroethene 3800000 108-88-3 Toluene 3800000 79-34-5 1,1,2,2-Tetrachloroethane 280000 U	67- 66-3			
71-55-6 1,1,1-Trichloroethane 38000 J 56-23-5 Carbon Tetrachloride 280000 U 75-27-4 Bromodichloromethane 280000 U 78-87-5 1,2-Dichloropropane 280000 U 10061-01-5 Cis-1,3-Dichloropropene 280000 U 79-01-6 Trichloroethene 80000 U 124-48-1 Dibromochloromethane 280000 U 79-00-5 1,1,2-Trichloroethane 43000 J 71-43-2 Benzene 280000 U 10061-02-6 Trans-1,3-Dichloropropene 280000 U 75-25-2 Bromoform 280000 U 108-10-1 4-Methyl-2-Pentanone 280000 U 591-78-6 2-Hexanone 90000 J 127-18-4 Tetrachloroethene 380000 U 108-88-3 Toluene 380000 U 79-34-5 1,1,2,2-Tetrachloroethane 280000 U 108-90-7 Chlorobenzene 280000 U 100-41-4 Ethylbenzene 34000	107-06-2	1,2-Dichloroethane		
56-23-5 Carbon Tetrachloride 280000 U 75-27-4 Bromodichloromethane 280000 U 78-87-5 1,2-Dichloropropane 280000 U 10061-01-5 cis-1,3-Dichloropropene 280000 U 79-01-6 Trichloroethene 80000 J 124-48-1 Dibromochloromethane 280000 U 79-00-5 1,1,2-Trichloroethane 43000 J 71-43-2 Benzene 280000 U 10061-02-6 Trans-1,3-Dichloropropene 280000 U 75-25-2 Bromoform 280000 U 108-10-1 4-Methyl-2-Pentanone 280000 U 591-78-6 2-Hexanone 90000 J 108-88-3 Toluene 360000 U 79-34-5 1,1,2,2-Tetrachloroethane 280000 U 108-90-7 Chlorobenzene 280000 U 100-41-4 Ethylbenzene 34000 J	78-93-3	2-Butanone	53000	J
75-27-4 Bromodichloromethane 280000 U 78-87-5 1,2-Dichloropropane 280000 U 10061-01-5 cis-1,3-Dichloropropene 280000 U 79-01-6 Trichloroethene 80000 J 124-48-1 Dibromochloromethane 280000 U 79-00-5 1,1,2-Trichloroethane 43000 J 71-43-2 Benzene 280000 U 10061-02-6 Trans-1,3-Dichloropropene 280000 U 75-25-2 Bromoform 280000 U 108-10-1 4-Methyl-2-Pentanone 280000 U 591-78-6 2-Hexanone 90000 J 127-18-4 Tetrachloroethene 360000 U 108-88-3 Toluene 380000 U 79-34-5 1,1,2,2-Tetrachloroethane 280000 U 108-90-7 Chlorobenzene 280000 U 100-41-4 Ethylbenzene 1000000 100-42-5 Styrene 34000 J	71-55-6	1,1,1-Trichloroethane	38000	J
78-87-5 1,2-Dichloropropane 280000 U 10061-01-5 cis-1,3-Dichloropropene 280000 U 79-01-6 Trichloroethene 80000 J 124-48-1 Dibromochloromethane 280000 U 79-00-5 1,1,2-Trichloroethane 43000 J 71-43-2 Benzene 280000 U 10061-02-6 Trans-1,3-Dichloropropene 280000 U 75-25-2 Bromoform 280000 U 108-10-1 4-Methyl-2-Pentanone 280000 U 591-78-6 2-Hexanone 90000 J 127-18-4 Tetrachloroethene 360000 U 108-88-3 Toluene 3800000 U 79-34-5 1,1,2,2-Tetrachloroethane 280000 U 108-90-7 Chlorobenzene 280000 U 100-41-4 Ethylbenzene 1000000 100-42-5 Styrene 34000 J	56-23-5	Carbon Tetrachloride	280000	Ū
10061-01-5 cis-1,3-Dichloropropene 280000 U 79-01-6 Trichloroethene 80000 J 124-48-1 Dibromochloromethane 280000 U 79-00-5 1,1,2-Trichloroethane 43000 J 71-43-2 Benzene 280000 U 10061-02-6 Trans-1,3-Dichloropropene 280000 U 75-25-2 Bromoform 280000 U 108-10-1 4-Methyl-2-Pentanone 280000 U 591-78-6 2-Hexanone 90000 J 127-18-4 Tetrachloroethene 360000 U 108-88-3 Toluene 3800000 U 79-34-5 1,1,2,2-Tetrachloroethane 280000 U 108-90-7 Chlorobenzene 280000 U 100-41-4 Ethylbenzene 1000000 100-42-5 Styrene 34000 J	75-27-4	Bromodichloromethane	280000	Ū
10061-01-5 cis-1,3-Dichloropropene 280000 U 79-01-6 Trichloroethene 80000 J 124-48-1 Dibromochloromethane 280000 U 79-00-5 1,1,2-Trichloroethane 43000 J 71-43-2 Benzene 280000 U 10061-02-6 Trans-1,3-Dichloropropene 280000 U 75-25-2 Bromoform 280000 U 108-10-1 4-Methyl-2-Pentanone 280000 U 591-78-6 2-Hexanone 90000 J 127-18-4 Tetrachloroethene 360000 U 108-88-3 Toluene 3800000 U 79-34-5 1,1,2,2-Tetrachloroethane 280000 U 108-90-7 Chlorobenzene 280000 U 100-41-4 Ethylbenzene 1000000 100-42-5 Styrene 34000 J	78- 87-5	1,2-Dichloropropane	280000	Ū
79-01-6 Trichloroethene 80000 J 124-48-1 Dibromochloromethane 280000 U 79-00-5 1,1,2-Trichloroethane 43000 J 71-43-2 Benzene 280000 U 10061-02-6 Trans-1,3-Dichloropropene 280000 U 75-25-2 Bromoform 280000 U 108-10-1 4-Methyl-2-Pentanone 280000 U 591-78-6 2-Hexanone 90000 J 127-18-4 Tetrachloroethene 360000 U 108-88-3 Toluene 3800000 U 79-34-5 1,1,2,2-Tetrachloroethane 280000 U 108-90-7 Chlorobenzene 280000 U 100-41-4 Ethylbenzene 1000000 100-42-5 Styrene 34000 J	10061-01-5		280000	U
79-00-5 1,1,2-Trichloroethane 43000 J 71-43-2 Benzene 280000 U 10061-02-6 Trans-1,3-Dichloropropene 280000 U 75-25-2 Bromoform 280000 U 108-10-1 4-Methyl-2-Pentanone 280000 U 591-78-6 2-Hexanone 90000 J 127-18-4 Tetrachloroethene 360000 U 108-88-3 Toluene 3800000 U 79-34-5 1,1,2,2-Tetrachloroethane 280000 U 108-90-7 Chlorobenzene 280000 U 100-41-4 Ethylbenzene 1000000 100-42-5 Styrene 34000 J	79-01-6	Trichloroethene	80000	J
71-43-2 Benzene 280000 U 10061-02-6 Trans-1,3-Dichloropropene 280000 U 75-25-2 Bromoform 280000 U 108-10-1 4-Methyl-2-Pentanone 280000 U 591-78-6 2-Hexanone 90000 J 127-18-4 Tetrachloroethene 360000 108-88-3 Toluene 3800000 79-34-5 1,1,2,2-Tetrachloroethane 280000 U 108-90-7 Chlorobenzene 280000 U 100-41-4 Ethylbenzene 1000000 100-42-5 Styrene 34000 J	124-48-1	Dibromochloromethane	280000	
10061-02-6 Trans-1,3-Dichloropropene 280000 U 75-25-2 Bromoform 280000 U 108-10-1 4-Methyl-2-Pentanone 280000 U 591-78-6 2-Hexanone 90000 J 127-18-4 Tetrachloroethene 360000 108-88-3 Toluene 3800000 79-34-5 1,1,2,2-Tetrachloroethane 280000 U 108-90-7 Chlorobenzene 280000 U 100-41-4 Ethylbenzene 1000000 100-42-5 Styrene 34000 J	79-00-5	1,1,2-Trichloroethane	43000	J
75-25-2 Bromoform 280000 U 108-10-1 4-Methyl-2-Pentanone 280000 U 591-78-6 2-Hexanone 90000 J 127-18-4 Tetrachloroethene 360000 108-88-3 Toluene 3800000 79-34-5 1,1,2,2-Tetrachloroethane 280000 U 108-90-7 Chlorobenzene 280000 U 100-41-4 Ethylbenzene 1000000 100-42-5 Styrene 34000 J	71-43-2	Benzene	280000	Ū
108-10-1 4-Methyl-2-Pentanone 280000 U 591-78-6 2-Hexanone 90000 J 127-18-4 Tetrachloroethene 360000 108-88-3 Toluene 3800000 79-34-5 1,1,2,2-Tetrachloroethane 280000 108-90-7 Chlorobenzene 280000 100-41-4 Ethylbenzene 1000000 100-42-5 Styrene 34000	10061-02-6	Trans-1,3-Dichloropropene	280000	Ū
591-78-6 2-Hexanone 90000 J 127-18-4 Tetrachloroethene 360000 108-88-3 Toluene 3800000 79-34-5 1,1,2,2-Tetrachloroethane 280000 108-90-7 Chlorobenzene 280000 100-41-4 Ethylbenzene 1000000 100-42-5 Styrene 34000	75-25-2	Bromoform	280000	Ū
591-78-6 2-Hexanone 90000 J 127-18-4 Tetrachloroethene 360000 108-88-3 Toluene 3800000 79-34-5 1,1,2,2-Tetrachloroethane 280000 108-90-7 Chlorobenzene 280000 100-41-4 Ethylbenzene 1000000 100-42-5 Styrene 34000				Ū
127-18-4 Tetrachloroethene 360000 108-88-3 Toluene 3800000 79-34-5 1,1,2,2-Tetrachloroethane 280000 U 108-90-7 Chlorobenzene 280000 U 100-41-4 Ethylbenzene 1000000 100-42-5 Styrene 34000 J		l		
108-88-3 Toluene 3800000 79-34-5 1,1,2,2-Tetrachloroethane 280000 U 108-90-7 Chlorobenzene 280000 U 100-41-4 Ethylbenzene 1000000 100-42-5 Styrene 34000 J	11			
79-34-5 1,1,2,2-Tetrachloroethane 280000 U 108-90-7 Chlorobenzene 280000 U 100-41-4 Ethylbenzene 1000000 100-42-5 Styrene 34000 J				
108-90-7 Chlorobenzene 280000 U 100-41-4 Ethylbenzene 1000000 100-42-5 Styrene 34000 J		1.1.2.2-Tetrachloroethane		Ū
100-41-4 Ethylbenzene 1000000 100-42-5 Styrene 34000 J				_
100-42-5 Styrene 34000 J				 -
				<u> </u>
	1330-20-7	Xylene (total)	4500000	

1 E

CLIENT SAMPLE NO.

VOLATILE ORGANICS ANALYSIS DATA SHEET TENTATIVELY IDENTIFIED COMPOUNDS

ACS-SB118SS3-6'-8'

ab Name: IEA-NC

Method: SOW 1/91

a. lode: IEA

Case No.: 1589-126 SDG No.: 01511

latrix: (soil/water) SOIL

Lab Sample ID: 960212404

iample wt/vol: 4 (g/mL) g

Lab File ID: 0210E07.D

.evel: (low/med) MED

Date Received: 02/01/96

Moisture: not dec. 13

Date Analyzed: 02/10/96

C Column: DB-624 ID: .53(mm) Dilution Factor: 200.0

oil Extract Volume: 10000(uL) Soil Aliquot Volume: 100(uL)

CONCENTRATION UNITS: (ug/L or ug/Kg) ug/kg

No ber TICs Found: 11

			· · · · · · · · · · · · · · · · · · ·	·
CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
000111-65-9		16.02	160000	JN
	Substituted Benzene	22.28	340000	J
	Unknown Alkane	22.54	380000	J
	Trimethyl Benzene Isomer	23.36	410000	5
000128-37-0	BUTYLATED HYDROXYTOLUENE	25.80	770000	JNY
	Substituted Benzene	26.63	340000	J
	Substituted Benzene	27.09	480000	J
	Substituted Naphthalene	27.35	410000	J
	Substituted Naphthalene	27.56	250000	J
000091-20-3		28.11	530000	JN
	2,3-Dihydro dimethyl 1H-Inde	28.78	270000	J
· · · · · · · · · · · · · · · · · · ·				
- 				

· · · · · · · · · · · · · · · · · · ·				
				<u> </u>
 				
		 		
		<u> </u>		
				
		1	1	1

1A

VOLATILE ORGANICS ANALYSIS DATA SHEET

ACS-SB119SS3-6'-8'

Method: SOW 1/91 Lab Name: IEA-NC

CAS NO. COMPOUND

Case No.: 1589-126 SDG No.: 01511 La Code: IEA

Matrix: (soil/water) SOIL Lab Sample ID: 960212405

Lab File ID: 0210E12.D Sample wt/vol: 4 (g/mL) g

Date Received: 02/01/96 Level: (low/med) MED

Date Analyzed: 02/11/96 % Moisture: not dec. 12

ID: .53(mm) Dilution Factor: 100.0 GC Column: DB-624

Soil Aliquot Volume: 100(uL) Soil Extract Volume: 10000(uL)

CONCENTRATION UNITS: (ug/L or ug/Kg) ug/kg Q

Chloromethane	140000	U
Bromomethane	140000	Ū
Vinvl Chloride	140000	U
Chloroethane	140000	Ū
Methylene Chloride	140000	U
Acetone	140000	U
Carbon Disulfide	140000	Ū
1,1-Dichloroethene	140000	U
1,1-Dichloroethane	140000	Ū
1,2-Dichloroethene (total)	47000	J
Chloroform	140000	Ü
1,2-Dichloroethane	140000	Ū
2-Butanone	140000	Ū
1,1,1-Trichloroethane	140000	Ü
Carbon Tetrachloride	140000	U
Bromodichloromethane	140000	Ū
1,2-Dichloropropane	140000	U
cis-1,3-Dichloropropene	140000	U
Trichloroethene	140000	Ū
Dibromochloromethane	140000	U
1,1,2-Trichloroethane	140000	Ü
Benzene	41000	J
Trans-1,3-Dichloropropene	140000	Ū
Bromoform	140000	Ū
4-Methyl-2-Pentanone	140000	U
2-Hexanone	140000	U
Tetrachloroethene	50000	J
Toluene	1600000	
1,1,2,2-Tetrachloroethane	140000	U
Chlorobenzene	140000	Ū
Ethylbenzene	590000	
Styrene	140000	U
Xylene (total)		
	Bromomethane Vinyl Chloride Chloroethane Methylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethene 1,1-Dichloroethane 1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene Trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene Toluene 1,1,2,7-Tetrachloroethane Tetrachloroethene Toluene 1,1,2,2-Tetrachloroethane Chlorobenzene Ethylbenzene Styrene	Bromomethane

1 E

CLIENT SAMPLE NO.

VOLATILE ORGANICS ANALYSIS DATA SHEET TENTATIVELY IDENTIFIED COMPOUNDS

ACS-SB119SS3-6'-8'

Lah Name: IEA-NC

Method: SOW 1/91

La. Code: IEA Case No.: 1589-126

SDG No.: 01511

Matrix: (soil/water) SOIL

Lab Sample ID: 960212405

Sample wt/vol: 4 (g/mL) g

Lab File ID: 0210E12.D

Level: (low/med) MED

Date Received: 02/01/96

% Moisture: not dec. 12

Date Analyzed: 02/11/96

GC Column: DB-624 ID: .53(mm)

Dilution Factor: 100.0

Soil Extract Volume: 10000(uL)

Soil Aliquot Volume: 100(uL)

CONCENTRATION UNITS: (ug/L or ug/Kg) ug/kg

t ber TICs Found: 10

	,			
CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
	SUBSTITUTED BENZENE	22.29	300000	J
	UNKNOWN ALKANE	22.57	490000	- 5
	SUBSTITUTED BENZENE	23.37	560000	J
	SUBSTITUTED BENZENE	24.37	260000	J
	ETHYL DIMETHYL BENZENE ISOME	25.07	250000	J
	UNKNOWN ALKANE	25.40	400000	J
	ETHYL DIMETHYL BENZENE ISOME	25.81	250000	J
	SUBSTITUTED BENZENE	26.46	250000	J
	SUBSTITUTED BENZENE	27.10	390000	J
000091-20-3	NAPHTHALENE	28.10	230000	JN
<u> </u>				
	<u></u>			
		-		
				
				
				
}				
		 		
				
<u> </u>				
		 		├
		 		
L	<u> </u>	1	L	L

1A VOLATILE ORGANICS ANALYSIS DATA SHEET

VBLK54

Lab Name: IEA-NC

Method: SOW 1/91

La. Code: IEA

Case No.: 1589-126

SDG No.: 01511

Matrix: (soil/water) SOIL

Lab Sample ID: VBLK54

Sample wt/vol: 4 (g/mL)

Lab File ID: 0210E02.D

Level: (low/med) MED

Date Received:

t Moisture: not dec.

CAS NO. COMPOUND

Date Analyzed: 02/10/96

GC Column: DB-624

.53 (mm) ID:

Dilution Factor: 1.0

Q

30il Extract Volume: 10000(uL)

Soil Aliquot Volume: 100(uL)

CONCENTRATION UNITS: (ug/L or ug/Kg) ug/kg

	·	
Chloromethane	1200	U
		$-\ddot{\mathbf{u}}$
		- ŭ-
l		- ŭ
		Ū
Acetone	1200	Ū
Carbon Disulfide	1200	U
1,1-Dichloroethene	1200	U
1,1-Dichloroethane	1200	U
1,2-Dichloroethene (total)	1200	U
Chloroform	1200	U
1,2-Dichloroethane	1200	U
2-Butanone	1200	U
1,1,1-Trichloroethane	1200	U
Carbon Tetrachloride	1200	U
Bromodichloromethane	1200	U
	1200	U
	1200	U
Trichloroethene	1200	U
Dibromochloromethane	1200	U
1,1,2-Trichloroethane	1200	Ü
Benzene	1200	U
Trans-1,3-Dichloropropene	1200	U
Bromoform	1200	U
4-Methyl-2-Pentanone	1200	υ
2-Hexanone	1200	U
	1200	Ū
Toluene	1200	U
	1200	Ū
Chlorobenzene	1200	U
Ethylbenzene	1200	U
Styrene	1200	U
Xylene (total)	1200	U
	Carbon Disulfide 1,1-Dichloroethene 1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene Trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene Toluene 1,1,2,2-Tetrachloroethane Chlorobenzene Ethylbenzene Styrene	Bromomethane

1E

CLIENT SAMPLE NO.

VOLATILE ORGANICS ANALYSIS DATA SHEET TENTATIVELY IDENTIFIED COMPOUNDS

VBLK54

La' Name: IEA-NC

Method: SOW 1/91

Lab Code: IEA

Case No.: 1589-126

SDG No.: 01511

fatrix: (soil/water) SOIL

Lab Sample ID: VBLK54

Sample wt/vol: 4 (g/mL) g

Lab File ID: 0210E02.D

Level: (low/med) MED

Date Received:

Moisture: not dec.

Date Analyzed: 02/10/96

GC Column: DB-624

ID: .53(mm)

Dilution Factor: 1.0

Soil Extract Volume: 10000(uL)

Soil Aliquot Volume: 100(uL)

CONCENTRATION UNITS:

Ne per TICs Found: 2 (ug/L or ug/Kg) ug/kg

CAS	NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
		Trichloro Benzene Isomer Dimethyl Naphthalene Isomer	28.54 32.74	710 1000	J J

1AVOLATILE ORGANICS ANALYSIS DATA SHEET

VBLK5M

Method: SOW 1/91 Lar Name: IEA-NC

SDG No.: 01511 Case No.: 1589-126 Lau Code: IEA

Lab Sample ID: VBLK5M fatrix: (soil/water) SOIL

Lab File ID: 0130E03.D Sample wt/vol: 4 (g/mL)

Date Received: Level: (low/med) MED

k Moisture: not dec. 0 Date Analyzed: 01/30/96

GC Column: DB-624 ID: .53 (mm) Dilution Factor: 1.0

Soil Aliquot Volume: 100(uL) 30il Extract Volume: 10000(uL)

CONCENTRATION UNITS:

CAS NO.		/L or ug/Kg)	ug/kg	Q
74-87-3	Chloromethane		1200	Ū
74-83-9	Bromomethane		1200	U
75-01-4	Vinyl Chloride		1200	U
75-00-3	Chloroethane		1200	U
75-09-2	Methylene Chloride		1200	U
64-1	Acetone		1200	Ü
-15-0	Carbon Disulfide		1200	U
75-35-4	1,1-Dichloroethene		1200	U
75-34-3	1,1-Dichloroethane		1200	Ū
540-5 9-0	1,2-Dichloroethene (total)		1200	U
67-66-3	Chloroform		1200	TÜ T
107-06-2	1,2-Dichloroethane		1200	Ū
78-93-3	2-Butanone		1200	U
71-55-6	1,1,1-Trichloroethane		1200	U
56-23- 5	Carbon Tetrachloride		1200	U
75-27-4	Bromodichloromethane		1200	U
78-87-5	1,2-Dichloropropane		1200	Ū
10061-01-5	cis-1,3-Dichloropropene		1200	U
79-01-6	Trichloroethene		1200	U
124-48-1	Dibromochloromethane		1200	U
79-00-5	1,1,2-Trichloroethane		1200	U
71-43-2	Benzene		1200	U
10061- 02-6	Trans-1,3-Dichloropropene		1200	U
75-25-2	Bromoform		1200	Ū
108-10-1	4-Methyl-2-Pentanone		1200	Ū
591-78-6	2-Hexanone		1200	U
127-18-4	Tetrachloroethene		1200	U
108-88-3	Toluene		1200	U
79-34-5	1,1,2,2-Tetrachloroethane		1200	U
108-90-7	Chlorobenzene		1200	U
100-41-4	Ethylbenzene		1200	U
100-42-5	Styrene		1200	- 0 -
1330-20-7	Xylene (total)		1200	 0

1E

CLIENT SAMPLE NO.

VOLATILE ORGANICS ANALYSIS DATA SHEET TENTATIVELY IDENTIFIED COMPOUNDS

VBLK5M

Lab Name: IEA-NC

Method: SOW 1/91

La~ Code: IEA

Case No.: 1589-126

SDG No.: 01511

Matrix: (soil/water) SOIL

Lab Sample ID: VBLK5M

Sample wt/vol: 4 (g/mL)

Lab File ID: 0130E03.D

Level: (low/med) MED

Date Received:

% Moisture: not dec.

Date Analyzed: 01/30/96

GC Column: DB-624

ID: .53 (mm)

Dilution Factor: 1.0

Soil Extract Volume: 10000(uL)

N ber TICs Found: 0

Soil Aliquot Volume: 100(uL)

CONCENTRATION UNITS: (ug/L or ug/Kg) ug/kg

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
				,
· · · · · · · · · · · · · · · · · · ·				
	· · · · · · · · · · · · · · · · · · ·			
				
			-	
				

0

VOLATILE ORGANICS ANALYSIS DATA SHEET

ACS-SB118SS3-6'-8'MS

Lah Name: IEA-NC

COMPOUND

CAS NO.

Method: SOW 1/91

Lau Code: IEA Case No.: 1589-126

SDG No.: 01511

ug/kg

Matrix: (soil/water) SOIL Lab Sample ID: 960212404MS

Sample wt/vol: 4 (g/mL) g Lab File ID: 0210E09.D

Level: (low/med) MED Date Received: 02/01/96

% Moisture: not dec. 13
Date Analyzed: 02/10/96

GC Column: DB-624 ID: .53(mm) Dilution Factor: 200.0

Soil Extract Volume: 10000(uL) Soil Aliquot Volume: 100(uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg)

	(dg/ 2 of dg/ N		
74-87-3	Chloromethane	280000	บ
74-83-9	Bromomethane	280000	Ū
75-01-4	Vinyl Chloride	280000	U
75-00-3	Chloroethane	280000	U
75-09-2	Methylene Chloride	280000	U
-64-1	Acetone	280000	U
ر -15-0	Carbon Disulfide	280000	Ū
75-35-4	1,1-Dichloroethene	280000	Ū
75-34-3	1,1-Dichloroethane	280000	U
540-59-0	1,2-Dichloroethene (total)	280000	Ü
67-66-3	Chloroform	280000	U
107-06-2	1,2-Dichloroethane	280000	Ū
78-93-3	2-Butanone	280000	U
71-55-6	1,1,1-Trichloroethane	280000	U
56-23-5	Carbon Tetrachloride	280000	U
75-27-4	Bromodichloromethane	280000	U
78-87-5	1,2-Dichloropropane	280000	Ü
10061-01-5	cis-1,3-Dichloropropene	280000	U
79-01-6	Trichloroethene	90000	J
124-48-1	Dibromochloromethane	280000	U
79-00-5	1,1,2-Trichloroethane	280000	U
71-43-2	Benzene	280000	U
10061-02-6	Trans-1,3-Dichloropropene	280000	Ū
75-25-2	Bromoform	280000	U
108-10-1	4-Methyl-2-Pentanone	280000	Ū
591-78-6	2-Hexanone	280000	U
127-18-4	Tetrachloroethene	390000	
108-88-3	Toluene	4100000	
79-34-5	1,1,2,2-Tetrachloroethane	280000	U
108-90-7	Chlorobenzene	280000	U
100-41-4	Ethylbenzene	1100000	
100-42-5	Styrene	280000	U
1330-20-7	Xylene (total)	5000000	

1A

CLIENT SAMPLE NO.

VOLATILE ORGANICS ANALYSIS DATA SHEET

ACS-SB118SS3-6'-8'MSD

Lah Name: IEA-NC

La~ Code: IEA

Method: SOW 1/91

Case No.: 1589-126

SDG No.: 01511

Matrix: (soil/water) SOIL

Lab Sample ID: 960212404MSD

Sample wt/vol: 4 (g/mL)

Lab File ID: 0210E10.D

Level: (low/med) MED

Date Received: 02/01/96

% Moisture: not dec. 13 Date Analyzed: 02/10/96

GC Column: DB-624

ID: .53 (mm) Dilution Factor: 200.0

Soil Extract Volume:

10000(uL)

Soil Aliquot Volume: 100(uL)

CONCENTRATION UNITS:

CAS NO. COMPOUND (ug/L or ug/Kg) ug/kg Q

			
74-87-3	Chloromethane	280000	U
74-83-9	Bromomethane	280000	- 0 - 1
75-01-4	Vinyl Chloride	280000	U
75-00-3	Chloroethane	280000	U
75-09-2	Methylene Chloride	280000	U
-64-1	Acetone	280000	U
-15-0	Carbon Disulfide	280000	U
75-35-4	1,1-Dichloroethene	280000	U
75-34-3	1,1-Dichloroethane	280000	Ū
540-59-0	1,2-Dichloroethene (total)	280000	Ū
67-66-3	Chloroform	280000	U
107-06-2	1,2-Dichloroethane	280000	U
78-93-3	2-Butanone	280000	U
-55-6	1,1,1-Trichloroethane	280000	U
<u>-23−5</u>	Carbon Tetrachloride	280000	Ū
75-27-4	Bromodichloromethane	280000	Ū
78-87-5	1,2-Dichloropropane	280000	Ū
10061-01-5	cis-1,3-Dichloropropene	280000	U
79-01-6	Trichloroethene	90000	J
124-48-1	Dibromochloromethane	280000	Ū
79-00-5	1,1,2-Trichloroethane	280000	U
71-43-2	Benzene	280000	Ü
10061-02-6	Trans-1,3-Dichloropropene	280000	U
75-25-2	Bromoform	280000	U
108-10-1	4-Methyl-2-Pentanone	280000	Ū
591-78-6	2-Hexanone	280000	U
127-18-4	Tetrachloroethene	370000	
108-88-3	Toluene	4000000	
79-34-5	1,1,2,2-Tetrachloroethane	280000	U
108-90-7	Chlorobenzene	280000	U
100-41-4	Ethylbenzene	1100000	
100-42-5	Styrene	280000	U
1330-20-7	Xylene (total)	4800000	i

2B SOIL VOLATILE SYSTEM MONITORING COMPOUND RECOVERY

Name: IEA-NC

Method: SOW 1/91

Lab Code: IEA

Case No.: 1589-126 SDG No.: 01511

Level: (low/med) MED

	CLIENT	SMC1	SMC2	SMC3	OTHER	TOT
	SAMPLE NO.	(TOL) #	(BFB)#	(DCE) #		OUT
		1				
01	VBLK5M	99	97	96		0
02	ACS-SB110SS4-7'-9'	96D	97D	96D		ŏ
03	VBLK54	101	97	93		ŏ
04	ACS-SB118SS3-6'-8'	100D	98D	96D		0
05	ACS-SB118SS3-6'-8'MS	101D	98D	96D		- 6
06	ACS-SB118SS3-6'-8'MSD	101D	97D	96D		0
07	ACS-SB119SS3-6'-8'	101D	100D	95D		
08	WC2-20113222-00	1010	1000	930		
09						
10			I			
11		L				
12						
13						
14						
15						
16						
17						
18						
19						}
20						
21						}
22						
23						
24						
25						
26						
27						
28						
29						
30						
ے ت						

QC LIMITS SMC1 (TOL) = Toluene-d8 (84-138) SMC2 (BFB) = Bromofluorobenzene (59-113) SMC3 (DCE) = 1,2-Dichloroethane-d4 (70-121) (84 - 138)

- # Column to be used to flag recovery values
- * Values outside of QC limits.
- D System Monitoring Compound diluted out

page 1 of 1

FORM II VOA-3

3 B SOIL VOLATILE MATRIX SPIKE/MATRIX SPIKE DUPLICATE RECOVERY

Lab Name: IEA-NC

Method: SOW 1/91

Law Code: IEA

Case No.: 1589-126

SDG No.: 01511

Matrix Spike - Client Sample No.: ACS-SB118SS3-6'-8' Level: (low/med) MED

COMPOUND	SPIKE ADDED (ug/Kg)	SAMPLE CONCENTRATION (ug/Kg)	MS CONCENTRATION (ug/Kg)	MS % REC	#	QC. LIMITS REC.
1,1-Dichloroethene	7200	0	0	0	D	59-172
Trichloroethene	7200	80000	90000	139	D	62-137
Benzene	7200	0	0	0	D	66-142
Toluene	7200	3800000	4100000	4167	D	59-139
lorobenzene	7200	0	0	0	D	60-133

COMPOUND	SPIKE ADDED (ug/Kg)	MSD CONCENTRATION (ug/Kg)	MSD % REC #	% RPD #	QC L RPD	IMITS REC.
,1-Dichloroethene	7200	0	0 D	0	22	59-172
Trichloroethene	7200	90000	139 D	0	24	62-137
Benzene	7200	0	0 D	0	21	66-142
Toluene	7200	400000	2778 D	40*	21	59-139
Chlorobenzene	7200	0	0 D	0	21	60-133

- # Column to be used to flag recovery and RPD values with an asterisk
- * Values outside of QC limits.
- D Spike compound diluted out.

1 out of 5 outside limits

Spike Recovery: 10 out of 10 outside limits

COMMENTS:	

VOLATILE METHOD BLANK SUMMARY

CLIENT SAMPLE NO.

VBLK54

L Name: IEA-NC

Method: SOW 1/91

Lab Code: IEA

Case No.: 1589-126

SDG No.: 01511

Lab File ID: 0210E02.D

Lab Sample ID: VBLK54

Date Analyzed: 02/10/96

Time Analyzed: 16:13

GC Column: DB-624 ID: .53(mm) Heated Purge: (Y/N) N

Instrument ID: MSD5

THIS METHOD BLANK APPLIES TO THE FOLLOWING SAMPLES, MS AND MSD:

	CLIENT SAMPLE NO.	LAB SAMPLE ID	LAB FILE ID	TIME ANALYZED
01	ACS-SB118SS3-6'-8'	060212404	0210E07.D	20:42
02	ACS-SB118SS3-6'-8'MS	960212404 960212404MS	0210E07.D	22:04
03	ACS-SB118SS3-6'-8'MSD	960212404MSD	0210E09.D	22:44
04	ACS-SB110353-0 -0 MSD ACS-SB119SS3-6 -8	960212404	0210E10.D	00:06
05	ACS-36119333-0 -6	900212403	OZIOLIZ.D	
06				
07				
08			L	·
09				
10				
1			,	
12,				
13				
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				
26		•		
27				
28				
29				
30				

COMMENTS:	

page 1 of 1

4 A VOLATILE METHOD BLANK SUMMARY

CLIENT SAMPLE NO.

VBLK5M

L Name: IEA-NC

Method: SOW 1/91

Lab Code: IEA

Case No.: 1589-126

SDG No.: 01511

Lab File ID: 0130E03.D

Lab Sample ID: VBLK5M

Date Analyzed: 01/30/96

Time Analyzed: 19:17

GC Column: DB-624 ID: .53(mm) Heated Purge: (Y/N) N

Instrument ID: MSD5

THIS METHOD BLANK APPLIES TO THE FOLLOWING SAMPLES, MS AND MSD:

CLIENT SAMPLE NO.	LAB SAMPLE ID	LAB FILE ID	TIME ANALYZED
01 ACS-SB110SS4-7'-9'	960151101	0130E07.D	22:26
02			
03			
04			
05 06			
07			
08			
09			
10			
1			
12		ļ	
13		 	
15			
16			
17			
18			
19			
20	ļ <u>-</u>		
21 22			
23		 	
24			
25			
26			
27			
28			
29	 	ļ	
30		 	
	<u> </u>	1	<u></u>

COMMENTS:	

page 1 of 1

8A VOLATILE INTERNAL STANDARD AREA AND RT SUMMARY

ab Name: IEA-NC

Method: SOW 1/91

ar Lode: IEA

Case No.: 1589-126

SDG No.: 01511

ab File ID (Standard): 0210E01.D

Date Analyzed: 02/10/96

nstrument ID: MSD5

Time Analyzed:

15:15

C Column: DB-624 ID: .53(mm)

Heated Purge: (Y/N) N

	IS1(BCM) AREA #	RT #	IS2(DFB) AREA #	RT #	IS3(CBZ) AREA #	RT #
12 HOUR STD UPPER LIMIT LOWER LIMIT	1920768 3841536 960384	10.28 10.78 9.78	7337000 14674000 3668500	12.47 12.97 11.97	6129399 12258798 3064700	18.76 19.26 18.26
EPA SAMPLE NO.						
2 ACS-SB118SS3-6'-8' 3 ACS-SB118SS3-6'-8'MS 4 ACS-SB118SS3-6'-8'MSD	2092039 1874453 1877308 1900638 2006674	10.26 10.26 10.28 10.24 10.26	8294178 7269201 7200384 7418966 7889737	12.45 12.45 12.46 12.43 12.45	7048406 6280866 6075167 6346631 6719501	18.76 18.75 18.76 18.74 18.75
1 2						

IS1 (BCM) = Bromochloromethane IS2 (DFB) = 1,4-Difluorobenzene IS3 (CBZ) = Chlorobenzene-d5

AREA UPPER LIMIT = +100% of internal standard area AREA LOWER LIMIT = - 50% of internal standard area RT UPPER LIMIT = +0.50 minutes of internal standard RT RT LOWER LIMIT = -0.50 minutes of internal standard RT

Column used to flag values outside QC limits with an asterisk.

* Values outside of QC limits.

8A VOLATILE INTERNAL STANDARD AREA AND RT SUMMARY

Lab Name: IEA-NC

Method: SOW 1/91

Code: IEA

Case No.: 1589-126

SDG No.: 01511

Lab File ID (Standard): 0130E01S.D

Date Analyzed: 01/30/96

Instrument ID: MSD5

Time Analyzed: 17:27

GC Column: DB-624

ID: .53 (mm)

Heated Purge: (Y/N) N

	1 - 2 - 2 - 2 - 3 - 3 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1			,	1775 / ABNT	
	ISI(BCM)	D 4	IS2(DFB) AREA #	RT #	IS3(CBZ) AREA #	Dm "
·	AREA #	RT #	AREA #	R1 #	AREA #	RT #
12 HOUR STD	1314981	10.32	4794436	12.49	4007378	18.75
UPPER LIMIT	2629962	10.82	9588872	12.99	8014756	19.25
LOWER LIMIT	657490	9.82	2397218	11.99	2003689	18.25
EPA SAMPLE						
· · · · · · · · · · · · · · · · · · ·						
O1 VBLK5M	1388863	10.31	5194364	12.47	4249853	18.74
02 ACS-SB110SS4-7'-9'	1371388	10.24	5210191	12.43	4408710	18.73
03						
04						
05						
06						
08						
00						
1						
11:						
12						
13						
14						
15						
16 17						
18						
19						
20						
21						
22						

IS1 (BCM) = Bromochloromethane IS2 (DFB) = 1,4-Difluorobenzene

IS3 (CBZ) = Chlorobenzene-d5

AREA UPPER LIMIT = +100% of internal standard area AREA LOWER LIMIT = - 50% of internal standard area

RT UPPER LIMIT = +0.50 minutes of internal standard RT RT LOWER LIMIT = -0.50 minutes of internal standard RT

Column used to flag values outside QC limits with an asterisk.

* Values outside of QC limits.

135155

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Matrix: (soil/water) SOIL Lab Sample ID: 960212410

Sample wt/vol: 30.2 (g/mL) G Lab File ID: P1021496 059.D

% Moisture: 12 decanted: (Y/N) N Date Received: 02/01/96

Extraction: (SepF/Cont/Sonc) SONC Date Extracted:02/09/96

Concentrated Extract Volume: 5000(uL) Date Analyzed: 02/17/96

Injection Volume: 1.0(uL) Dilution Factor: 10.0

GPC Cleanup: (Y/N) Y pH: 6.9 Sulfur Cleanup: (Y/N) N

CONCENTRATION UNITS:

CAS NO. COMPOUND (ug/L or ug/Kg) UG/KG Q

12674-11-2----Aroclor-1016 370 11104-28-2----Aroclor-1221 760 U 11141-16-5-----Aroclor-1232 370 U 53469-21-9-----Aroclor-1242 370 U 12672-29-6-----Aroclor-1248 3200 11097-69-1----Aroclor-1254 Ū 370 11096-82-5----Aroclor-1260 370 U

135155DL

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

I Code: IEA Case No.: 1589-126

SDG No.: 01511

Matrix: (soil/water) SOIL

Lab Sample ID: 960212410DL

Sample wt/vol:

30.2 (g/mL) G

Lab File ID: P1021496 104.D

% Moisture: 12

decanted: (Y/N) N

Date Received: 02/01/96

Extraction: (SepF/Cont/Sonc) SONC

Date Extracted: 02/09/96

Concentrated Extract Volume:

5000(uL)

Date Analyzed: 02/20/96

Injection Volume:

CAS NO.

1.0(uL)

COMPOUND

Dilution Factor: 100.0

GPC Cleanup: (Y/N) Y pH: 6.9

Sulfur Cleanup: (Y/N) N

CONCENTRATION UNITS: (ug/L or ug/Kg) UG/KG

Q

12674-11-2Aroclor-1016 11104-28-2Aroclor-1221 11141-16-5Aroclor-1232	3700 7600 3700	ט ט ט
53469-21-9Aroclor-1242	3700	Ū
12672-29-6Aroclor-1248	2700	DJ
11097-69-1Aroclor-1254	3700	Ü
11096-82-5Aroclor-1260	3700	ן ע

3SS479

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Case No.: 1589-126 Code: IEA

SDG No.: 01511

Matrix: (soil/water) SOIL

Lab Sample ID: 960151103

Sample wt/vol:

30.0 (g/mL) G

P2020196 187.D

% Moisture: 12

decanted: (Y/N) N

Date Received: 01/25/96

Extraction: (SepF/Cont/Sonc) SONC

Date Extracted: 02/01/96

Concentrated Extract Volume:

5000(uL)

Date Analyzed: 02/13/96

Injection Volume: 1.0(uL)

CAS NO.

Dilution Factor: 10.0

GPC Cleanup: (Y/N) Y

pH: 7.4

Sulfur Cleanup: (Y/N) N

CONCENTRATION UNITS: COMPOUND

(ug/L or ug/Kg) UG/KG

Lab File ID:

Q

PESTICIDE ORGANICS ANALYSIS DATA SHEET

CLIENT SAMPLE NO.

3SS479DL

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Code: IEA

Case No.: 1589-126

SDG No.: 01511

Matrix: (soil/water) SOIL

Lab Sample ID: 960151103DL

Sample wt/vol:

30.0 (q/mL) G

Lab File ID: P2020196 186.D

% Moisture: 12

decanted: (Y/N) N

Date Received: 01/25/96

Extraction: (SepF/Cont/Sonc) SONC

Date Extracted: 02/01/96

Concentrated Extract Volume:

5000(uL)

Date Analyzed: 02/13/96

Injection Volume: 1.0(uL)

Dilution Factor: 100.0

GPC Cleanup: (Y/N) Y

pH: 7.4

CONCENTRATION UNITS:

Sulfur Cleanup: (Y/N) N

CAS NO.	COMPOUND	(ug/L or ug/Kg) UG/KG	Q
	Aroclor-1016	3800	
	Aroclor-1221	7600	
53469-21-9	Aroclor-1242	3600	
	Aroclor-1248 Aroclor-1254	3800	· I -
11096-82-5-	Aroclor-1260	3800) U

485105

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

SDG No.: 01511 lode: IEA Case No.: 1589-126

Lab Sample ID: 960212406 Matrix: (soil/water) SOIL

30.0 (g/mL) G Lab File ID: Sample wt/vol: P1021496 060.D

t Moisture: 12 decanted: (Y/N) N Date Received: 02/01/96

Extraction: (SepF/Cont/Sonc) SONC Date Extracted: 02/09/96

Concentrated Extract Volume: 5000(uL) Date Analyzed: 02/17/96

Dilution Factor: 2.0 Injection Volume: 1.0(uL)

SPC Cleanup: (Y/N) Y pH: 7.5 Sulfur Cleanup: (Y/N) N

CONCENTRATION UNITS: CAS NO. COMPOUND (ug/L or ug/Kg) UG/KG Q

		1
12674-11-2Aroclor-1016	75	U
11104-28-2Aroclor-1221	150	U
11141-16-5Aroclor-1232	75	U
53469-21-9Aroclor-1242	⁻ 75	ע (
12672-29-6Aroclor-1248	2200	P
11097-69-1Aroclor-1254	1200	P
11096-82-5Aroclor-1260	340	P

485105DL

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Code: IEA

Case No.: 1589-126

SDG No.: 01511

fatrix: (soil/water) SOIL

Lab Sample ID: 960212406DL

Lab File ID:

P1021496 044.D

Sample wt/vol:

30.0 (g/mL) G

Moisture: 12

decanted: (Y/N) N

Date Received: 01/25/96

Extraction: (SepF/Cont/Sonc) SONC

Date Extracted: 02/09/96

Concentrated Extract Volume:

5000 (uL)

Date Analyzed: 02/16/96

Injection Volume:

CAS NO.

1.0(uL)

Dilution Factor: 20.0

PC Cleanup: (Y/N) Y

pH: 7.5

Sulfur Cleanup: (Y/N) N

CONCENTRATION UNITS: COMPOUND

(ug/L or ug/Kg) UG/KG

Q

12674-11-2Aroclor-1016 11104-28-2Aroclor-1221 11141-16-5Aroclor-1232 53469-21-9Aroclor-1242 12672-29-6Aroclor-1248 11097-69-1Aroclor-1254 11096-82-5Aroclor-1260	750 1500 750 750 3700 1900 510	i .
------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	--------------------------------------------------	-----

7SS368

Q

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

COMPOUND -

Code: IEA

SDG No.: 01511 Case No.: 1589-126

fatrix: (soil/water) SOIL Lab Sample ID: 960212407

30.1 (g/mL) GLab File ID: P1021496 046.D Sample wt/vol:

k Moisture: 27 decanted: (Y/N) N Date Received: 02/01/96

Date Extracted: 02/09/96 Extraction: (SepF/Cont/Sonc) SONC

Concentrated Extract Volume: 5000(uL) Date Analyzed: 02/16/96

Dilution Factor: 20.0 [njection Volume: 1.0(uL)

FPC Cleanup: (Y/N) Y pH: 5.9 Sulfur Cleanup: (Y/N) N

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/KG CAS NO. 12674-11-2----Aroclor-1016 900 U 11104-28-2----Aroclor-1221 1800 U 11141-16-5-----Aroclor-1232 U 900 53469-21-9-----Aroclor-1242 900 U 12672-29-6-----Aroclor-1248 900 U 11097-69-1-----Aroclor-1254 35000 11096-82-5-----Aroclor-1260 Ū 900

PESTICIDE ORGANICS ANALYSIS DATA SHEET

CLIENT SAMPLE NO.

7SS368DL

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Code: IEA

Case No.: 1589-126

SDG No.: 01511

Matrix: (soil/water) SOIL

Lab Sample ID: 960212407DL

30.1 (g/mL) G

Lab File ID: P1021496 040.D

Sample wt/vol: % Moisture: 27 decanted: (Y/N) N

Date Received: 02/01/96

Extraction: (SepF/Cont/Sonc) SONC

Date Extracted: 02/09/96

Concentrated Extract Volume:

5000 (uL)

Injection Volume:

1.0(uL)

Date Analyzed: 02/16/96 Dilution Factor: 200.0

GPC Cleanup: (Y/N) Y pH: 5.9

Sulfur Cleanup: (Y/N) N

CONCENTRATION UNITS: CAS NO. COMPOUND

(ug/L or ug/Kg) UG/KG 0

12674-11-2Aroclor-1016 11104-28-2Aroclor-1221 11141-16-5Aroclor-1232 53469-21-9Aroclor-1242 12672-29-6Aroclor-1248	9000 18000 9000 9000	7
12672-29-6Aroclor-1248 11097-69-1Aroclor-1254 11096-82-5Aroclor-1260	9000 44000 9000	D U

PESTICIDE ORGANICS ANALYSIS DATA SHEET

CLIENT SAMPLE NO.

855368

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

La Code: IEA Case No.: 1589-126

Sample wt/vol:

SDG No.: 01511

fatrix: (soil/water) SOIL Lab Sample ID: 960212408

30.1 (g/mL) G Lab File ID: P1021496 047.D

t Moisture: 20 decanted: (Y/N) N Date Received: 02/01/96

Extraction: (SepF/Cont/Sonc) SONC Date Extracted:02/09/96

Concentrated Extract Volume: 5000(uL) Date Analyzed: 02/16/96

Dilution Factor: 20.0 [njection Volume: 1.0(uL)

SPC Cleanup: (Y/N) Y pH: 6.7 Sulfur Cleanup: (Y/N) N

CAS NO.	COMPOUND			Q
11104-28-2- 11141-16-5- 53469-21-9- 12672-29-6-	Aroclor-1221 Aroclor-1232 Aroclor-1242 Aroclor-1248		820 1700 820 820 820 7500	บ บ บ บ P
11096-82-5-	Aroclor-1260		7300	P
	12674-11-2- 11104-28-2- 11141-16-5- 53469-21-9- 12672-29-6- 11097-69-1-	CAS NO. COMPOUND 12674-11-2Aroclor-1016 11104-28-2Aroclor-1221 11141-16-5Aroclor-1232 53469-21-9Aroclor-1242 12672-29-6Aroclor-1248 11097-69-1Aroclor-1254 11096-82-5Aroclor-1260	CAS NO. COMPOUND (ug/L or ug/Kg) UG 12674-11-2Aroclor-1016 11104-28-2Aroclor-1221 11141-16-5Aroclor-1232 53469-21-9Aroclor-1242 12672-29-6Aroclor-1248 11097-69-1Aroclor-1254	12674-11-2Aroclor-1016 820 11104-28-2Aroclor-1221 1700 11141-16-5Aroclor-1232 820 53469-21-9Aroclor-1242 820 12672-29-6Aroclor-1248 820 11097-69-1Aroclor-1254 7500

8SS368DL

Q

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Lah Code: IEA Case No.: 1589-126 SDG No.: 01511

Macrix: (soil/water) SOIL Lab Sample ID: 960212408DL

Sample wt/vol: 30.1 (g/mL) G Lab File ID: P1021496_041.D

% Moisture: 20 decanted: (Y/N) N Date Received: 02/01/96

Extraction: (SepF/Cont/Sonc) SONC Date Extracted:02/01/96

Concentrated Extract Volume: 5000(uL) Date Analyzed: 02/16/96

Injection Volume: 1.0(uL) Dilution Factor: 200.0

GPC Cleanup: (Y/N) Y pH: 6.7 Sulfur Cleanup: (Y/N) N

CONCENTRATION UNITS: (ug/L or ug/Kg) UG/KG

12674-11-2----Aroclor-1016 8200 U 11104-28-2----Aroclor-1221 17000 U 11141-16-5----Aroclor-1232 8200 U 53469-21-9----Aroclor-1242 8200 U 12672-29-6----Aroclor-1248 U 8200 11097-69-1----Aroclor-1254 12000 D 11096-82-5-----Aroclor-1260 12000 D

PESTICIDE ORGANICS ANALYSIS DATA SHEET

CLIENT SAMPLE NO.

S51113

ab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Case No.: 1589-126

SDG No.: 01511

(atrix: (soil/water) SOIL

Lab Sample ID: 960212409

sample wt/vol:

Ja' Code: IEA

30.0 (g/mL) G

decanted: (Y/N) N

Lab File ID:

P1021496 061.D

; Moisture: 11

Date Received: 02/01/96

Extraction: (SepF/Cont/Sonc) SONC

Date Extracted: 02/09/96

:oncentrated Extract Volume:

Date Analyzed: 02/17/96

Injection Volume: 1.0(uL)

Dilution Factor: 2.0

PC Cleanup: (Y/N) Y

pH: 8.1

Sulfur Cleanup: (Y/N) N

CONCENTRATION UNITS:

CAS NO. COMPOUND (ug/L or ug/Kg) UG/KG Q

5000(uL)

12672-29-6Aroclor-1248 1200 P 11097-69-1Aroclor-1254 760 P 11096-82-5Aroclor-1260 74 U	11097-69-1Aroclor-1254	760	. U U U P P
----------------------------------------------------------------------------------------------	------------------------	-----	-------------------------

PESTICIDE ORGANICS ANALYSIS DATA SHEET

S51113DL

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

lah Code: IEA

Case No.: 1589-126

SDG No.: 01511

fallix: (soil/water) SOIL

Lab Sample ID: 960212409DL

Lab File ID:

P1021496 045.D

Sample wt/vol:

30.0 (g/mL) G

Date Received: 02/01/96

k Moisture: 11

decanted: (Y/N) N

Extraction: (SepF/Cont/Sonc) SONC

Date Extracted:02/09/96

Concentrated Extract Volume: 5000(uL)

Date Analyzed: 02/16/96

[njection Volume: 1.0(uL)

Dilution Factor: 20.0

FPC Cleanup: (Y/N) Y pH: 8.1

Sulfur Cleanup: (Y/N) N

CONCENTRATION UNITS:

CAS NO.

COMPOUND

(ug/L or ug/Kg) UG/KG

Q

12674-11-2Aroclor-1016	740	U
11104-28-2Aroclor-1221	1500	U
11141-16-5Aroclor-1232	740	U
53469-21-9Aroclor-1242	740	U
12672-29-6Aroclor-1248	1600	D
11097-69-1Aroclor-1254	710	D
11096-82-5Aroclor-1260	740	U

S51113MS

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Ja' Code: IEA Case No.: 1589-126 SDG No.: 01511

Matrix: (soil/water) SOIL Lab Sample ID: 960212409MS

3ample wt/vol: 30.0 (g/mL) G Lab File ID: P1021496_062.D

t Moisture: 11 decanted: (Y/N) N Date Received: 02/01/96

Extraction: (SepF/Cont/Sonc) SONC Date Extracted:02/09/96

Concentrated Extract Volume: 5000(uL) Date Analyzed: 02/17/96

Injection Volume: 1.0(uL) Dilution Factor: 2.0

FPC Cleanup: (Y/N) Y pH: 8.1 Sulfur Cleanup: (Y/N) N

CONCENTRATION UNITS:

CAS NO. COMPOUND (ug/L or ug/Kg) UG/KG Q

12674-11-2Aroclor-1016 11104-28-2Aroclor-1221 11141-16-5Aroclor-1232 53469-21-9Aroclor-1242 12672-29-6Aroclor-1248 11097-69-1Aroclor-1254 11096-82-5Aroclor-1260	74 150 74 74 990 1300 74	U U U P P U
------------------------------------------------------------------------------------------------------------------------------------------------------------------	--------------------------------------------	----------------------------

S51113MSD

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

I Code: IEA Case No.: 1589-126

SDG No.: 01511

Matrix: (soil/water) SOIL

Lab Sample ID: 960212409MSD

Lab File ID: P1021496 063.D

Sample wt/vol:

30.0 (g/mL) G

% Moisture: 11 decanted: (Y/N) N Date Received: 02/01/96

Concentrated Extract Volume: 5000(uL) Date Analyzed: 02/17/96

Date Extracted: 02/09/96

Injection Volume: 1.0(uL)

Extraction: (SepF/Cont/Sonc) SONC

Dilution Factor: 2.0

GPC Cleanup: (Y/N) Y pH: 8.1

Sulfur Cleanup: (Y/N) N

Q	
U U U P P	

SS368D

P1021496 058.D

SDG No.: 01511

Lab File ID:

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

La' Code: IEA Case No.: 1589-126

Lab Sample ID: 960212411

fatrix: (soil/water) SOIL

30.2 (g/mL) GSample wt/vol:

decanted: (Y/N) N Date Received: 02/01/96 b Moisture: 16

Extraction: (SepF/Cont/Sonc) SONC Date Extracted: 02/09/96

Concentrated Extract Volume: 5000(uL) Date Analyzed: 02/17/96

Dilution Factor: 20.0 Injection Volume: 1.0(uL)

Sulfur Cleanup: (Y/N) N PC Cleanup: (Y/N) Y pH: 7.8

CONCENTRATION UNITS: CAS NO. COMPOUND (ug/L or ug/Kg) UG/KG Q

12674-11-2Aroclor-1016 11104-28-2Aroclor-1221 11141-16-5Aroclor-1232 53469-21-9Aroclor-1242 12672-29-6Aroclor-1248 11097-69-1Aroclor-1254 11096-82-5Aroclor-1260	780 1600 780 780 780 4200 3100	U U U U P
------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	--------------------------------------------------	-----------------------

1D PESTICIDE ORGANICS ANALYSIS DATA SHEET

CLIENT SAMPLE NO.

SS368DDL

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

I

SDG No.: 01511

Matrix: (soil/water) SOIL

Lab Sample ID: 960212411DL

Lab File ID:

P1021496 042.D

Sample wt/vol:

30.2 (g/mL) G

% Moisture: 16

decanted: (Y/N) N

Date Received: 02/01/96

Extraction: (SepF/Cont/Sonc) SONC

Date Extracted:02/09/96

Concentrated Extract Volume:

5000(uL)

Date Analyzed: 02/16/96

Injection Volume:

1.0(uL)

Dilution Factor: 200.0

GPC Cleanup: (Y/N) Y

pH: 7.8

Sulfur Cleanup: (Y/N) N

CONCENTRATION UNITS:

CAS NO.

COMPOUND

(ug/L or ug/Kg) UG/KG

Q

12674-11-2Aroclor-1016 11104-28-2Aroclor-1221 11141-16-5Aroclor-1232 53469-21-9Aroclor-1242 12672-29-6Aroclor-1248 11097-69-1Aroclor-1254 11096-82-5Aroclor-1260	7800 16000 7800 7800 7800 4600 3700	U U U U Q Q Q Q Q Q
------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-------------------------------------------------------	------------------------------------------------

SS5911

P2020196 189.D

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

30.0 (g/mL) G

Case No.: 1589-126 Lab Code: IEA

Sample wt/vol:

SDG No.: 01511

Lab File ID:

Lab Sample ID: 960151102

M. ix: (soil/water) SOIL

Date Received: 01/25/96 % Moisture: 12 decanted: (Y/N) N

Date Extracted:02/01/96 Extraction: (SepF/Cont/Sonc) SONC

Date Analyzed: 02/13/96 Concentrated Extract Volume: 5000(uL)

Dilution Factor: 50.0 Injection Volume: 1.0(uL)

Sulfur Cleanup: (Y/N) N GPC Cleanup: (Y/N) Y pH: 7.6

CONCENTRATION UNITS: CAS NO. COMPOUND (ug/L or ug/Kg) UG/KG Q

12674-11-2Aroclor-1016 11104-28-2Aroclor-1221 11141-16-5Aroclor-1232 53469-21-9Aroclor-1242	1900 3800 1900 1900	บ
12672-29-6Aroclor-1248 11097-69-1Aroclor-1254 11096-82-5Aroclor-1260	3000 4500 1900	P U

SS5911DL

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Le Code: IEA

Case No.: 1589-126

SDG No.: 01511

Matrix: (soil/water) SOIL

Lab File ID: P2020196 188.D

Sample wt/vol:

30.0 (g/mL) G

% Moisture: 12

decanted: (Y/N) N

Date Received: 01/25/96

Extraction: (SepF/Cont/Sonc) SONC

Date Extracted: 02/01/96

Lab Sample ID: 960151102DL

Concentrated Extract Volume: 5000(uL)

Date Analyzed: 02/13/96

Injection Volume: 1.0(uL)

Dilution Factor: 500.0

GPC Cleanup: (Y/N) Y

pH: 7.6

Sulfur Cleanup: (Y/N) N

CONCENTRATION UNITS:

CAS NO. COMPOUND (ug/L or ug/Kg) UG/KG Q

12674-11-2Aroclor-1016 11104-28-2Aroclor-1221 11141-16-5Aroclor-1232 53469-21-9Aroclor-1242 12672-29-6Aroclor-1248 11097-69-1Aroclor-1254 11096-82-5Aroclor-1260	19000 38000 19000 19000 3400 5700 19000	U U U DJP DJP U
11096-82-5Aroclor-1260	19000	Ü

SS5911MS

Lab File ID: P2020196 192.D

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

30.0 (g/mL) G

Sample wt/vol:

Lab Code: IEA Case No.: 1589-126 SDG No.: 01511

Lab Sample ID: 960151102MS

Macrix: (soil/water) SOIL

Date Received: 01/25/96 % Moisture: 12 decanted: (Y/N) N

Extraction: (SepF/Cont/Sonc) SONC Date Extracted: 02/01/96

Date Analyzed: 02/13/96 Concentrated Extract Volume: 5000(uL)

Dilution Factor: 50.0 Injection Volume: 1.0(uL)

Sulfur Cleanup: (Y/N) N GPC Cleanup: (Y/N) Y pH: 7.6

CONCENTRATION UNITS:

COMPOUND	(ug/L or	ug/Kg)	UG/KG	Q
Aroclor-1221Aroclor-1232Aroclor-1242Aroclor-1248Aroclor-1254			1900 3800 1900 1900 4000 5700 1900	U U U P P
	COMPOUND Aroclor-1016Aroclor-1221Aroclor-1232Aroclor-1242Aroclor-1248Aroclor-1254Aroclor-1260	Aroclor-1016 Aroclor-1221 Aroclor-1232 Aroclor-1242 Aroclor-1248	Aroclor-1016Aroclor-1221 Aroclor-1232 Aroclor-1242 Aroclor-1248Aroclor-1254	Aroclor-1016 1900 Aroclor-1221 3800 Aroclor-1232 1900 Aroclor-1242 1900 Aroclor-1248 4000 Aroclor-1254 5700

SS5911MSD

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Lab Code: IEA

Case No.: 1589-126

SDG No.: 01511

Mc_ix: (soil/water) SOIL

Lab Sample ID: 960151102MSD

Lab File ID: P2020196 193.D

Sample wt/vol:

30.0 (g/mL) G

% Moisture: 12

decanted: (Y/N) N

Date Received: 01/25/96

Extraction: (SepF/Cont/Sonc) SONC

Date Extracted: 02/01/96

Concentrated Extract Volume: 5000(uL)

Date Analyzed: 02/14/96

Injection Volume:

CAS NO.

1.0(uL)

COMPOUND

Dilution Factor: 50.0

GPC Cleanup:

(Y/N) Y

pH: 7.6

Sulfur Cleanup: (Y/N) N

CONCENTRATION UNITS:

0 (ug/L or ug/Kg) UG/KG

1900 12674-11-2----Aroclor-1016 11104-28-2----Aroclor-1221 3800 U 11141-16-5-----Aroclor-1232 1900 U 1900 U 53469-21-9-----Aroclor-1242 P 12672-29-6----Aroclor-1248 3400 P 11097-69-1----Aroclor-1254 4900 11096-82-5----Aroclor-1260 1900 U

SOIL PESTICIDE SURROGATE RECOVERY

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Lah Code: IEA Case No.: 1589-126 SDG No.: 01511

Gc Column(1): RTX-35 ID: 0.53 (mm) GC Column(2): DB-1701 ID: 0.53 (mm)

	CLIENT	TCX 1	TCX 2	DCB 1	DCB 2	OTHER	OTHER	TOT
	SAMPLE NO.	%REC #	%REC #	%REC #	%REC #	(1)	(2)	OUT
	========	=====	======		=====	======	=====	===
01	135155	11D	5D	26D	39D			0
02	135155DL	OD	OD	0D	0D			0
03	485105	52D	27D	56D	47D			0
04	485105DL	OD	0D	OD OD	OD			0
05	7SS368	OD	OD OD	OD	OD OD			0
06	7SS368DL	OD	OD	OD	OD			0
07	8SS368	OD	OD	OD	OD			0
08 09	8SS368DL	OD	OD	0D	OD			0
10	PBLK92 S51113	94	93 35D	101 59D	93 115			0
11	S51113 S51113DL	67	0D	0D				0
12	S51113DL S51113MS	0D 55D	26D	48D	0D 354D			0
13	S51113MSD	54D	25D	48D	338D			0
14	SS368D	0D	0D	0D	0D			0
15	SS368DDL	00	OD	OD	OD			0
16	33300000	05	05	OD	0.5			١
17								
18								
19					<u> </u>			
20					i·			
21				i			 [-	—— j
22								
23							-	
24				I·				
25								
26			l·					
27			·					
28								
29								
30				-				
1	· · · · · · · · · · · · · · · · · · ·	I	I.	I .	I.	I -		

ADVISORY QC LIMITS

TCX = Tetrachloro-m-xylene (60-150) DCB = Decachlorobiphenyl (60-150)

Column to be used to flag recovery values
* Values outside of QC limits
D Surrogate diluted out

SOIL PESTICIDE SURROGATE RECOVERY

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Lah Code: IEA Case No.: 1589-126 SDG No.: 01511

3C column(1): DB-1701 ID: 0.53 (mm) GC Column(2): RTX-35 ID: 0.53 (mm)

	CLIENT	TCX 1	TCX 2	DCB 1	DCB 2	OTHER	OTHER	TOT
	SAMPLE NO.	TCX 1	REC #	DCB 1	REC #	(1)	(2)	OUT
	=======================================	======	======	=====	======	======	======	===
01	3 <i>SS</i> 479	10D	13D	16D	0D			0
02	3SS479DL	OD	OD	0D	OD			0
03	PBLK82	88	111	08	123		<u> </u>	0
04 05	SS5911 SS5911DL	OD OD	0D 0D	OD OD	OD OD			0
06	SS5911MS	OD	OD	OD	QD			0
07	SS5911MSD	OD	OD	OD	OD			0
80								l l
09								
10 11		·						
12	·							
13	· 							
14								
15								
16 17]				
18								
19			i					
20								
21								
22								
23								
25			i					
26		\						[
27								
28								
29								
30								!

ADVISORY QC LIMITS

TCX = Tetrachloro-m-xylene (60-150) DCB = Decachlorobiphenyl (60-150)

Column to be used to flag recovery values
* Values outside of QC limits
D Surrogate diluted out

SOIL PESTICIDE MATRIX SPIKE/MATRIX SPIKE DUPLICATE RECOVERY

.ab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

ab Code: IEA Case No.: 1589-126

SDG No.: 01511

(at.ix Spike - Client Sample No.: S51113

COMPOUND	SPIKE ADDED (ug/Kg)	SAMPLE CONCENTRATION (ug/Kg)	MS CONCENTRATION (ug/Kg)	MS % REC #	QC. LIMITS REC.
Aroclor-1260	370	0.0	0.0	0*	60-140

COMPOUND	SPIKE ADDED (ug/Kg)	MSD CONCENTRATION (ug/Kg)	MSD % REC #	% RPD #	QC L	IMITS REC.
oclor-1260 .	370	0.0	0*	0	40	60-140

f Column to be used to flag recovery and RPD values with an	asterisk
-------------------------------------------------------------	----------

-				\sim	7	
٠ ١	/alues	outside	OI		TIMIL	-5

RPD: 0 out of 1 outside limits
Spike Recovery: 2 out of 2 outside limits

COMMENTS:		 	

SOIL PESTICIDE MATRIX SPIKE/MATRIX SPIKE DUPLICATE RECOVERY

ab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

ab Code: IEA Case No.: 1589-126

SDG No.: 01511

lat.ix Spike - Client Sample No.: SS5911

COMPOUND	SPIKE ADDED (ug/Kg)	SAMPLE CONCENTRATION (ug/Kg)	MS CONCENTRATION (ug/Kg)	MS % REC #	QC. LIMITS REC.
Aroclor-1260	380	0.0	0.0	0*	60-140
		·		Ì	
				ĺ	

COMPOUND	SPIKE ADDED (ug/Kg)	MSD CONCENTRATION (ug/Kg)	MSD % REC #	% RPD #	QC L:	MITS REC.
clor-1260	380	0.0	0*	0	40	60-140
•						

¥	Column	to	be	used	to	flag	recovery	and	RPD	values	with	an	asterisk
---	--------	----	----	------	----	------	----------	-----	-----	--------	------	----	----------

RPD: 0 out of 1 outside limits
Spike Recovery: 2 out of 2 outside limits

COMMENTS:	

^{*} Values outside of QC limits

PBLK82

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

I-5 Code: IEA Case No.: 1589-126

SDG No.: 01511

Las Sample ID: PBLK82 Lab File ID:

P2020196 148.D

Matrix: (soil/water) SOIL

Extraction: (SepF, Cont/Sonc) SONC

Sulfur Cleanup: (Y/N) N

Date Extracted: 02/01/96

Date Analyzed (1): 02/10/96

Date Analyzed (2): 02/15/96

Time Analyzed (1): 2327

Time Analyzed (2): 2209

Instrument ID (1): HP5890P2

Instrument ID (2): HP5890P1

GC Column (1):DB-1701 ID: 0.53(mm) GC Column (2):RTX-35 ID: 0.53(mm)

THIS METHOD BLANK APPLIES TO THE FOLLOWING SAMPLES, MS AND MSD

	CLIENT	LAB	DATE	DATE
	SAMPLE NO.	SAMPLE ID	ANALYZED 1	ANALYZED 2
	=========		========	========
01	3SS479	960151103	02/13/96	02/16/96
02		960151103DL	02/13/96	02/16/96
03	SS5911	960151102	02/13/96	02/16/96
04	SS5911DL	960151102DL	02/13/96	02/15/96
05	SS5911MS	960151102MS	02/13/96	02/16/96
06	SS5911MSD	960151102MSD	02/14/96	02/16/96
07				
08				
09				
10				
11				
12				
13				
14				
15				
16				
17				
18 19				
20				
21				
22	·			
23				
24				
25				
26				
20		·		

COMMENTS:	

PBLK82

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Lah Code: IEA

Case No.: 1589-126

SDG No.: 01511

fac.ix: (soil/water) SOIL

Lab Sample ID: PBLK82

Sample wt/vol:

30.0 (g/mL) G

Lab File ID: P2020196 148.D

% Moisture: 0

decanted: (Y/N) N

Date Received: / /

Extraction: (SepF/Cont/Sonc) SONC

Date Extracted: 02/01/96

Concentrated Extract Volume: 5000(uL)

Date Analyzed: 02/10/96

Injection Volume: 1.0(uL)

Dilution Factor: 1.0

GPC .Cleanup: (Y/N) Y

pH:

Sulfur Cleanup: (Y/N) N

CONCENTRATION UNITS:

CAS NO.

COMPOUND

(ug/L or ug/Kg) UG/KG

Q

PESTICIDE METHOD BLANK SUMMARY

CLIENT SAMPLE NO.

PBLK92

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Lab Code: IEA Case No.: 1589-126

SDG No.: 01511

Law Sample ID: PBLK92

Lab File ID:

P1021496 039.D

Matrix: (soil/water) SOIL

Extraction: (SepF, Cont/Sonc) SONC

Sulfur Cleanup: (Y/N) N

Date Extracted:

02/09/96

Date Analyzed (1): 02/16/96

Date Analyzed (2): 02/17/96

Time Analyzed (1): 1257

Time Analyzed (2): 0926

Instrument ID (1): HP5890P1

Instrument ID (2): HP5890P2

GC Column (1):RTX-35 ID: 0.53(mm) GC Column (2):DB-1701 ID: 0.53(mm)

THIS METHOD BLANK APPLIES TO THE FOLLOWING SAMPLES, MS AND MSD

	CLIENT	LAB	DATE	DATE
	SAMPLE NO.	SAMPLE ID	ANALYZED 1	ANALYZED 2
01	135155	960212410	02/17/96	02/23/96
02	135155DL	960212410DL	02/20/96	02/23/96
03		960212406	02/17/96	02/25/96
04	485105DL	960212406DL	02/16/96	02/17/96
05	7SS368	960212407	02/16/96	02/17/96
06	7SS368DL	960212407DL	02/16/96	02/17/96
07	8SS368	960212408	02/16/96	02/23/96
80	8SS368DL	960212408DL	02/16/96	02/17/96
09	S51113	960212409	02/17/96	02/23/96
10		960212409DL	02/16/96	02/17/96
11		960212409MS	02/17/96	02/23/96
12		960212409MSD	02/17/96	02/23/96
13		960212411	02/17/96	02/23/96
14	SS368DDL	960212411DL	02/16/96	02/17/96
15				
16				
17				
18				
19				
20 21				
22				
23				
24				
25				
26				
20	۱	ll		

COMMENTS:		

PESTICIDE ORGANICS ANALYSIS DATA SHEET

CLIENT SAMPLE NO.

PBLK92

Lab Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Lab Code: IEA Case No.: 1589-126 SDG No.: 01511

M. ix: (soil/water) SOIL Lab Sample ID: PBLK92

Sample wt/vol: 30.0 (g/mL) G Lab File ID: P1021496 039.D

% Moisture: 0 decanted: (Y/N) N Date Received: / /

Extraction: (SepF/Cont/Sonc) SONC Date Extracted:02/09/96

Concentrated Extract Volume: 5000(uL) Date Analyzed: 02/16/96

Injection Volume: 1.0(uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) Y pH: ____ Sulfur Cleanup: (Y/N) N

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG Q

12674-11-2----Aroclor-1016

11141-16-5Aroclor-1232 53469-21-9Aroclor-1242 12672-29-6Aroclor-1248 11097-69-1Aroclor-1254 11096-82-5Aroclor-1260

IEA Assigned Number Index

Case No.: 1589-126

SDG No.: 01511

IEA Lab Sample Number	Sample Number	Abbreviated Sample Number
9601511-01	ACS-SB110SS4-7'-9'	· 0ss479
9601511-02	ACS-SB112SS5-9'-11'	SS5911
9601511-03	ACS-SB113SS4-7'-9'	3SS479 ·
9601511-21	HB01511	нв
9602124-04	ACS-SB118SS3-6'-8'	888368
9602124-05	ACS-SB119SS3-6'-8'	9SS368
9602124-06	ACS-SB124SS4-8.5'-10.5'	485105
9602124-07	ACS-SB127SS3-6'-8'	7 SS368 ·
9602124-08	ACS-SB128SS3-6'-8'	888368
9602124-09	ACS-SB129SS5-11'-13'	S51113
9602124-10	ACS-SB214SS6-13.5'-15.5'	135155 ·
9602124-11	ACS-SB128SS3-6'-8' DUP	SS368D

1A

VOLATILE ORGANICS ANALYSIS DATA SHEET

CLIENT SAMPLE NO.

ACS-SB142SS3-6'-8'

Lab Name: IEA-NC

Method: SOW 1/91

ab Code: IEA

Case No.: 1589-134

SDG No.: 02301

Matrix: (soil/water) SOIL

Lab Sample ID: 960230101

Sample wt/vol: 4 (g/mL) g

Lab File ID: 0219E03.D

Level: (low/med) MED

Date Received: 02/13/96

% Moisture: not dec. 17

Date Analyzed: 02/19/96

GC Column: DB-624

COMPOSITION

ID: .53(mm)

Dilution Factor: 20.0

Soil Extract Volume: 10000(uL)

Soil Aliquot Volume: 100(uL)

CONCENTRATION UNITS:

CAS NO.	COMPOUND (ug/L or ug/Kg)	ug/kg	Q
		I	
74-87-3	Chloromethane	29000	U
74-83-9	Bromomethane	29000	U
75-01-4	Vinyl Chloride	29000	Ü
75-00-3	Chloroethane	29000	U
75-09-2	Methylene Chloride	29000	Ū
67-64-1	Acetone	29000	U
75-15-0	Carbon Disulfide	29000	Ū
75-35-4	1,1-Dichloroethene	29000	Ū
75-34-3	1,1-Dichloroethane	29000	U
540-59-0	1,2-Dichloroethene (total)	12000	J
67-66-3	Chloroform	29000	U
107-06-2	1,2-Dichloroethane	29000	Ū
78-93-3	2-Butanone	29000	Ū
71-55-6	1,1,1-Trichloroethane	36000	
¥ 56-23-5	Carbon Tetrachloride	29000	U
75-27-4	Bromodichloromethane	29000	U
78-87-5	1,2-Dichloropropane	29000	Ū
10061-01-5	cis-1,3-Dichloropropene	29000	U
79-01-6	Trichloroethene	29000	U
124-48-1	Dibromochloromethane	29000	U
79-00-5	1,1,2-Trichloroethane	29000	U
71-43-2	Benzene	29000	Ū
10061-02-6	Trans-1,3-Dichloropropene	29000	U
75-25-2	Bromoform	29000	U
108-10-1	4-Methyl-2-Pentanone	29000	U
591-78-6	2-Hexanone	29000	U
127-18-4	Tetrachloroethene	29000	U
108-88-3	Toluene	68000	
79-34-5	1,1,2,2-Tetrachloroethane	29000	Ū
108-90-7	Chlorobenzene	29000	U
100-41-4	Ethylbenzene	31000	
100-42-5	Styrene	29000	Ū
1330-20-7	Xylene (total)	200000	

1E

CLIENT SAMPLE NO.

VOLATILE ORGANICS ANALYSIS DATA SHEET TENTATIVELY IDENTIFIED COMPOUNDS

ACS-SB142SS3-6'-8'

Tab Name: IEA-NC

Method: SOW 1/91

_ab Code: IEA

Case No.: 1589-134

SDG No.: 02301

Matrix: (soil/water) SOIL

Lab Sample ID: 960230101

Sample wt/vol: 4 (g/mL)

Lab File ID: 0219E03.D

Level: (low/med) MED

Date Received: 02/13/96

% Moisture: not dec.

Date Analyzed: 02/19/96

GC Column: DB-624

ID: .53(mm)

Dilution Factor: 20.0

Soil Extract Volume: 10000(uL)

Soil Aliquot Volume: 100(uL)

CONCENTRATION UNITS:

Number TICs Found: 10 (ug/L or ug/Kg) ug/kg

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
	DIMETHYLETHYLBENZENE ISOMER	25.07	180000	J
	METHYLMETHYLETHYLBENZENEISOM	25.66	260000	J
	DIMETHYLETHYLBENZENE ISOMER	25.80	360000	J
	SUBSTITUTED BENZENE	26.00	200000	J
	TETRAMETHYLBENZENE ISOMER	26.37	230000	J
	TETRAMETHYLBENZENE ISOMER	26.44	330000	J
	SUBSTITUTED BENZENE	26.66	210000	J
	UNKNOWN PAH	26.83	220000	J
	UNKNOWN PAH	27.08	470000	J
	SUBSTITUTED BENZENE	27.69	280000	J
<u> </u>				
 				
<u> </u>				
}				
	<u> </u>			
	<u> </u>			
}				

1A

VOLATILE ORGANICS ANALYSIS DATA SHEET

CLIENT SAMPLE NO.

ACS-SB143SS3-6'-8'

Tab Name: IEA-NC

Method: SOW 1/91

_ab Code: IEA

Case No.: 1589-134

SDG No.: 02301

Matrix: (soil/water) SOIL

Lab Sample ID: 960230102

Sample wt/vol: 4 (g/mL)

Lab File ID: 0219513.D

Level: (low/med) MED

Date Received: 02/13/96

% Moisture: not dec. 23 Date Analyzed: 02/19/96

GC Column: DB-624

ID: .53(mm)

Dilution Factor: 1.0

Soil Extract Volume:

10000(uL)

Soil Aliquot Volume: 100(uL)

CONCENTRATION UNITS:

CAS NO.		g/L or ug/Kg)	ug/kg	Q
74-87-3	Chloromethane		1600	U
74-83-9	Bromomethane		1600	บ
75-01-4	Vinyl Chloride		1600	U
75-00-3	Chloroethane		1600	U
75-09-2	Methylene Chloride		1600	U
67-64-1	Acetone		1600	U
75-15-0	Carbon Disulfide		1600	U
75-35-4	1,1-Dichloroethene		1600	U
75-34-3	1,1-Dichloroethane		1600	U
540-59-0	1,2-Dichloroethene (total)		1600	Ū
67-66-3	Chloroform		1600	U
107-06-2	1,2-Dichloroethane		1600	U
78-93-3	2-Butanone		1600	U
/1-55-6	1,1,1-Trichloroethane		1600	U
56-23-5	Carbon Tetrachloride		1600	U
75-27-4	Bromodichloromethane		1600	Ū
78-87-5	1,2-Dichloropropane		1600	Ū
10061-01-5	cis-1,3-Dichloropropene		1600	Ū
79-01-6	Trichloroethene		1600	Ū
124-48-1	Dibromochloromethane		1600	U
79-00-5	1,1,2-Trichloroethane		1600	U
71-43-2	Benzene		1600	U
10061-02-6	Trans-1,3-Dichloropropene		1600	Ū
75-25-2	Bromoform		1600	U
108-10-1	4-Methyl-2-Pentanone		1600	Ü
591-78-6	2-Hexanone		1600	Ü
127-18-4	Tetrachloroethene		760	J
108-88-3	Toluene		1600	Ū
79-34-5	1,1,2,2-Tetrachloroethane		1600	Ū
108-90-7	Chlorobenzene		1600	Ü
100-41-4	Ethylbenzene		1600	U
100-42-5	Styrene		1600	Ū
1330-20-7	Xylene (total)		1600	Ü

1E

CLIENT SAMPLE NO.

VOLATILE ORGANICS ANALYSIS DATA SHEET TENTATIVELY IDENTIFIED COMPOUNDS

ACS-SB143SS3-6'-8'

Tab Name: IEA-NC

Method: SOW 1/91

_ab Code: IEA

Case No.: 1589-134

SDG No.: 02301

Matrix: (soil/water) SOIL

Lab Sample ID: 960230102

Sample wt/vol: 4 (g/mL) g

Lab File ID: 0219513.D

Level: (low/med) MED

Date Received: 02/13/96

% Moisture: not dec. 23 Date Analyzed: 02/19/96

GC Column: DB-624

.53 (mm) ID:

Dilution Factor: 1.0

Soil Extract Volume: 10000(uL)

Soil Aliquot Volume: 100(uL)

CONCENTRATION UNITS: (ug/L or ug/Kg) ug/kg

Number TICs Found: 10

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
	UNKNOWN BRANCHED ALKANE	22.04	3200	J
·	UNKNOWN BRANCHED ALKANE	24.54	2900	J
	DIMETHYLNAPHTHALENE ISOMER	25.92	4400	J
	DIMETHYLNAPHTHALENE ISOMER	26.43	4200	J
	UNKNOWN BRANCHED ALKANE	26.61	5100	J
	DIMETHYLNAPHTHALENE ISOMER	27.09	3300	J
002027-17-0	NAPHTHALENE, 2-(1-METHYLETHY	29.10	5800	JN
	TRIMETHYLNAPHTHALENE ISOMER	30.05	4100	J
	TRIMETHYLNAPHTHALENE ISOMER	30.25	4400	J
	UNKNOWN ALKANE	30.49	2900	J
···				
				
······································		·		·
		 		
		 		
	<u> </u>	 		
		 		
		 		
		 		
		 	 	
		 		
	<u> </u>	1	1	

1A

VOLATILE ORGANICS ANALYSIS DATA SHEET

CLIENT SAMPLE NO.

ACS-SB143SS3-6'-8' D

Tab Name: IEA-NC

Method: SOW 1/91

سه Code: IEA

Case No.: 1589-134

SDG No.: 02301

Matrix: (soil/water) SOIL

Lab Sample ID: 960230103

Sample wt/vol: 4 (g/mL)

Lab File ID: 0219514.D

Level: (low/med) MED

Date Received: 02/13/96

% Moisture: not dec. 20 Date Analyzed: 02/19/96

GC Column: DB-624

ID: .53 (mm) Dilution Factor: 1.0

Soil Extract Volume: 10000(uL)

Soil Aliquot Volume:

100(uL)

CONCENTRATION UNITS:

CAS NO.		ug/L or	ug/kg	Q
74-87-3	Chloromethane		1500	מ
74-83-9	Bromomethane		1500	U
75-01-4	Vinyl Chloride		1500	U
75-00-3	Chloroethane		1500	U
75-09-2	Methylene Chloride		1500	Ü
37-64-1	Acetone		 1500	U
75-15-0	Carbon Disulfide		1500	U
75-35-4	1,1-Dichloroethene		1500	U
75-34-3	1,1-Dichloroethane		 1500	ט
540-59-0	1,2-Dichloroethene (total)	1500	U
67-66-3	Chloroform		1500	Ü
107-06-2	1,2-Dichloroethane		1500	U
78-93-3	2-Butanone		1500	U
1-55-6	1,1,1-Trichloroethane		1500	U
56-23-5	Carbon Tetrachloride		1500	<u> </u>
75-27-4	Bromodichloromethane		1500	U
78-87-5	1,2-Dichloropropane		1500	Ū
10061-01-5	cis-1,3-Dichloropropene		1500	U
79-01-6	Trichloroethene		1500	U
124-48-1	Dibromochloromethane		1500	U
79-00-5	1,1,2-Trichloroethane		1500	U
71-43-2	Benzene		1500	U
10061-02-6	Trans-1,3-Dichloropropene		1500	Ū
75-25-2	Bromoform		1500	Ū
108-10-1	4-Methyl-2-Pentanone		1500	U
591-78-6	2-Hexanone		1500	Ū
127-18-4	Tetrachloroethene		690	J
108-88-3	Toluene		1500	Ū
79-34-5	1,1,2,2-Tetrachloroethane	;	1500	U
108-90-7	Chlorobenzene		1500	U
100-41-4	Ethylbenzene		 1500	Ū
100-42-5	Styrene		1500	U
1330-20-7	Xylene (total)		1500	U

1E

CLIENT SAMPLE NO.

VOLATILE ORGANICS ANALYSIS DATA SHEET TENTATIVELY IDENTIFIED COMPOUNDS

ACS-SB143SS3-6'-8' D

Tab Name: IEA-NC

Method: SOW 1/91

SDG No.: 02301

_ab Code: IEA

Case No.: 1589-134

Matrix: (soil/water) SOIL

Lab Sample ID: 960230103

Sample wt/vol: 4 (g/mL) g

Lab File ID: 0219514.D

Level: (low/med) MED

Date Received: 02/13/96

% Moisture: not dec. 20

Date Analyzed: 02/19/96

GC Column: DB-624

ID: .53(mm) Dilution Factor: 1.0

Soil Extract Volume: 10000(uL)

Soil Aliquot Volume: 100(uL)

CONCENTRATION UNITS: (ug/L or ug/Kg) ug/kg

Number TICs Found: 10

RTEST. CONC. CAS NUMBER COMPOUND NAME 0 UNKNOWN BRANCHED ALKANE 22.00 2600 J 1800 22.54 UNKNOWN BRANCHED ALKANE J UNKNOWN BRANCHED ALKANE 23.32 2200 J UNKNOWN ALKANE 23.88 2200 J UNKNOWN BRANCHED ALKANE 24.99 1700 J 26.14 UNKNOWN 1600 26.51 UNKNOWN PAH 1600 J UNKNOWN BRANCHED ALKANE 26.62 3700 J TRIMETHYLNAPHTHALENE ISOMER 27.32 1900 J 32.71 DIMETHYLNAPHTHALENE ISOMER 1900

1A

VOLATILE ORGANICS ANALYSIS DATA SHEET

CLIENT SAMPLE NO.

VBLK5F

The Name: IEA-NC

Method: SOW 1/91

⊥ab Code: IEA

Case No.: 1589-134

SDG No.: 02301

Matrix: (soil/water) SOIL

Lab Sample ID: VBLK5F

Sample wt/vol: 4 (g/mL)

Level: (low/med) MED

Lab File ID: 0219503.D

Date Received:

% Moisture: not dec.

Date Analyzed: 02/19/96

GC Column: DB-624

ID: .53(mm)

Dilution Factor: 1.0

Soil Extract Volume: 10000(uL)

Soil Aliquot Volume: 100(uL)

CONCENTRATION UNITS:

CAS NO.		(ug/L or ug/Kg)	ug/kg	Q
74-87-3	Chloromethane		1200	ט
74-83-9	Bromomethane		1200	U
75-01-4	Vinyl Chloride		1200	0
75-00-3	Chloroethane		1200	U
75-09-2	Methylene Chloride		1200	U
67-64-1	Acetone		1200	U
75-15-0	Carbon Disulfide		1200	U
75-35-4	1,1-Dichloroethene		1200	<u></u>
75-34-3	1,1-Dichloroethane		1200	0
540-59-0	1,2-Dichloroethene (total	3	1200	Ü
67-66-3	Chioroform		1200	Ū
107-06-2	1,2-Dichloroethane		1200	U
78-93-3	2-Butanone		1200	U
1-55-6	1,1,1-Trichloroethane		1200	U
56-23-5	Carbon Tetrachloride		1200	Ū
75-27-4	Bromodichloromethane		1200	U
78-87-5	1,2-Dichloropropane		1200	Ū
10061-01-5	cis-1,3-Dichloropropene		1200	U
79-01-6	Trichloroethene		1200	U
124-48-1	Dibromochloromethane		1200	U
79-00-5	1,1,2-Trichloroethane		1200	U
71-43-2	Benzene		1200	U
10061-02-6	Trans-1,3-Dichloropropene		1200	U
75-25-2	Bromoform		1200	Ü
108-10-1	4-Methyl-2-Pentanone		1200	U
591-78-6	2-Hexanone		1200	U
127-18-4	Tetrachloroethene		1200	Ū
108-88-3	Toluene		1200	Ü
79-34-5	1,1,2,2-Tetrachloroethane		1200	U
108-90-7	Chlorobenzene		1200	Ü
100-41-4	Ethylbenzene		1200	Ū
100-42-5	Styrene		1200	Ū
1330-20-7	Xylene (total)		1200	Ū

1E

CLIENT SAMPLE NO.

VOLATILE ORGANICS ANALYSIS DATA SHEET TENTATIVELY IDENTIFIED COMPOUNDS

VBLK5F

Tab Name: IEA-NC

Method: SOW 1/91

Lub Code: IEA

Case No.: 1589-134

SDG No.: 02301

Matrix: (soil/water) SOIL

Lab Sample ID: VBLK5F

Sample wt/vol: 4 (g/mL)

Lab File ID: 0219503.D

Level: (low/med) MED Date Received:

% Moisture: not dec.

Date Analyzed: 02/19/96

GC Column: DB-624

ID: .53 (mm) Dilution Factor: 1.0

Soil Extract Volume:

10000(uL)

Soil Aliquot Volume: 100(uL)

CONCENTRATION UNITS:

Number TICs Found: 0 (ug/L or ug/Kg) ug/kg CAS NUMBER COMPOUND NAME EST. CONC.

CAS NUMBER	COMPOUND NAME	RI	EST. CONC.	<u>Q</u>
			 	
			 	
				
			 	
			 	
			 -	
			 	
			 	
			 	
			†~~ ~~	
			t	
			 	
			† †	
			 -	
			· · · · · · · · · · · · · · · · · · ·	

1A

VOLATILE ORGANICS ANALYSIS DATA SHEET

CLIENT SAMPLE NO.

VBLK5H

Tab Name: IEA-NC

Method: SOW 1/91

_ub Code: IEA

Case No.: 1589-134

SDG No.: 02301

Matrix: (soil/water) SOIL

Lab Sample ID: VBLK5H

Sample wt/vol: 4 (g/mL)

Lab File ID: 0219E02.D

Level: (low/med) MED Date Received:

Date Analyzed: 02/19/96

GC Column: DB-624

% Moisture: not dec.

ID: .53 (mm) Dilution Factor: 1.0

Soil Extract Volume: 10000(uL)

Soil Aliquot Volume: 100(uL)

CONCENTRATION UNITS:

CAS NO. COMPOUND (ug/L or ug/Kg) ug/kg Q

74-87-3	Chloromethane	1200	ប
74-83-9	Bromomethane	1200	- ŏ -
75-01-4	Vinyl Chloride	1200	- ŏ -
75-00-3	Chloroethane	1200	Ŭ
75-09-2	Methylene Chloride	1200	$\overline{\overline{U}}$
57-64-1	Acetone	1200	— <u>ŏ</u> −
75-15-0	Carbon Disulfide	1200	$-\ddot{\mathbf{v}}$
75-35-4	1,1-Dichloroethene	1200	Ü
75-34-3	1,1-Dichloroethane	1200	- 0
540-59-0	1,2-Dichloroethene (total)	1200	- 0
67-66-3	Chloroform	1200	~~~
107-06-2	1,2-Dichloroethane	1200	$\frac{1}{0}$
78-93-3	2-Butanone	1200	- 0 -
1-55-6		1200	_ Ŭ _
56-23-5	1,1,1-Trichloroethane Carbon Tetrachloride	1200	- 6
75-27-4	Bromodichloromethane	1200	
78-87-5		1200	- 0
10061-01-5	1,2-Dichloropropane	1200	
79-01-6	cis-1,3-Dichloropropene Trichloroethene	1200	U
124-48-1		1200	$-\ddot{\mathbf{v}}$
79-00-5	Dibromochloromethane	1200	- 0
71-43-2	1,1,2-Trichloroethane		- 0
10061-02-6	Benzene	1200	- 0
75-25-2	Trans-1,3-Dichloropropene	1200	
	Bromoform	1200	- U
108-10-1	4-Methyl-2-Pentanone	1200	
591-78-6	2-Hexanone	1200	Ü
127-18-4	Tetrachloroethene	1200	Ü
108-88-3	Toluene	1200	Ü
79-34-5	1,1,2,2-Tetrachloroethane	1200	U
108-90-7	Chlorobenzene	1200	Ü
100-41-4	Ethylbenzene	1200	U
100-42-5	Styrene	1200	Ŭ
1330-20-7	Xylene (total)	1200	Ü

1E

CLIENT SAMPLE NO.

VOLATILE ORGANICS ANALYSIS DATA SHEET TENTATIVELY IDENTIFIED COMPOUNDS

VIATIVEDI IDENITITED COMPOUNDS VBL

Case No.: 1589-134

VBLK5H

Tab Name: IEA-NC

Lub Code: IEA

IEA-NC Method: SOW 1/91

SDG No.: 02301

Matrix: (soil/water) SOIL

Lab Sample ID: VBLK5H

Sample wt/vol: 4 (g/mL) g

Lab File ID: 0219E02.D

Level: (low/med) MED

Date Received:

% Moisture: not dec. 0

Number TICs Found: 10

Date Analyzed: 02/19/96

GC Column: DB-624

ID: .53(mm)

Dilution Factor: 1.0

Soil Extract Volume: 10000(uL)

Soil Aliquot Volume: 100(uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) ug/kg

=				
CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
	Unknown	25.87	940	J
	Unknown Pah	26.26	850	J
002027-17-	O NAPHTHALENE, 2-(1-METHYLETHY	26.51	2600	JN
	TRIMETHYLNAPHTHALENE ISOMER	26.94	1100	J
	TRIMETHYLNAPHTHALENE ISOMER	27.34	4200	J
	TRIMETHYLNAPHTHALENE ISOMER	27.54	4200	J
	TRIMETHYLNAPHTHALENE ISOMER	28.25	2400	J
	TRIMETHYLNAPHTHALENE ISOMER	28.53	2600	J
	TRIMETHYLNAPHTHALENE ISOMER	29.02	730	J
	TRIMETHYLNAPHTHALENE ISOMER	29.19	2900	J
· · · · · · · · · · · · · · · · · · ·				
			··-	
		 		
		·		
		 		
		 		
		ļ		
	 	 		
		 		
		 		
	+	ļ.———		
		 		
		 		
		 		
		 	 	
		-		
		ļ		
	<u> </u>	<u> </u>	L	

1A

VOLATILE ORGANICS ANALYSIS DATA SHEET

CLIENT SAMPLE NO.

ACS-SB142SS3-6'-8'MS

'ab Name: IEA-NC

Method: SOW 1/91

_ab Code: IEA

Case No.: 1589-134

SDG No.: 02301

Matrix: (soil/water) SOIL

Lab Sample ID: 960230101MS

Sample wt/vol: 4 (g/mL) g

Lab File ID: 0219E04.D

Level: (low/med) MED

Date Received: 02/13/96

% Moisture: not dec. 17

Date Analyzed: 02/19/96

GC Column: DB-624

ID: .53(mm) Dilution Factor: 20.0

Soil Extract Volume: 10000(uL)

Soil Aliquot Volume: 100(uL)

CONCENTRATION UNITS:

CAS NO.	COMPOUND (ug/L or ug/Kg)	ug/kg	Q
54.05.0			
74-87-3	Chloromethane	29000	<u> </u>
74-83-9	Bromomethane	29000	Ü
75-01-4	Vinyl Chloride	29000	Ü
75-00-3	Chloroethane	29000	Ü
75-09-2	Methylene Chloride	29000	Ü
67-64-1	Acetone	29000	Ü
75-15-0	Carbon Disulfide	29000	Ü
75-35-4	1,1-Dichloroethene	14000	J
75-34-3	1,1-Dichloroethane	29000	Ü
540-59-0	1,2-Dichloroethene (total)	12000	J
67-66-3	Chloroform	29000	<u> </u>
107-06-2	1,2-Dichloroethane	29000	U
78-93-3	2-Butanone	29000	U
1-55-6	1,1,1-Trichloroethane	34000	
56-23-5	Carbon Tetrachloride	29000	υ
75-27-4	Bromodichloromethane	29000	U
78-87-5	1,2-Dichloropropane	29000	U
10061-01-5	cis-1,3-Dichloropropene	29000	U
79-01-6	Trichloroethene	12000	J
124-48-1	Dibromochloromethane	29000	U
79-00-5	1,1,2-Trichloroethane	29000	U
71-43-2	Benzene	16000	J
10061-02-6	Trans-1,3-Dichloropropene	29000	Ū
75-25-2	Bromoform	29000	U
108-10-1	4-Methyl-2-Pentanone	29000	U
591-78-6	2-Hexanone	29000	<u> </u>
127-18-4	Tetrachloroethene	29000	U
108-88-3	Toluene	75000	
79-34-5	1,1,2,2-Tetrachloroethane	29000	U
108-90-7	Chlorobenzene	13000	Ĵ
100-41-4	Ethylbenzene	28000	J
100-42-5	Styrene	29000	Ū
1330-20-7	Xylene (total)	180000	<u>_</u>

1A

VOLATILE ORGANICS ANALYSIS DATA SHEET

CLIENT SAMPLE NO.

0

ACS-SB142SS3-6'-8'MSD

Tab Name: IEA-NC

Method: SOW 1/91

_ab Code: IEA

Case No.: 1589-134

SDG No.: 02301

Matrix: (soil/water) SOIL

Lab Sample ID: 960230101MSD

Sample wt/vol: 4 (g/mL) g

COMPOUND

Lab File ID: 0219E05.D

Level: (low/med) MED

Date Received: 02/13/96

% Moisture: not dec. 17

Date Analyzed: 02/20/96

GC Column: DB-624

CAS NO.

ID: .53 (mm) Dilution Factor: 20.0

Soil Extract Volume: 10000(uL)

Soil Aliquot Volume: 100(uL)

CONCENTRATION UNITS: ug/kg

(ug/L or ug/Kg)

74-87-3 Chloromethane 29000 U 74-83-9 Bromomethane 29000 U 75-01-4 Vinyl Chloride Ū 29000 75-00-3 Chloroethane 29000 U Methylene Chloride 75-09-2 29000 Ū 37-64-1 Acetone 29000 U Carbon Disulfide *1*5-15-0 29000 U 1,1-Dichloroethene 75-35-4 12000 J 1,1-Dichloroethane 75-34-3 29000 Ħ 540-59-0 1,2-Dichloroethene (total) 12000 J 67-66-3 Chloroform 29000 IJ 1,2-Dichloroethane 107-06-2 <u> 29000</u> ŦŤ 78-93-3 2-Butanone 29000 Ū 1,1,1-Trichloroethane 71-55-6 34000 56-23-5 Carbon Tetrachloride 29000 Bromodichloromethane 75-27-4 29000 Ħ 78-87-5 1,2-Dichloropropane 29000 Ū cis-1,3-Dichloropropene Trichloroethene 29000 10061-01-5 Ū 79-01-6 13000 29000 124-48-1 Dibromochloromethane U 1,1,2-Trichloroethane 29000 79-00-5 U 71-43-2 Benzene 16000 J 10061-02-6 Trans-1,3-Dichloropropene 29000 Ū 29000 75-25-2 Bromoform u 4-Methyl-2-Pentanone 108-10-1 29000 Ħ 591-78-6 2-Hexanone 29000 Ü 127-18-4 Tetrachloroethene 5400 J 76000 108-88-3 Toluene 1,1,2,2-Tetrachloroethane Ū 79-34-5 29000 Chlorobenzene 108-90-7 12000 J 100-41-4 Ethylbenzene 29000 J 100-42-5 Styrene 29000 Ū 1330-20-7 Xylene (total) 190000

2B SOIL VOLATILE SYSTEM MONITORING COMPOUND RECOVERY

Tab Name: IEA-NC

Method: SOW 1/91

__ab Code: IEA

Case No.: 1589-134

SDG No.: 02301

Level: (low/med) MED

CLIENT SAMPLE NO. SMC1 (TOL) # (BFB) # (DCE) # OTHER TOL (DCE) # OTHER T	_
01 VBLK5F 02 ACS-SB143SS3-6'-8' 03 ACS-SB143SS3-6'-8' D 04 VBLK5H 05 ACS-SB142SS3-6'-8' B 06 ACS-SB142SS3-6'-8'MS 07 ACS-SB142SS3-6'-8'MS 09 D 10 D 10 D 11 D 11 D 11 D 11 D 11 D 11	
02 ACS-SB143SS3-6'-8' 101 97 104 03 ACS-SB143SS3-6'-8' D 100 103 04 VBLK5H 98 101 106 05 ACS-SB142SS3-6'-8' 98D 100D 102D 06 ACS-SB142SS3-6'-8'MS 98D 101D 104D 07 ACS-SB142SS3-6'-8'MSD 98D 100D 107D 08 09 10 10 10 10 11 12 13 14 15 16 17 18 19 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10 10	T
02 ACS-SB143SS3-6'-8' 101 97 104 03 ACS-SB143SS3-6'-8' D 100 100 103 04 VBLK5H 98 101 106 05 ACS-SB142SS3-6'-8' 98D 100D 102D 06 ACS-SB142SS3-6'-8'MS 98D 101D 104D 07 ACS-SB142SS3-6'-8'MSD 98D 100D 107D 08 09 10 11 12 13 14 15 16 17 18 19	
03	0
04 VBLK5H 98 101 106 05 ACS-SB142SS3-6'-8' 98D 100D 102D 06 ACS-SB142SS3-6'-8'MS 98D 101D 104D 07 ACS-SB142SS3-6'-8'MSD 98D 100D 107D 08 09 10 11 12 13 14 15 16 17 18 19	0
05 ACS-SB142SS3-6'-8' 98D 100D 102D 06 ACS-SB142SS3-6'-8'MS 98D 101D 104D 07 ACS-SB142SS3-6'-8'MSD 98D 100D 107D 08 09 09 00 00 00 00 00 00 00 00 00 00 00	0
06 ACS-SB142SS3-6'-8'MS 98D 101D 104D 07 ACS-SB142SS3-6'-8'MSD 98D 100D 107D 08 09 09 00 00 00 00 00 00 00 00 00 00 00	0
07 ACS-SB142SS3-6'-8'MSD 98D 100D 107D 08 09 10 11 12 13 14 15 16 17 18 19	0
08 09 10 11 12 13 14 15 16 17 18	0
09 10 11 12 13 14 15 16 17 18 19	Ō
10 11 12 13 14 15 16 17 18	
11 12 13 14 15 16 17 18	
12 13 14 15 16 17 18 19	
13 14 15 16 17 18 19	
14 15 16 17 18 19	
15 16 17 18 19	
15 16 17 18 19	
16 17 18 19	\neg
17 18 19	$\neg \neg$
18	
19	
	\neg
21	
22	\dashv
23	\dashv
24	
25	
26	
27	
28	
29	
30	

QC LIMITS

SMC1 (TOL) = Toluene-d8 (84-138) SMC2 (BFB) = Bromofluorobenzene (59-113) SMC3 (DCE) = 1,2-Dichloroethane-d4 (70-121)

- # Column to be used to flag recovery values
- * Values outside of QC limits.
- D System Monitoring Compound diluted out

page 1 of 1

FORM II VOA-2

3B SOIL VOLATILE MATRIX SPIKE/MATRIX SPIKE DUPLICATE RECOVERY

Tab Name: IEA-NC

Method: SOW 1/91

⊥ab Code: IEA

Case No.: 1589-134

SDG No.: 02301

Matrix Spike - Client Sample No.: ACS-SB142SS3-6'-8' Level: (low/med) MED

COMPOUND	SPIKE ADDED (ug/Kg)	SAMPLE CONCENTRATION (ug/Kg)	MS CONCENTRATION (ug/Kg)	MS % REC	#	QC. LIMITS REC.
1,1-Dichloroethene	7500	0	14000	187	D	59-172
Trichloroethene	7500	0	12000	160	D	62-137
Benzene	7500	0	16000	213	D	66-142
Toluene	7500	68000	75000	93	D	59-139
Chlorobenzene	7500	0	13000	173	D	60-133

COMPOUND	SPIKE ADDED (ug/Kg)	MSD CONCENTRATION (ug/Kg)	MSD % REC #	% RPD #	QC L RPD	IMITS REC.
1,1-Dichloroethene	7500	12000	160 D	16	22	59-172
Trichloroethene	7500	13000	173 D	8	24	62-137
Benzene	7500	16000	213 D	0	21	66-142
Toluene	7500	76000	107 D	14	21	59-139
Chlorobenzene	7500	12000	160 D	8	21	60-133

- # Column to be used to flag recovery and RPD values with an asterisk
- * Values outside of QC limits.
- D Spike compound diluted out.

RPD: 0 out of 5 outside limits

Spike Recovery: 7 out of 10 outside limits

COMMENTS:	

4A VOLATILE METHOD BLANK SUMMARY

CLIENT SAMPLE NO.

VBLK5F	
--------	--

b Name: IEA-NC

Method: SOW 1/91

Lab Code: IEA

Case No.: 1589-134

SDG No.: 02301

Lab File ID: 0219503.D

Lab Sample ID: VBLK5F

Date Analyzed: 02/19/96

Time Analyzed: 09:38

GC Column: DB-624 ID: .53(mm) Heated Purge: (Y/N) N

Instrument ID: MSD5

THIS METHOD BLANK APPLIES TO THE FOLLOWING SAMPLES, MS AND MSD:

	CLIENT SAMPLE NO.	LAB SAMPLE ID	LAB FILE ID	TIME ANALYZED
	ACS-SB143SS3-6'-8'	960230102	0219513.D	16:54
02 03	ACS-SB143SS3-6'-8' D	960230103	0219514.D	17:35
04				
05				
06		 		
07				
08 09			 	
יפט				
				
46				
13				
14 15				
16				
17				
18				
-				
20				
21 22				
23				
24				
25				
26				
27 28				
29				
30				

COMMENTS:	

page 1 of 1

4A VOLATILE METHOD BLANK SUMMARY

CLIENT SAMPLE NO.

VBLK5H		

b Name: IEA-NC

Method: SOW 1/91

Lab Code: IEA

Case No.: 1589-134

SDG No.: 02301

Lab File ID: 0219E02.D

Lab Sample ID: VBLK5H

Date Analyzed: 02/19/96

Time Analyzed: 21:34

GC Column: DB-624 ID: .53(mm)

Heated Purge: (Y/N) N

Instrument ID: MSD5

THIS METHOD BLANK APPLIES TO THE FOLLOWING SAMPLES, MS AND MSD:

	CLIENT SAMPLE NO.	LAB SAMPLE ID	LAB FILE ID	TIME ANALYZED
01	ACS-SB142SS3-6'-8'	960230101	0219E03.D	22:26
02	ACS-SB142SS3-6'-8'MS	960230101MS	0219E04.D	23:25
03	ACS-SB142SS3-6'-8'MSD	960230101MSD	0219E05.D	00:05
04				
05				
06				
07				
80				
09				
חר				
1				
13				
14				
15 16				
17				
18				
19				{
20				
21				
22		ļ		
23				
24				
25				
26				
27			<u> </u>	
28				
29			 	
30			 	
20			 	
		<u> </u>	l	L

COMMENTS:	

page 1 of 1

8A VOLATILE INTERNAL STANDARD AREA AND RT SUMMARY

Tab Name: IEA-NC

Method: SOW 1/91

مم Code: IEA

Case No.: 1589-134

SDG No.: 02301

Lab File ID (Standard): 0219501.D

Date Analyzed: 02/19/96

Instrument ID: MSD5

Time Analyzed: 07:54

GC Column: DB-624 ID: .53(mm)

Heated Purge: (Y/N) N

	IS1(BCM)		IS2 (DFB)	 	IS3 (CBZ)	
	AREA #	RT #	AREA #	RT #	AREA #	RT #
12 HOUR STD	637601	10.26	2325780	12.44	1957828	18.72
UPPER LIMIT LOWER LIMIT	1275202 318800	10.76 9.76	4651560 1162890	12.94 11.94	3915656 978914	19.22 18.22
EPA SAMPLE NO.						
1 VBLK5F	686565	10.26	2645179	12.45	2139193	18.76
ACS-SB143SS3-6'-8'	712404	10.29	2746431	12.48	2250829	18.76
3 ACS-SB143SS3-6'-8' D	699235	10.27	2684784	12.45	2214927	18.73
04				<u> </u>		L
05						
07						
\(\frac{1}{2}\)						L <u>-</u>
3						
4						
15						
6						
.81						
9						
20						
21						
.2						

IS1 (BCM) = Bromochloromethane

IS2 (DFB) = 1,4-Difluorobenzene

IS3 (CBZ) = Chlorobenzene-d5

AREA UPPER LIMIT = +100% of internal standard area AREA LOWER LIMIT = - 50% of internal standard area

RT UPPER LIMIT = +0.50 minutes of internal standard RT RT LOWER LIMIT = -0.50 minutes of internal standard RT

Column used to flag values outside QC limits with an asterisk.

* Values outside of QC limits.

re 1 of 1

8A VOLATILE INTERNAL STANDARD AREA AND RT SUMMARY

Tab Name: IEA-NC

Method: SOW 1/91

_ab Code: IEA

Case No.: 1589-134

SDG No.: 02301

Lab File ID (Standard): 0219E01.D

Date Analyzed: 02/19/96

Instrument ID: MSD5

Time Analyzed: 20:41

GC Column: DB-624 ID: .53(mm)

Heated Purge: (Y/N) N

	IS1 (BCM)		TC2 (DEBY		TC2/0071	
1	AREA #	RT#	IS2(DFB) AREA #	RT #	IS3(CBZ) AREA #	RT #
	AREA #	K1 #	AREA #	KI #	AREA #	KI #
12 HOUR STD	779162	10.33	2801133	12.49	2324722	18.76
UPPER LIMIT	1558324	10.83	5602266	12.99	4649444	19.26
LOWER LIMIT	389581	9.83	1400566	11.99	1162361	18.26
EPA SAMPLE						
NO.						
VBLK5H	784543	10.31	2978764	12.49	2443947	18.77
)2 ACS-SB142SS3-6'-8'	795935	10.31	2934452	12.49	2468671	18.78
3 ACS-SB142SS3-6'-8'MS	763438	10.32	2829419	12.49	2408820	18.78
04 ACS-SB142SS3-6'-8'MSD	751689	10.29	2841435	12.47	2407546	18.77
05						
06						
07						
18						
				~		
ıí						
						
3						
14						
L5						1
16						
17						
L8						
.9						
20						
21						
22	<u> </u>				l	

IS1 (BCM) = Bromochloromethane

IS2 (DFB) = 1,4-Difluorobenzene

IS3 (CBZ) = Chlorobenzene-d5

AREA UPPER LIMIT = +100% of internal standard area AREA LOWER LIMIT = - 50% of internal standard area

RT UPPER LIMIT = +0.50 minutes of internal standard RT RT LOWER LIMIT = -0.50 minutes of internal standard RT

Column used to flag values outside QC limits with an asterisk.

* Values outside of QC limits.

je 1 of 1

(1)	IONTGOME	RY WAT	SON	C	CHAIN	OF C	JS1	ΓΟΙ	DΥ	RE	EC	OR	D		-		INSTR	,		2 WEE	
SAMPLER(S)	thith	1:1	2-1	7,60,	Mrs.		OF CONTAINERS	No.	100	20°			<i>//</i>	<i> </i>	/ /			ا بران		LAB USE	ONLY
COLLECTION DATE	COLLECTION TIME	COMP	<i>)</i>	SAMI	PLE ID		Š	V	$\sqrt{\mathcal{E}}$					Ι.		17,89	REMARKS	V.	MAT	RIX	LAB NO.
164.	1110	X	ACS-5814	12-553-	6-8		1	X								9.59	1174	5 pr-10			 -
1.66:	1335	1 X	ACS-SBI	43 SS 3	-6-8		1	X								420	1	Diplice	ήţ		
4610		X	ACS-SB				1/		X		j.					9796	14	•			
26.61	1345	X	ACS-SB	<u> 43554</u>	1-8/2-	10/2	11	<u> </u>	X							9.59	(4 5"				
		<u> </u>					Ш	<u> </u>													
		ļ			<u> </u>		#	ļ	<u> </u>		<u> </u>										
	ļ	ļ		·			∦	<u> </u>													
		ļ	-~				 	 	ļ		L_					- 8	·				
1 7		-		<u>.</u>				<u> </u>			<u> </u>	<u> </u>									
	ļ						╂	ļ	ļ		<u> </u>							<u>, (</u>			
0050111 1110	TOUGTIONS	<u> </u>	L				Щ	<u>† </u>			<u> </u>										
SPECIAL INS	THUCTIONS:	COC	Soul H	5 92.	クッカナ	RECEIVED:	דאו 🗀	ACT		ON IC	E 1	TEMP		0	F		PROJ.	MGR.: <u>* ア</u> ゲ	VIK I	<u>~</u>	
	KUN	D_{ij}	hide o	~ }	# 9.29	9853 C 14514	(. ! 	/ ? :<	Inc	· ,> c	y ^ *	teg	<i>‡</i> {	9-2	981	2					
	/ sic	ANATURE	1111		1	PRINT NAM	ME.		1					С	OMP	ANY / TITL	E.			DATE	TIME
RELINQUISH	ED BY: /	40	1.1.1		Davio	Pien	6.10	er.		Max	190	MIL	 ا ما	7.		1,44	8 25 July 2	60,00		140	12 1
RECEIVED BY	Y:												,		,						-
					1				Т											ł	1

C-O-C No. 010573

RELINQUISHED BY: RECEIVED BY:

NAME OF COURIER:

SPECIAL

JRNAROUND

PBLK06

Q

Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Lab Code: IEA Case No.: 1589-134 SDG No.: 02301

Matrix: (soil/water) SOIL Lab Sample ID: PBLK06

Sample wt/vol: 30.0 (g/mL) G Lab File ID: P4030296 147.D

% Moisture: 0 decanted: (Y/N) N Date Received: / /

Extraction: (SepF/Cont/Sonc) SONC Date Extracted: 02/21/96

Concentrated Extract Volume: 5000(uL) Date Analyzed: 03/08/96

Injection Volume: 1.0(uL) Dilution Factor: 1.0

COMPOUND

CAS NO.

GPC Cleanup: (Y/N) Y pH: ____ Sulfur Cleanup: (Y/N) N

CONCENTRATION UNITS: (ug/L or ug/Kg) UG/KG

12674-11-2----Aroclor-1016 33 U 11104-28-2----Aroclor-1221 67 U 11141-16-5----Aroclor-1232 33 U 53469-21-9----Aroclor-1242 33 U 12672-29-6----Aroclor-1248 33 U 11097-69-1-----Aroclor-1254 33 U 11096-82-5----Aroclor-1260 33 U

PESTICIDE ORGANICS ANALYSIS DATA SHEET

CLIENT SAMPLE NO.

3SS3P

> Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Lab Code: IEA Case No.: 1589-134

SDG No.: 02301

Matrix: (soil/water) SOIL

Lab Sample ID: 960230104

Sample wt/vol:

30.1 (g/mL) G

Lab File ID: P4030296 150.D

% Moisture: 18

decanted: (Y/N) N

Date Received: 02/13/96

Extraction: (SepF/Cont/Sonc) SONC

Date Extracted: 02/21/96

Concentrated Extract Volume: 5000(uL)

Date Analyzed: 03/08/96

Injection Volume: 1.0(uL)

Dilution Factor: 10.0

GPC Cleanup: (Y/N) Y pH: 6.5

Sulfur Cleanup: (Y/N) N

CONCENTRATION UNITS:

CAS NO.

COMPOUND

(ug/L or ug/Kg) UG/KG

Q

12674-11-2Aroclor-1016 11104-28-2Aroclor-1221 11141-16-5Aroclor-1232 53469-21-9Aroclor-1242 12672-29-6Aroclor-1248 11097-69-1Aroclor-1254	400 810 400 900 400 2100	U U CP U CP
11096-82-5Aroclor-1260	400	ับ

3SS3PDL

J Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Lab Code: IEA

Case No.: 1589-134

SDG No.: 02301

Matrix: (soil/water) SOIL

Lab Sample ID: 960230104DL

Sample wt/vol:

30.1 (g/mL) G

Lab File ID: P4030296 148.D

% Moisture: 18 decanted: (Y/N) N

Date Received: 02/13/96

Extraction: (SepF/Cont/Sonc) SONC

Date Extracted: 02/21/96

Concentrated Extract Volume:

Date Analyzed: 03/08/96

Injection Volume: 1.0(uL)

Dilution Factor: 100.0

GPC Cleanup: (Y/N) Y

pH: 6.5

5000(uL)

Sulfur Cleanup: (Y/N) N

CONCENTRATION UNITS:

CAS NO.

COMPOUND

(ug/L or ug/Kg) UG/KG

Q

12674-11-2Aroclor-1016	4000	ט
11104-28-2Aroclor-1221	8100	ט
11141-16-5Aroclor-1232	4000	ט
53469-21-9Aroclor-1242	700	JP
12672-29-6Aroclor-1248	4000	ט
11097-69-1Aroclor-1254	2200	JP
11096-82-5Aroclor-1260	4000	U
	1]

CLIENT SAMPLE NO.

3SS4

b Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Lab Code: IEA Case No.: 1589-134 SDG No.: 02301

Matrix: (soil/water) SOIL Lab Sample ID: 960230105

Sample wt/vol: 30.0 (g/mL) G Lab File ID: P4030296 153.D

% Moisture: 13 decanted: (Y/N) N Date Received: 02/13/96

Extraction: (SepF/Cont/Sonc) SONC Date Extracted:02/21/96

Concentrated Extract Volume: 5000(uL) Date Analyzed: 03/08/96

Injection Volume: 1.0(uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) Y pH: 7.7 Sulfur Cleanup: (Y/N) N

CONCENTRATION UNITS:

CAS NO. COMPOUND (ug/L or ug/Kg) UG/KG Q

12674-11-2----Aroclor-1016 38 U 11104-28-2----Aroclor-1221 77 U 11141-16-5----Aroclor-1232 U 38 53469-21-9----Aroclor-1242 1400 CP 12672-29-6-----Aroclor-1248 38 U 11097-69-1----Aroclor-1254 450 CP 11096-82-5----Aroclor-1260 38 U

CLIENT SAMPLE NO.

3SS4DL

Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Lab Code: IEA Case No.: 1589-134

SDG No.: 02301

Matrix: (soil/water) SOIL

Lab Sample ID: 960230105DL

Sample wt/vol:

30.0 (g/mL) G

Lab File ID: P4030296 149.D

% Moisture: 13

decanted: (Y/N) N

Date Received: 02/13/96

Extraction: (SepF/Cont/Sonc) SONC

Date Extracted: 02/21/96

Concentrated Extract Volume: 5000(uL)

Date Analyzed: 03/08/96

Injection Volume: 1.0(uL)

Dilution Factor: 10.0

GPC Cleanup: (Y/N) Y pH: 7.7

Sulfur Cleanup: (Y/N) N

CONCENTRATION UNITS:

CAS NO.

COMPOUND

(ug/L or ug/Kg) UG/KG

12674-11-2Aroclor-1016 11104-28-2Aroclor-1221 11141-16-5Aroclor-1232 53469-21-9Aroclor-1242 12672-29-6Aroclor-1248 11097-69-1Aroclor-1254 11096-82-5Aroclor-1260	380 770 380 1400 380 590 380	U U DP U DP
------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	------------------------------------------------	-------------------------

CLIENT SAMPLE NO.

3SS3PMS

SDG No.: 02301

Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Lab Code: IEA Case No.: 1589-134

Lab Sample ID: 960230104MS Matrix: (soil/water) SOIL

Lab File ID: P4030296 151.D Sample wt/vol: 30.1 (g/mL) G

% Moisture: 18 decanted: (Y/N) N Date Received: 02/13/96

Extraction: (SepF/Cont/Sonc) SONC Date Extracted: 02/21/96

Concentrated Extract Volume: 5000(uL) Date Analyzed: 03/08/96

Injection Volume: 1.0(uL) Dilution Factor: 10.0

GPC Cleanup: (Y/N) Y Sulfur Cleanup: (Y/N) N pH: 6.5

CONCENTRATION UNITS: CAS NO. COMPOUND (ug/L or ug/Kg) UG/KG Q

12674-11-2Aroclor-1016	400	ט
11104-28-2Aroclor-1221	810	ט
11141-16-5Aroclor-1232	400	U
53469-21-9Aroclor-1242	1300	P
12672-29-6Aroclor-1248	400	U
11097-69-1Aroclor-1254	3200	P
11096-82-5Aroclor-1260	1500	P

CLIENT SAMPLE NO.

3SS3PMSD

Q

) Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

CAS NO. COMPOUND

Lab Code: IEA Case No.: 1589-134 SDG No.: 02301

Matrix: (soil/water) SOIL Lab Sample ID: 960230104MSD

Sample wt/vol: 30.1 (g/mL) G Lab File ID: P4030296 152.D

% Moisture: 18 decanted: (Y/N) N Date Received: 02/13/96

Extraction: (SepF/Cont/Sonc) SONC Date Extracted:02/21/96

Concentrated Extract Volume: 5000(uL) Date Analyzed: 03/08/96

Injection Volume: 1.0(uL) Dilution Factor: 10.0

GPC Cleanup: (Y/N) Y pH: 6.5 Sulfur Cleanup: (Y/N) N

CONCENTRATION UNITS: (ug/L or ug/Kg) UG/KG

400	U
810	Ŭ
400	U
2000	P
400	U
4900	P
3200	P
	810 400 2000 400 4900

2F SOIL PESTICIDE SURROGATE RECOVERY

Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Lab Code: IEA Case No.: 1589-134 SDG No.: 02301

GC Column(1): DB-1701 ID: 0.53 (mm) GC Column(2): RTX-35 ID: 0.53 (mm)

	1 77 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7	1000		1505	15-25-	AMILES	LAMITER	1
	CLIENT	TCX 1	TCX 2	DCB 1	DCB 2	OTHER	OTHER	TOT
	SAMPLE NO.	%REC #	%REC #	%REC #	%REC #	(1)	(2)	OUT
	========	=====	======	=====	=====	=====	=====	===
01	3SS3P	29D	130D	G08	130D	l	i	0
02	3SS3PDL	OD	OD.	OD	OD.			01
03	3SS3PMS	42D	354D	332D	362D			0
04	3SS3PMSD	53D	164D	570D	186D			ol
05	3554	57*	1200*	570*	1400*	·		4
06	3SS4DL	51D	120D	159D	121D			o
07	PBLK06	46*	96	72	100			1
08	I DDI(OO		30	, 2	100			
09								
10								
11		·						
12				·				
12								
13							·	
14								
15								
16								
17		·]	·	
18								
19						·		
20								1
21								
22								
23								
24]						
25								
26								1
27								
28	·				·	j		
29								
30								
20		/			/	/	}	1

ADVISORY QC LIMITS

TCX = Tetrachloro-m-xylene (60-150)DCB = Decachlorobiphenyl (60-150)

Column to be used to flag recovery values
* Values outside of QC limits

D Sample diluted

SOIL PESTICIDE MATRIX SPIKE/MATRIX SPIKE DUPLICATE RECOVERY

Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Lab Code: IEA Case No.: 1589-134

SDG No.: 02301

Matrix Spike - Client Sample No.: 3SS3P

COMPOUND	SPIKE ADDED (ug/Kg)	SAMPLE CONCENTRATION (ug/Kg)	MS CONCENTRATION (ug/Kg)	MS % REC #	QC. LIMITS REC.
Aroclor-1260	400	0.0	150	38*	60-140

COMPOUND	SPIKE ADDED (ug/Kg)	MSD CONCENTRATION (ug/Kg)	MSD % REC #	% RPD #		IMITS REC.
Aroclor-1260	400	320	80	71*	40	60-140

Column to be used to flag recovery and RPD values with an asterisk

+	Valu	 oute	ah i	of i	റ്	limits

RPD: 1 out of 1 outside limits
Spike Recovery: 1 out of 2 outside limits

COMMENTS:	

4C PESTICIDE METHOD BLANK SUMMARY

CLIENT SAMPLE NO.

PBLK06

Name: INDUSTRIAL & ENVIRONMENTA Contract: SOW 1/91

Lab Code: IEA Case No.: 1589-134

SDG No.: 02301

Lab Sample ID: PBLK06

Lab File ID: P4030296 147.D

Matrix: (soil/water) SOIL

Extraction: (SepF, Cont/Sonc) SONC

Sulfur Cleanup: (Y/N) N

Date Extracted: 02/21/96

Date Analyzed (1): 03/08/96

Date Analyzed (2): 03/12/96

Time Analyzed (1): 1544

Time Analyzed (2): 2116

Instrument ID (1): HP5890P4

Instrument ID (2): HP5890P1

GC Column (1):DB-1701 ID: 0.53(mm) GC Column (2):RTX-35 ID: 0.53(mm)

THIS METHOD BLANK APPLIES TO THE FOLLOWING SAMPLES, MS AND MSD

	CLIENT	LAB	DATE	DATE
	SAMPLE NO.	SAMPLE ID	ANALYZED 1	ANALYZED 2
	******		******	******
01	3SS3P	960230104	03/08/96	03/10/96
02	3SS3PDL	960230104DL	03/08/96	03/10/96
03		960230104MS	03/08/96	03/10/96
C4	3SS3PMSD	960230104MSD	03/08/96	03/10/96
05	3554	960230105	03/08/96	03/10/96
06	3SS4DL	960230105DL	03/08/96	03/10/96
07				
08				
09				
10				
11]
12				
13				[
14				
15				
16				
17				
18				
19				
20				
21				
22				
24 25				
26			 	
20		l !		

COMMENTS:	

EPA SAMPLE NO. 149554-8.5/10.

Lab Name: IEA-CT Contract:

Lab Code: IEACT Case No.: 0219 SAS No.: SDG No.: Z0219

Matrix: (soil/water):SOIL Lab Sample ID: 0219001

Sample wt/vol: 30 (g/ml) G Lab File ID: B5213CLP326

% Moisture: 18 decanted: (Y/N)N Date Received: 02/16/96

Extraction: (SepF/Cont/Sonc) SONC Date Extracted: 02/16/96

Concentrated Extract Volume: 5000 (uL) Date Analyzed: 02/17/96

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N)Y pH: 6.7 Sulfur Cleanup: (Y/N)N

CAS NO. COMPOUND CONCENTRATION UNITS: Q (ug/L or ug/kg) <u>UG/kG</u>

12674-11-2 | Aroclor-1016 40 11104-28-2 | Aroclor-1221 82 Ū 11141-16-5 | Aroclor-1232 40 IJ 53469-21-9 Aroclor-1242 40 Ū 12672-29-6 Aroclor-1248 40 T 11097-69-1 Aroclor-1254 40 Ū Aroclor-1260 11096-82-5 40

EPA SAMPLE NO. 149557-16/15

Lab Name: IEA-CT Contract: Lab Code: IEACT Case No.: 0219 SAS No.: SDG No.: 20219 Lab Sample ID: 0219002001 Matrix: (soil/water):SOIL Sample wt/vol: 30 (g/ml) G Lab File ID: B5213CLP327 % Moisture: 20 decanted: (Y/N)N Date Received: 02/16/96 Extraction: (SepF/Cont/Sonc) SONC Date Extracted: 02/16/96 Concentrated Extract Volume: 5000 (uL) Date Analyzed: 02/17/96 Injection Volume: 1.0 (uL) Dilution Factor: 1.0

CAS NO. COMPOUND

GPC Cleanup: (Y/N)Y pH:8.3

CONCENTRATION UNITS: 0 (ug/L or ug/Kg) UG/KG

Sulfur Cleanup: (Y/N)N

	Aroclor-1016	41	Ü
	Aroclor-1221	84	Ū
	Aroclor-1232	41	U
	Aroclor-1242	41	U
	Aroclor-1248	41	U
	Aroclor-1254	41	U
11096-82-5	Aroclor-1260	41	U

EPA SAMPLE NO. 150**5**\$3-6/8

Lab Name: IEA-CT Contr	act:
Lab Code: <u>IEACT</u> Case No.: <u>0219</u> SAS No.:	SDG No.: <u>Z0219</u>
Matrix: (soil/water): <u>SOIL</u>	Lab Sample ID: <u>0219003</u>
Sample wt/vol: 30 (g/ml) G	Lab File ID: <u>B5213CLP328</u>
% Moisture: <u>19</u> decanted: (Y/N) <u>N</u>	Date Received: 02/16/96
Extraction: (SepF/Cont/Sonc) <u>SONC</u>	Date Extracted: 02/16/96
Concentrated Extract Volume: 5000 (uL)	Date Analyzed: <u>02/17/96</u>
Injection Volume: 1.0 (uL)	Dilution Factor: 1.0

GPC Cleanup: (Y/N)Y pH:6.9

Sulfur Cleanup: (Y/N)N

CAS NO. COMPOUND

CONCENTRATION UNITS: Q (ug/L or ug/Kg) UG/KG

	Aroclor-1016	41	U
	Aroclor-1221	83	Ü
	Aroclor-1232	41	U
	Aroclor-1242	41	Ū
	Aroclor-1248	500	
11097-69-1	Aroclor-1254	150	
11096-82-5	Aroclor-1260	49.	

EPA SAMPLE NO. 151553-5/7

Lab Name: <u>IEA-CT</u> Cor	tract:
Lab Code: <u>IEACT</u> Case No.: <u>0219</u> SAS No.	o.: SDG No.: <u>Z0219</u>
Matrix: (soil/water):SOIL	Lab Sample ID: 0219004
Sample wt/vol: 30 (g/ml) G	Lab File ID: <u>B5213CLP329</u>
% Moisture: 18 decanted: (Y/N)N	Date Received: 02/16/96
Extraction: (SepF/Cont/Sonc) SONC	Date Extracted: 02/16/96
Concentrated Extract Volume: 5000 (uL)	Date Analyzed: 02/17/96
Injection Volume: 1.0 (uL)	Dilution Factor: 1.0
GPC Cleanup: (Y/N)Y pH:6.6	Sulfur Cleanup: $(Y/N)N$
CAS NO. COMPOUND	CONCENTRATION UNITS: Q (ug/L or ug/kg) <u>UG/kG</u>
12674-11-2 Aroclor-1016	40 0
11104-28-2 Aroclor-1221	82 Ü
11141-16-5 Aroclor-1232	40 U
53469-21-9 Aroclor-1242	40 U
12672-29-6 Aroclor-1248	40 U

11097-69-1 Aroclor-1254 11096-82-5 Aroclor-1260

40

40

Ū

Ū

EPA SAMPLE NO. 151555-9/11

Lab Name: <u>IEA-CT</u> Contr	act:
Lab Code: <u>IEACT</u> Case No.: <u>0219</u> SAS No.:	SDG No.: <u>Z0219</u>
Matrix: (soil/water):SOIL	Lab Sample ID: 0219005
Sample wt/vol: 30 (g/ml) G	Lab File ID: <u>B5213CLP330</u>
% Moisture: 15 decanted: $(Y/N)N$	Date Received: <u>02/16/96</u>
Extraction: (SepF/Cont/Sonc) <u>SONC</u>	Date Extracted: 02/16/96
Concentrated Extract Volume: 5000 (uL)	Date Analyzed: <u>02/17/96</u>
Injection Volume: 1.0 (uL)	Dilution Factor: 1.0
GPC Cleanup: (Y/N)Y pH:7	Sulfur Cleanup: (Y/N)N

CAS NO. COMPOUND CONCENTRATION UNITS: Q (ug/L or ug/Kg) UG/KG

	Aroclor-1016		ן ט
	Aroclor-1221	79	Ū
	Aroclor-1232	3.9	Ū
	Aroclor-1242	39	U
	Aroclor-1248	39	Ū
	Aroclor-1254	39	Û
11096-82-5	Aroclor-1260	39	U

CCSS

1D PESTICIDE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO. 152**55**4-7/9

Lab Name: <u>IEA-CT</u> Contract:

Lab Code: IEACT Case No.: 0219 SAS No.: SDG No.: Z0219

Matrix: (soil/water): SOIL Lab Sample ID: 0219006

Sample wt/vol: 30 (g/ml) G Lab File ID: B5213CLP331

% Moisture: 19 decanted: (Y/N)N Date Received: 02/16/96

Extraction: (SepF/Cont/Sonc) SONC Date Extracted: 02/16/96

Concentrated Extract Volume: 5000 (uL) Date Analyzed: 02/17/96

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N)Y pH:6.9 Sulfur Cleanup: (Y/N)N

CAS NO. COMPOUND CONCENTRATION UNITS: (ug/L or ug/Kg) UG/KG

12674-11-2 | Aroclor-1016 41 Ū 83 11104-28-2 | Aroclor-1221 Ū 11141-16-5 Aroclor-123? 41 ับ 53469-21-9 | Aroclor-1242 $\overline{\sigma}$ 41 12672-29-6 | Aroclor-1248 Ū 41 11097-69-1 Aroclor-1254 41 Ū 11096-82-5 | Aroclor-1260 υ

EPA SAMPLE NO. 152**SS**5-9/11

Lab Name: <u>IEA-CT</u> Contr	act:
Lab Code: <u>IEACT</u> Case No.: <u>0219</u> SAS No.:	
Matrix: (soil/water):SOIL	Lab Sample ID: 0219007 (0)
Sample wt/vol: 30 (g/ml) G	Lab File ID: B5213CLP332
% Moisture: 19 decanted: (Y/N)N	Date Received: <u>02/16/96</u>
Extraction: (SepF/Cont/Sonc) <u>SONC</u>	Date Extracted: 02/16/96
Concentrated Extract Volume: 5000 (uL)	Date Analyzed: 02/17/96
Injection Volume: 1.0 (uL)	Dilution Factor: 1.0

GPC Cleanup: (Y/N)Y pH:7.2

Sulfur Cleanup: (Y/N)N_

CAS NO. COMPOUND

CONCENTRATION UNITS: Q (ug/L or ug/Kg) UG/KG

	Aroclor-1016	41	Ū
	Aroclor-1221	83	Ū
11141-16-5	Aroclor-1232	41	Ū
53469-21-9	Aroclor-1242	41	U
	Aroclor-1248	41	Ū
	Aroclor-1254	41	Ū
11096-82-5	Aroclor-1260	41	Ū

EPA	SAMPLE	$\mathbb{C}N$
PB-	K86	

	Lacc:
Lab Code: <u>IEACT</u> Case No.: <u>0219</u> SAS No.:	SDG No.: 20219 (213.
Matrix: (soil/water):SOIL	Lab Sample ID: <u>021696-B02</u>
Sample wt/vol: 30 (g/ml) G	Lab File ID: <u>B5213CLP325</u>
% Moisture: 0 decanted: (Y/N)N	Date Received:
Extraction: (SepF/Cont/Sonc) <u>SONC</u>	Date Extracted: 02/16/96
Concentrated Extract Volume: 5000 (uL)	Date Analyzed: 02/17/96
Injection Volume: 1.0 (uL)	Dilution Factor: 1.0
GPC Cleanup: (Y/N)Y pH:	Sulfur Cleanup: $(Y/N)N$
	CONCENTRATION UNITS: Q (ug/L or ug/Kg) <u>UG/KG</u>
12674-11-2 Aroclor-1016	33 U

12674-11-2	Aroclor-1016	·	33	TT
	Aroclor-1221		67	-
	Aroclor-1232		33	Ū
	Aroclor-1242		33	ប
	Aroclor-1248		33	Ū
	Aroclor-1254		33	Ū
11096-82-5	Aroclor-1260		33	Ū

EPA SAMPLE NO. 149554-8.5/10

_____ Contract: ____ Lab Name: <u>IEA-CT</u>

Lab Code: IEACT Case No.: 0219 SAS No.: ____ SDG No.: Z0219

Matrix: (soil/water):SOIL Lab Sample ID: 0219001MS

Sample wt/vol: 30 (g/m1) G Lab File ID: B5213CLP333

% Moisture: 18 decanted: (Y/N)N Date Received: 02/16/96

Extraction: (SepF/Cont/Sonc) SONC Date Extracted: 02/16/96

Concentrated Extract Volume: 5000 (uL) Date Analyzed: 02/17/96

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N)Y pH:6.7 Sulfur Cleanup: (Y/N)N

CAS NO. COMPOUND CONCENTRATION UNITS: (ug/L or ug/Kg) <u>UG/KG</u>

12674-11-2	2-0010- 1016	10	79
		₩.0	1 0
11104-28-2		82	Ŭ
11141-16-5		40	U
53469-21-9		480	
12672-29-6		40	Ū
11097-69-1		40	U
11096-82-5	Aroclor-1260	380	P

EPA SAMPLE NO. 149**55**4-8.5/10.

Lab Name: <u>IEA-CT</u> _____Contract: _____

Lab Code: <u>IEACT</u> Case No.: <u>0219</u> SAS No.; ____ SDG Nc.: <u>Z0219</u>

Lab Sample ID: 0219001MSDA249 Matrix: (soil/water):<u>SOIL</u>

Sample wt/vol: 30 (g/ml) GLab File ID: B5213CLP334

% Moisture: 18 ___ decanted: (Y/N)N_ Date Received: 02/16/96

Extraction: (SepF/Cont/Sonc) <u>SONC</u> Date Extracted: 02/16/96

Concentrated Extract Volume: 5000 (uL) Date Analyzed: 02/17/96

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N)Y pH:6.7 Sulfur Cleanup: (Y/N) N

CAS NO. COMPOUND CONCENTRATION UNITS: (ug/L or ug/Kg) <u>UG/KG</u>

12674-11-2 Aroclor-1016 11104-28-2 Aroclor-1221 11141-16-5 Aroclor-1232 53469-21-9 Aroclor-1242 12672-29-6 Aroclor-1248 11097-69-1 Aroclor-1254 Ū 82 U 40 U 460 40 Ū 40 Ū 11096-82-5 | Aroclor-1260 <u> 320</u>

2F SOIL PESTICIDE SURROGATE RECOVERY

al	Name:	IEA-CT			Contract	<u> </u>	
ьab	Code:	<u>IEACT</u>	Case	No.: <u>0219</u>	SAS No.:	SDG No.: 2	
GC	Column	(1): <u>DB</u>	-1701	ID: <u>0.53</u> (m	m) GC Colum	n(2): <u>RTX-35</u>	ID: <u>0.53</u> (mm)

EPA		TCX	1 TCX	2 DCB	1 DC:	3 2		OTHER	TOT
SAMPLE	NO.	%REC	# %REC	# %REC	# %R	EC #	(1)	(2)	OUT
PBLK86		79				118			0
149554-8	3.5/10	. 10			22	103			1 0
149557-1	6/18	95				103			0
150553-6		128	8			119			0
151553-5		101	11			114			0
151555-9	7	90	6		9	701*			1
152554 - 7	1/9	96	10			118			0
152555-9	/11	86	9			131			0
149554-8	.5/10	.MS	106	109	136		43		ļ
149554-8	1.5/10	. MSD	99	102	124		119	·	<u> </u>
								<u> </u>	ļ
			_		-				
			_						-
								ļ	
								 	
· · · · · · · · · · · · · · · · · · ·									
<i></i>									1
			 					 	ļ
								 	
								ļ	
								<u> </u>	ļ
								ļ	
				-	-			ļ	
								ļ	L
<u> </u>								ļ	
		···					~	 	
			J						
			L						

ADVISORY QC LIMITS (60-150)

TCX = Tetrachloro-m-xylene DCB = Decachlorobiphenyl

(60-150)

Column to be used to flag recovery values
* Values outside of QC limits
D Surrogate diluted out

page <u>1</u> of <u>1</u>.

FORM II PEST-1

MONTGOMERY WATSON	CHAIN OF C	JSTODY	' RECORI	D	SPECIAL INSTRUCTION PECFA WI LUST ACT 307 REPORT DRY W	IS: 	AYS
CITY: STATE:	17.0075 11.4 SY - 5/2-10/2 S7 - 16.15' S3 - 6-8' S3 - 5-7 S5- 5-11 S4 - 7-9 S5 - 9-11	TOTALI TOTALINE TOTAL		9 9 9 9	REMARKS 29316 29316 29319 2932 29821 23822	MATRIX	JSE ONLY LAB NO.
SPECIAL INSTRUCTIONS: RULL + GIRMINGUAD - 2 DA 2 DAY TAT (OF 3DAY if 3 Lay is A SIGNATURE, 1)	MONDAY IS	INTACT [ONICE TEMP		Phile 768.	. 191.5620	
RELINQUISHED BY:	DAVISTIC CZY		Mongonay	COMPANY VARCON	Truley 1690	DATI	TIME
RECEIVED BY:							
RELINQUISHED BY:				·			
RECEIVED BY:							
C-O-C No. 010574	real His Golden	8.2 5×6			NAME OF COURIER:	Z 10) (A	

83

F

)

F

GEOTECHNICAL LABORATORY RESULTS


CGC, Inc.) 11.1) Project 1)2. 4077.0075

Job No.___ Joh Name: AS-Bactor Was Alarman Date 3 / 4/196

J scation: DC ff th Indian Sheet 3 of 3

Unit Price Hourly Cost Sheet in 251 to 212 Storage Attn: VRusque + + 2 Testing Applicability____ (Special Lab Instructions or Notes) Type of Sample: These samples are CONTAMINATED * X * Jar Sample Use Precautions * B * Bag Sample * ST * Shelby Tube " P " Pail Color Laboratory Tests Lab Pan Boring Semple Location Туре Layer W/S Ц Depth NM Area 52 23-25 GY ACS 5B151 GY ST SB 212 ACS ALS SB 206 19-21 38 ACS 158109 (Please use a pencil, write legibly and space out the entries) * Primary Sample Designation for Reporting

Geotechnical Laboratory Work Set-Up Sheet



Date: March 18, 1996

FALLING HEAD PERMEABILITY TEST

CGC, Inc., 1409 Emil Street, Madison, WI (608) 257-6377

PROJECT: ACS - Barrier Wall Alignment, Job No. 4077.0075

LOCATION: Griffith, Indiana

SAMPLE: Shelby Tube: ACS - SB 109

DEPTH (ft) 19.0 to 21.0

SOIL DESCRIPTION Gray Lean CLAY, Little Sand, Trace Gravel (CL)

	<u>INITIAL</u>	<u>FINAL</u>
\smile		
SAMPLE DIAMETER (CM)	7.34	7.34
SAMPLE LENGTH, L (cm)	20.60	20.60
MOISTURE CONTENT, %	16.4	16.6
DRY DENSITY (lb/cu ft)	115.7	115.7

RUN	COEFFICIENT OF PERMEABILITY, k (cm/s∞)
1	2.7 x 10- ⁴
2	2.4 x 10 ⁻⁴
3	2.2 x 10 ⁻⁸
4	2.0 x 10 ⁻⁴
5	2.1 x 10 ⁻⁸
6	1.7 x 10 ⁴
7	1.8 x 10 ⁻⁸
8	1.7 x 10 ⁴
9	1.7 x 10 ⁻⁴

AVERAGE COEFFICIENT OF PERMEABILITY = 1.7 x 10⁴ cm/sec (Based on run numbers 7 through 9)

2.3aL ho FORMULA: k = ---- log10 ---,

h1


Where a = cross-sectional area of standpipe,


t = time for water level to fall from initial height, ho, to final height, h1

(All other terms are defined above)

REMARKS: This permeability test was performed on a relatively undisturbed 3-inch diameter nelby tube sample at it's natural moisture content.

CHECKED BY: DATE: $\frac{3|18|96}{4}$ APPROVED BY: $\frac{100}{100}$ DATE: $\frac{3|19|96}{4}$





Date: March 18, 1996

FALLING HEAD PERMEABILITY TEST

JGC, Inc., 1409 Emil Street, Madison, WI (608) 257-6377

PROJECT:

ACS - Barrier Wall Alignment, Job No. 4077.0075

LOCATION:

Griffith, Indiana

SAMPLE:

Shelby Tube: ACS - SB 206

DEPTH (ft)

25.5 to 27.5

SOIL DESCRIPTION Gray Lean CLAY, Some Sand, Trace Gravel (CL)

	INITIAL	<u>FINAL</u>
→MPLE DIAMETER (CM)	7.34	7.34
SAMPLE LENGTH, L (cm)	22.91	22.91
MOISTURE CONTENT, %	18.8	19.1
DRY DENSITY (lb/cu ft)	110.0	110.0

RUN	COEFFICIENT OF PERMEABILITY, k (cm/sec)
1	3.3 x 10 ⁻⁸
2	2.5 x 10 ⁻⁸
3	2.6 x 10 ⁻⁸
4	2.5 x 10 ⁻⁸
5	2.2 x 10 ⁻⁴
6	2.2 x 10 ⁴
7	2.0 x 10 ⁻⁴
8	2.1 x 10 ⁴
9	2.0 x 10 ⁻⁴

AVERAGE COEFFICIENT OF PERMEABILITY = 2.0×10^{-8} cm/sec (Based on run numbers 7 through 9)


2.3aL ho FORMULA: k = ---- log10


At

Where a = cross-sectional area of standpipe,

t = time for water level to fall from initial height, ho, to final height, h1 (All other terms are defined above)

REMARKS: This permeability test was performed on a relatively undisturbed 3-inch diameter elby tube sample at it's natural moisture content.





Date: March_18, 1996

FALLING HEAD PERMEABILITY TEST

GC, Inc., 1409 Emil Street, Madison, WI (608) 257-6377

PROJECT:

ACS - Barrier Wall Alignment, Job No. 4077.0075

LOCATION:

Griffith, Indiana

SAMPLE:

Shelby Tube: ACS - SB 151

DEPTH (ft)

23.0 to 25.0

SOIL DESCRIPTION Gray Lean CLAY, Some Sand, Trace Gravel (CL)

	INITIAL	FINAL
\MPLE DIAMETER (CM)	7.34	7.34
SAMPLE LENGTH, L (cm)	21.77	21.77
MOISTURE CONTENT, %	18.0	18.1
DRY DENSITY (lb/cu ft)	108.2	108.2

RUN	COEFFICIENT OF PERMEABILITY, k (cm/sec)
1	3.4 x 10 ⁻⁸
2	3.0 x 10 ⁻⁸
3	2.6 x 10 ⁻⁸
4	2.3 x 10 ⁻⁸
5	1.8 x 10 ⁻⁸
6	1.8 x 10 ⁻⁸
7	1.8 x 10 ⁻⁸
8	1.8 x 10 ⁻⁸
9	1.8 x 10 ⁻⁸

AVERAGE COEFFICIENT OF PERMEABILITY = 1.8 x 10⁻⁸ cm/sec (Based on run numbers 7 through 9)

2.3aL FORMULA: k = --- log10


Where a = cross-sectional area of standpipe,


t = time for water level to fall from initial height, ho, to final height, h1

(All other terms are defined above)

REMARKS: This permeability test was performed on a relatively undisturbed 3-inch diameter elby tube sample at it's natural moisture content.

DATE: 3/18/96 APPROVED BY: MNS DATE: 3/19/96





Date: March 18, 1996

FALLING HEAD PERMEABILITY TEST

JC, Inc., 1409 Emil Street, Madison, WI (608) 257-6377

PROJECT:

ACS - Barrier Wall Alignment, Job No. 4077.0075

LOCATION:

Griffith, Indiana

SAMPLE:

Shelby Tube: ACS - SB 212

DEPTH (ft)

29.0 to 31.0

SOIL DESCRIPTION Gray Lean CLAY, Little Sand, Trace Gravel (CL)

	INITIAL	<u>FINAL</u>	
°AMPLE DIAMETER (CM)	7.34	7.34	
→MPLE LENGTH, L (cm)	20.83	20.83	
MOISTURE CONTENT, %	18.5	18.9	
DRY DENSITY (lb/cu ft)	107.6	107.6	

RUN	COEFFICIENT OF PERMEABILITY, k (cm/sec)
1	3.6 x 10 ⁻⁸
2	2.9 x 10 ⁻⁸
3	2.7 x 10 ⁻⁸
4	2.5 x 10 ⁻⁸
5	2.4 x 10 ⁻⁸
6	2.3 x 10 ⁻⁸
7	2.2 x 10 ⁻⁸
8	2.5 x 10 ⁻⁸
9	2.4 x 10 ⁻⁸

AVERAGE COEFFICIENT OF PERMEABILITY = 2.4×10^{-8} cm/sec (Based on run numbers 7 through 9)

2.3aL FORMULA: $k = --- \log 10 ---$,

Where a = cross-sectional area of standpipe,

t = time for water level to fall from initial height, ho, to final height, h1

At (All other terms are defined above)

REMARKS: This permeability test was performed on a relatively undisturbed 3-inch diameter

lby tube sample at it's natural moisture content.

DATE: 3 18 96 APPROVED BY: MAS DATE: 3

